Pre-Commercial Demonstration of Cost-Effective Advanced HVAC Controls

2014 Building Technologies Office Peer Review





Hayden Reeve, reevehm@utrc.utc.com United Technologies Research Center

Project Summary

<u>Timeline</u>:

Start date: Feb 1, 2011

Planned end date: April 30, 2015

Key Milestones

- 1. Model eval. of opt. control benefits (01/13)
- 2. Demonstration of opt. control in two buildings (9/13 and 1/14)
- Demonstration of scalable deployment in two buildings (2/15)

Budget:

Total DOE \$ to date: \$0.86M (through 3/2014)

Total Cost Share \$ to date: \$0.43M

Total future DOE \$: \$0.45M (4/2014-3/2015)

Total future Cost Share \$: \$0.11M

Target Market/Audience:

Key Partners:

	Penn State	Virginia Tech				
	Purdue	UTC				
)						

Project Goal:

Demonstrate cost-effective and scalable deployment of optimal controls that achieve >20% HVAC energy reduction versus state-ofthe-art building automation systems.

This technology targets building automation systems for medium-size buildings with central HVAC systems. Medium and large market segments account for ~35% of commercial building HVAC energy use (1.9 Quads).



Problem Statement: Optimal control coordination of HVAC equipment can reduce energy by >20% over current building automation systems (BAS) but is not widely deployed due to **challenges with complexity, scalability, and deployment.**

Target Market and Audience: This technology targets building automation systems (BAS) for medium buildings with central HVAC systems. These systems account for ~35% of commercial building HVAC energy use (1.9 Quads).

Impact of Project: Provide a proof-point of commercial viability through demonstration of **cost-effective deployment** of optimal building controls:


- Near-term: successful demonstration of scalable and cost effective (<3 year payback) optimal controls that reduces HVAC energy usage by >20% over current BAS control
- 2. Intermediate-term: accelerated commercialization of technology
- 3. Long-term: Wide-spread scalable deployment of adaptive optimal controls that achieve >20% HVAC energy reduction.



Approach: Demonstrate benefits of optimal HVAC equipment operation in real buildings versus current BAS control.

Key Issues: Cost-effective, scalable deployment requires adaptive optimal control approach compatible with current BAS architectures and the skillset of field personnel.

Distinctive Characteristics: Requires no building specific models, no manual calibration, and uses existing BAS hardware and sensors. Can be offered as retro-fit overlay to existing BAS.






Energy Efficiency & Renewable Energy

Results: Building 101 – The Navy Yard, Philadelphia

Predicted Energy Savings




Model-based evaluation enables investigation of season, climate zone, and building type impact on energy savings.

~20% HVAC energy reduction predicted for Bldg. 101



Results: Building 101 – The Navy Yard, Philadelphia

Building Demonstration Results




Real-world demonstration validates approach and provides proof-point to stakeholders.

>20% HVAC energy reduction demonstrated in Bldg. 101



Scalable Deployment: Distributed Opt. Approach



- <u>Scalable</u>: Approach mirrors current control architecture and hardware structure
- <u>Deployable</u>: Adaptive selfdeployed online estimation models eliminate the need for manual model calibration and (re)tuning



Progress and Accomplishments

Lessons Learned:

- 1) <u>Focus on installation cost and complexity</u> should be commensurate with focus on energy savings. Leveraging lessons learned and conclusions from previous DOE and DOD efforts.
- 2) Demonstrating benefits in field requires careful back-to-back comparison (accounting for weather, occupancy etc.)
- 3) Healthy building equipment is pre-requisite for optimal operation.

Accomplishments: Demonstrated >20% HVAC energy reduction versus current BAS control while reducing discomfort and equipment cycling.

Market Impact: Demonstrated >20% HVAC energy reduction beyond current BAS control (with existing hardware and sensors) consistent with project goals. Will demonstrate scalable approach can meet deployment requirements:

- 1. Define requirements for commercially viable deployment
- 2. Demonstrate that adaptive optimal approaches can meet these requirements

⁸Awards/Recognition: None



Energy Efficiency & Renewable Energy

Project Integration and Collaboration

Project Integration: Engaged industry (Automated Logic Corporation) and academia (VT, Purdue, etc) to review technical approach and market requirements.

Partners, Subcontractors, and Collaborators: This work is undertaken as part of the Penn State Consortium for Building Energy Innovation (CBEI), formerly the Energy Efficient Building Hub. Overall controls team under this consortium includes Penn State (Stephen Treado), Purdue (Jim Braun), and VT (Eugene Cliff).

Communications: Work profiled at DOE Controls Workshop (2013, Portland), International High Performance Buildings Conference (2013-2014, Purdue), Intelligent Buildings Operations Workshop (2013, UC-Boulder), and Engineered Systems HPB Conference (2012, VA).



Next Steps and Future Plans: Demonstrate scalable installation of optimal controls in two buildings by February 2015:

- Document installation effort and resulting performance at Bldg. 101 (7/2014)
- 2. Go/No-Go: Installation effort demonstrates path to meet commercialization requirements (10/2014)
- 3. Implement diagnostics at 2nd demo site (Swope) to ensure system health (10/2014)
- 4. Document installation effort and resulting benefits of optimal controls at Swope (01/2015)



Bldg. 101: Philadelphia Navy Yard



Swope School of Music, West Chester, PA
U.S. DEPARTMENT OF
ENERGY
Energy Efficiency &
Renewable Energy

REFERENCE SLIDES



Energy Efficiency & Renewable Energy Project Budget: Annually funded as part of CBEI. Total DOE budget \$1.32M.
Variances: No project budget variances to date. 2013 demonstration plan modified to address building HVAC equipment failures (DX replacement) and Swope building demonstration delay.
Cost to Date: \$860K (65%) of DOE funds expended to date
Additional Funding: Cost share (UTC): \$430K to date; additional \$112K planned.

Budget History									
02/2011 – FY2013 (past)			.014 rent)	FY2015 – 04/2015 (planned)					
DOE	Cost-share	DOE	Cost-share	DOE	Cost-share				
\$756K	\$378K	\$553K	\$164K	-	-				



Project Plan and Schedule

- 2013 demonstration plans redirected due to building equipment failures. Swope demonstration to be completed in 2014.
- Budget Period 4 effort to start 05/2014.
- Go/No-Go: Show path to scalable and cost effective deployment (10/2014)

Project Start: Feb, 2011		Completed Work										
Projected End: April, 2015		Active Task (in progress work)										
		 Milestone/Deliverable (Originally Planned) 										
		Milestone/Deliverable (Actual)										
		FY2013			FY2014			FY2015				
Task	Q1 (Oct-Dec)	Q2 (Jan-Mar)	Q3 (Apr-Jun)	Q4 (Jul-Sep)	Q1 (Oct-Dec)	Q2 (Jan-Mar)	Q3 (Apr-Jun)	Q4 (Jul-Sep)	Q1 (Oct-Dec)	Q2 (Jan-Mar)	Q3 (Apr-Jun)	Q4 (Jul-Sep)
Past Work												
Model Evaluation of Opt. Controls for Bldg 101		•										
Demo Opt. Controls in Bldg 101					Þ							
Demo Opt. Controls in Swope SOM												
Current/Future Work												
Demo scalable install of opt controls at Bldg 101								•				
Demo scalable install of diagnostics at Swope									♦			
G/NG: Effort to install capability demonstrates												
path to meet commercialization requirements												
Demo scalable install of opt controls at Swope										•		
Evaluate energy benefits, installation cost, ROI												