

# 2009 DOE Annual Merit Review

## Hydrogen Vehicle and Infrastructure

### Demonstration and Validation

*Rosalind (Roz) B. Sell*  
*General Motors Corporation*  
*May 20, 2009*



Project ID #: tv\_05\_sell

# Overview

## Timeline

- Project Start = 10/1/04
- Project End = 9/30/09
- Project is 90% complete

## Budget

- \$88.0 M Total Project
  - \$44.0 M DOE share
  - \$44.0 M GM share
- FY08 Funding \$6.0 M
- FY09 Funding TBD

## Barriers

### - Targets

- Vehicles
  - Vehicle range and fuel cell (FC) durability
- Hydrogen Fueling Infrastructure
  - \$H2/gge
- Maintenance and Training Facilities

## Partners

- Shell Hydrogen, LLC – hydrogen fueling
- U.S. Army Fort Belvoir, VA – maintenance facilities
- Quantum Technologies, Inc. – maintenance facilities
- Viewpoint Systems – data acquisition
- NextEnergy – Codes and Standards

## Phase 2 – vehicle operators

### • **Project Driveway customers and drivers**

#### Phase 1 – vehicle operators

- U.S. Environmental Protection Agency
- State of Virginia Department of Environmental Quality
- U.S. Postal Service
- D.C. Department of Transportation

# Objectives

## Program Objective

- General Motors and energy partner Shell Hydrogen are deploying a system of hydrogen fuel cell electric vehicles integrated with a hydrogen fueling infrastructure to operate under real world conditions
  - Demonstrate progressive generations of fuel cell system technology
  - Demonstrate multiple approaches to hydrogen generation and delivery for vehicle fueling
  - Collect and report operating data

## Past Year Objectives – Execute next generation of fuel cell technology

- Obtain vehicle operators
- Collect, analyze, report data from program vehicles and fueling locations
- Construct hydrogen fueling stations in NYC metropolitan area and southern California
- Operate maintenance and training facilities in Project Driveway locations
- Complete permitting databases and continue data population
- Meet all Project Deliverables



# Approach

## Demonstrate fuel cell electric vehicles

- Deploy total of 50 fuel cell electric vehicles (FCEVs) in various terrains, driving conditions, and climates including cold weather
- Demonstrate two generations of fuel cell technology

## Establish retail-like hydrogen stations for public fueling

- Install total of five fueling stations on East and West coasts
- Explore hydrogen generation/delivery options such as electrolysis

## Set up maintenance and service operations in support of FCEVs

- Train personnel in maintenance, fueling, technical support, safety

## Generate and report data required under the Program

- Capture vehicle on-road and dynamometer test data
- Capture hydrogen infrastructure production/fueling data

## Document Codes and Standards learnings

- NextEnergy to develop Codes and Standards permitting templates and database of permitting experiences





# Project Driveway

First meaningful and largest market test of fuel cell electric vehicles

- Over 100 Chevrolet Equinox Fuel Cell Electric vehicles
- Launched in late 2007 continuing through 2010
- Markets with diverse climates and conditions:
  - California (LA, Sacramento)
  - Washington, D.C.
  - Greater New York City metropolitan area



Comprehensive feedback on all elements of customer experience and vehicle performance to guide future FCEV and infrastructure development

## Drivers

- Businesses, government
- General public - hand raiser process on Chevrolet.com
- Celebrity influencers, policymakers and media

# Project Driveway

- Over 80,000 people applied on Chevrolet.com
- 2,000+ members in Project Driveway blog community
- Exceeded 500,000 miles in customers' hands
- More than 7,200 fills at fueling stations
- Over 55,000 people experienced the vehicle at events
- More than 1,200 first responders trained in 8 cities
- 100s of stories in print, broadcast and digital media



# Equinox Fuel Cell Driver Feedback

## Top Positive Comments

- The customer support – driver relationship management
- The vehicle performance – quiet, smooth and powerful
- Fuel economy and range – better than expected
- Visibility of the vehicle – drivers like to be approached and talk about the car

## Top Constructive Comments

- Hydrogen fuel availability and the fueling process
- Brake feel, response and effort



# Chevrolet Equinox Fuel Cell Electric Vehicle

## Performance

- Range 168 miles 2008 EPA adjusted
  - Fuel capacity of 4.2 kg at 700 bar
- Acceleration 0-60 mph in 12 seconds
- Top speed 100 mph
- Expected to meet all applicable FMVSS
- Freeze durable over the vehicle life



## Content

- Visibly distinctive styling/graphics
- 17 inch aluminum wheels
- 2 front bucket seats (heated) and 2-passenger rear bench
- Navigation radio with fuel cell graphic energy display
- OnStar
- Driver, passenger and roof rail air bags
- ABS, traction control and stability control
- Front wheel drive
- Regenerative braking
- Single speed electric motor traction system

# Managing the Customer Experience

## Driver Relationship Managers (DRMs)

- Single point of contact 24/7
- Provides driver education and training
- Keeps drivers informed on any program updates

## All vehicles equipped with OnStar

- Provides safety and security for drivers
- Full concierge service: turn-by-turn navigation, hands-free calling, XM radio, fuel station locations





# Project Driveway



... in her own words

# Technical Accomplishments

## Eastern Region



Washington, D.C.

# Technical Accomplishments

## Eastern Region

### Vehicles – Phase 2

- 19 Chevrolet Equinox FCEVs demonstrating GM's 4<sup>th</sup> generation of fuel cell technology have been deployed in Washington, D.C., and NYC metro area
  - Cold weather testing in New York
- Vehicles collect data according to NREL Data Reporting Templates and fuel at Shell Hydrogen and GM facilities

### Maintenance and Training Facilities

- Ongoing maintenance and training activities at Ardsley, NY and Fort Belvoir, VA facilities



**Fort Belvoir, VA**






**Ardsley, NY**



# Technical Accomplishments

## Eastern Region Hydrogen Fueling Infrastructure

Station	Location	350 bar	700 bar	Generation/Delivery	Comments
<b>GM Maintenance &amp; Training Center</b> 	Ardsey, NY	N/A	3/08	Delivered compressed gas	450+ First Responders trained Infrared capable Can fill 3 FCEVs back-to-back 5 min each, 7-10 per day 1 <sup>st</sup> U.S. station tested for H2 quality at 700 bar
<b>Shell Hydrogen City of White Plains</b> 	White Plains, NY	9/07	3/08	Onsite electrolysis	350 bar & 700 bar offline 8/08 because of fire Incident investigation completed 12/08 with DOE participation 350 bar expected online 3/09 700 bar expected online Q309
<b>Shell Hydrogen Benning Rd.</b> 	Washington, D.C.	11/04	6/08	Delivered liquid	700 bar offline 8/08 expected online 3/09 400+ First Responders trained Gaseous fueling accommodating all vehicle manufacturers

– JFK Airport and Bronx stations are currently under construction; expected to be operational mid 2009

# NY First-Term Congressman Eric Massa

## Corning, NY to Washington, D.C.

Corning, NY Media Launch



Benning Road Fueling



290 miles



Advocate for the technology



Arrives at Swearing-In Ceremony





# Technical Accomplishments

## Western Region



Irvine, California

# Technical Accomplishments

## Western Region

### Vehicles – Phase 2

- 23 Chevrolet Equinox FCEVs demonstrating GM's 4<sup>th</sup> generation of fuel cell technology have been deployed in the Los Angeles area
- Vehicles collect data according to NREL Data Reporting Templates and fuel at Shell Hydrogen, Clean Energy, University of California Irvine and GM facilities

### Maintenance and Training Facilities




- Ongoing maintenance and training activities at Burbank, CA and Quantum Lake Forest facilities



Burbank, CA

# Technical Accomplishments

## Western Region Hydrogen Fueling Infrastructure

Station	Location	350 bar	700 bar	Generation/Delivery	Comments
<b>Clean Energy/GM</b> 	Near LAX, CA	N/A	1/09	Delivered compressed gas	Completed <5 months Permitting <6 weeks  Infrared capable  Can fill 3 FCEVs back-to-back 5 min each, 7-10 per day
<b>GM Maintenance &amp; Training Center</b> 	Burbank, CA	11/07	11/07	Delivered compressed gas	200+ First Responders trained  Faster-fill (15-minute) installation under construction
<b>Shell Hydrogen, Santa Monica Blvd.</b> 	West LA, CA	6/08	N/A	Onsite Electrolysis on Canopy	100+ First Responders trained  World's first Canopy-mount electrolyzer based gaseous station at 350 bar  Gaseous refueling accommodating all vehicle manufacturers

– GM/SH West LA station is currently under construction; expected to be operational mid 2009

# Cold Weather Performance

Proving ground testing for cold start up (Kapuskasing, ON in Canada)


19 DOE vehicles were deployed in North East this winter and performed with customers as expected





# Data Upload During Fueling

Wireless transfer of data between vehicle and fueling stations



# Technical Accomplishments

## Codes and Standards (C & S) – NextEnergy



### Database

- Hydrogen Permitting Officials database posted to NextEnergy Center website

### Annual Conference September 18-19, 2008

- Focus on current industry efforts toward C&S development
- Featured panels from C&S organizations, city and state authorities

### Code Development

- NextEnergy is a member of NFPA 2 hydrogen code Task Group 8
- Working toward public release of the NFPA 2 document in March 2009





# Future Work

## Vehicles

- Continue executing Phase 2 vehicle deployment

## Hydrogen Fueling Infrastructure

- Inaugurate remaining hydrogen fueling stations
  - Two new NYC metro stations by mid 2009 at 350/700 bar
  - One new West LA station by mid 2009 at 700 bar

## Maintenance and Training Facilities

- Continue to conduct new driver training on Equinox FCEV, hydrogen safety, hydrogen fueling
- Continue to service vehicles

## Codes and Standards – NextEnergy

- Annual conference slated for Fall 2009; designed for attendees to experience permitting process firsthand

# Critical Infrastructure Next Steps

- Compelling, retail-like fueling stations
  - Geographically targeted regions where automakers want to put vehicles
  - 700bar fast-fill fueling with infrared communication link
  - Compelling station designs (customer and technology perspectives)
  - Robust hydrogen capacity and throughput – designed for growth
  - Operational with (or before) vehicles – market enabler
- Access to all stations
  - All automotive companies and their customers have access
  - Standard fueling protocol – safe / fast / effective fueling of all vehicles
  - Address liability exposure – straight-forward access agreements with consistent principles or eliminate access agreements altogether
- Expedient station approval and permitting process
  - State-wide consistency and local adherence
  - Community support
- Funding support and incentives/enablers
  - Stations, station technology and capacity upgrades, operating costs
  - Liability coverage/solution (funded liability pool, liability cap)
  - Assurance stations will be there on time - supply base






Germany



U.S.



# Project Summary

Accomplishments	Barrier / Target
<ul style="list-style-type: none"> <li>6 stations in operation with 3 more in process demonstrating multiple approaches to hydrogen generation and delivery</li> </ul>	<p>Hydrogen Fueling Infrastructure</p> 
<ul style="list-style-type: none"> <li>4 GM facilities for customer training and vehicle service – each equipped with 700 bar</li> </ul>	<p>Maintenance and Training Facilities</p> 
<ul style="list-style-type: none"> <li>50 vehicles deployed demonstrating 2 generations of fuel cell technology</li> </ul>	<p>Vehicles</p>  
<ul style="list-style-type: none"> <li>Data collection, analysis and reporting</li> </ul>	<ul style="list-style-type: none"> <li>Range</li> <li>Durability</li> <li><math>\text{\\$H}_2/\text{gge}</math></li> </ul> 





This presentation does not contain any proprietary information