WOLF CREEK HYDROPOWER REHABILITATION ANALYSIS REPORT

David Bishop, USACE Kathleen King, MWH October 12, 2016

"The views, opinions and findings contained in this report are those of the authors(s) and should not be construed as an official Department of the Army position, policy or decision, unless so designated by other official documentation."







WOLF CREEK POWER PLANT

Location:
Russell County, KY
River Mile 460.9

Generation: 6 Units @ 51.8 MW 310.5 MW









CONSTRAINTS

SEPA MOU

Minimum Flow

Dissolved Oxygen

Drawdown Limits

Downstream Release

Temperature

Water Control Manual

Refill Restrictions







ANALYSIS

Opinion of Probable Construction Cost

Opinion of Schedule

Water Availability & Energy Modeling

Comparative Benefit-cost Analysis







DEFINITION OF ALTERNATIVES

Alternative	Description	MW	Rated Plant Capacity (MW)	GWh/yr	Estimated Project Cost
Existing		51.8	310.5	972	
1	In-Kind	51.8	310.5	1,011.7	\$158,786,000
2	5 Larger	67.5	379.8	1,006.3	\$171,817,000
	1 Smaller	42.3	379.6		
3	6 Larger	67.5	405.0	996.4	\$167,772,000
4	Alt.1 w/Larger Generator	62.5	375.0	1,019.3	\$161,584,000
5	Alt. 1 w/ "design base"	51.8	310.5		\$138,956,000
6	Alt. 1 w/reuse of Wicket Gates	51.8	310.5	1,009.4	\$154,994,000







ALTERNATIVES CARRIED FORWARD


Alternative	Description	MW	Rated Plant Capacity (MW)	GWh/yr	Estimated Project Cost	Outage (Years)
Existing		51.8	310.5	972		
1	In-Kind	51.8	310.5	1,011.7	\$158,786,000	5.8
3	6 Larger	67.5	405.0	996.4	\$167,772,000	6.2
4	Alt.1 w/Larger Generator	62.5	375.0	1,019.3	\$161,584,000	5.8
6	Alt. 1 w/reuse of Wicket Gates	51.8	310.5	1,009.4	\$154,994,000	5.8







PROJECTED BENEFITS











- Minimal Change in Tailwater Flows
 - Unlikely to induce erosion

- National Environmental Protection Act
 - Categorical Exclusion

- Section 106, National Historic Preservation Act
 - Changes inside the plant = Further Coordination







CONCLUSION & RECOMMENDATION

- Keep all six units the same size
 - In-Kind (1 & 6)
 - Incidental Uprate (4)
 - Uprate (3)
- Carefully review peak/off-peak assumptions (duration and value)
- Additional steps (not in scope of study)
 - Prepare equipment laydown plan during design phase
 - Dissolved Oxygen Additional Information
 - Inspect & Certify powerhouse crane
 - Ensure contractor completes stress & fatigue analysis for any critical, reused components





