

Integrated Systems Packages Optimized for the Real Estate Lifecycle

New Project



LBNL

Paul Mathew

(510) 486 5116 | pamathew@lbl.gov

Project Summary

Timeline:

Start date: Oct 2018 **[NEW project]**

Planned end date: Sep 2021

Key Milestones

- Design and specification of Integrated System Packages (ISPs). 6-30-2019
- FLEXLAB testing of ISPs. 3-31-2020
- Field validation of ISPs in CBRE buildings. 6-30-2021

Budget:

Total Project \$ to Date:

- DOE: \$825,000 (FY19)
- Cost Share: \$0 (in-kind)

Total Project \$:

- DOE: \$2,731,000 (FY19-21)
- Cost Share: \$600,000 (planned in-kind)

Key Partners:

CBRE	<i>Advisory Committee:</i> ComEd, EDF, Emcor, Gensler, NYSERDA, PG&E, Paypal, Therma, TRC, ULI
kW Engineering	
Rocky Mountain Inst.	

Project Outcome:

This project aims to enable scaled adoption of deep energy savings retrofits by: a) creating standardized integrated systems packages that reduce “hassle” and transaction costs; and b) embedding them within routine real-estate events. The ISPs can in effect make integrated systems the low-risk ‘default’ option for routine real-estate life cycle events such as renovation, lease fit out, and equipment replacement.

This project supports BTO CBI MYPP strategies #1,2

Team



P. Mathew



P. Coleman



C. Regnier



J. Page



J. Shackelford



D. Kubischta



P. Pollard



D. Jump



G. Hopkins



M. Jungclaus



V. Olgay



M. Groppi



LBLN **leads the overall project** and will conduct the **FLEXLAB testing** of integrated systems packages (ISPs). LBNL has over 30 years experience in the research, development, and validation of energy efficiency technologies and strategies.



kW Engineering will lead **engineering development** and advise **field commissioning and M&V** of ISPs, drawing on their expertise in designing and implementing energy efficiency solutions for commercial buildings.



Rocky Mountain Institute will help with **stakeholder engagement**, drawing on their expertise in accelerating the adoption of market-based solutions that cost-effectively advance energy efficiency and renewables.




CBRE's Global Energy & Sustainability team delivers energy and sustainability solutions for CBRE clients. They will **support implementation of ISPs at CBRE sites.**

DOE Managers: Ken Sandler, Cindy Zhu

The Challenge

Integrated systems technologies can deliver deep energy savings...



Almost 500 zero-net-energy buildings!

Source: New Buildings Institute

...but:

- retrofits are often **too disruptive** because they are **not aligned with the real estate life-cycle**;
- require **significant engineering expertise** to implement and operate,
- utility incentives often entail **overly cumbersome M&V**;
- lingering concerns with **savings uncertainty and persistence**.

It's not easy to implement deep retrofits



Hinders scale adoption needed to meet BTO goals

Approach: Proposed Solution

Develop and field-validate a scalable approach to achieve deeper building energy savings in existing buildings. Two key elements:

1. **Integrated systems packages** (ISPs) that reduce transaction costs through technology packaging, standardization and streamlining.
2. Embed ISPs in routine **real estate life cycle events**, to reduce disruption and increase cost-effectiveness.




This effort complements BTO LBNL "Beyond Widgets" project by:

- tailoring packages to real estate lifecycle events;
- field-validating in real buildings.


Vision:

Integrated systems with deep savings become the low-risk 'default' option for routine real-estate life cycle events

ISPs: Illustrative examples




Approach: Method




Approach: Expected Outputs & Audience

1 *Resource sets for design and delivery chain*



Applicability guides



Benefit-cost calculators



functional test protocols



Installation requirements



operational guidelines

2 *Laboratory and field validation results*



Energy performance



Cost-benefit



Transaction costs

Key audiences:

- **Building owners/managers and tenants**
 - Develop scope of work and procure products/services for real estate events.
- **Design professionals, service providers, vendors**
 - Offer value-added “upsell” offerings to building owners and operators.
 - Ease the sales cycle and reduce customer acquisition costs.
- **Efficiency programs**
 - Offer incentives based on field validation results.
 - Reduce the level of effort to deploy these technologies via custom incentive programs.

Impact: Stock analysis

- Stock analysis using BTO SCOUT tool
- Technical potential assumes ISPs with 20% savings
- Two adoption scenarios: 10%, 30%

Sector	Annual energy use baseline TBtu	Annual savings tech. potential TBtu	Annual savings (10% adoption) TBtu	Annual savings (30% adoption) TBtu
Large Office	1400	280	28	84
Small Office	807	161	16	48
Total	2207	441	44	132

Enabling scale adoption of integrated systems routinely in the real estate life-cycle



Savings depth x breadth

Progress to date

Note: This is a new project, started Oct 2018

Characterize real estate events

- 33 stakeholder discussions completed
- Synthesized themes and takeaways for ISPs – draft report completed

ISP design and specification

- 2 design charrettes conducted - reviewed 36 candidate measures for ISPs
- Developed outline for package elements

Technical advisory committee

- Constituted TAC with 11 members
- Conducted first TAC meeting

33 Stakeholder Discussions


11



- Operators
- Owners
- Tenants
- Investors
- Developers
- A/E
- Construction
- Lease lawyers



- Two large real estate investment firms
- Two well known tech firms
- Large bank
- Large asset management firm



Stakeholder Perspectives: Key Themes

**Payback is (almost always)
still important**

3-5 years "if you're lucky"

Can be overridden with other benefits

**Packaging and standardization
are valuable**

*Reduction in time, hassle, and risk
What's proven and easy gets done*

**Lease and ownership structure
(and term) matter**

*Who pays for energy?
What's the "hold period"?*

**Organizational priorities and
practices vary widely**

Even within the same organization

**Get in the
specs**

*templates, portals,
standards, ...*

**Timing
matters**


*"there a 3-4 week
window..."*

**The key
influencer is ...
not obvious**

Key Takeaways for ISP Development

- **Provide context-specific guidance to select packages** *With easy-to-use tools (e.g., flow charts) that cover systems, lease structure, etc.*
- **Modularize packages** *Allow for building-specific characteristics and broaden their applicability*
- **Calculate cost effectiveness with user-relevant cost baselines** *Based on incremental savings and costs for particular real estate event*
- **Articulate the value of non-energy benefits** *Substantively and preferably quantitatively*
- **Make it easy across the whole delivery chain** *Comprehensive set of resources for selection, specification, procurement, installation, commissioning, operations*
- **Be technology-agnostic** *Most stakeholders don't have favorites; proveness, cost effectiveness and ease of implementation are more important criteria.*

ISP design process



	Tenant Fit Out Limited	Tenant Fit Out Expanded	Whole Building Renovation	RTU replacement
Lighting Lamp replacement	X	X	X	
Lighting fixture replacement	X	X	X	
Lighting occ controls	X	X	X	
Lighting daylight controls	X	X	X	
Lighting: Networked Lighting Control Sy	X	X	X	
Automated Interior shades	X	X	X	
Exterior shades			X	
Window films			X	X
Secondary Window inserts			X	
Window glazing upgrade			X	
Cool roofs			X	X
Plug load controls		X	X	
RTU upgrade			X	X
RTU upgrade w/ enthalpy recovery			X	X
RTU heat pumps			X	X
VRF RTU heat pump			X	X
VRF RTU heat pump w/ heat recovery			X	X
RTU w/ indirect evap cooling			X	X
VAV min reset	X	X	X	X
Thermafusers		X	X	
Rezoning		X	X	
DCV w/ CO2		X	X	X
DCV w/ occupancy	X	X	X	X
Intermittent ventilation	X	X	X	X
Ceiling fans w/ set point reset		X	X	
RCx incl ASHRAE guideline 36	X	X	X	X
Model predictive control			X	X
Heatpump DHW			X	
Instantaneous DHW			X	
Submetering	X	X	X	
Monitoring based Cx	X		X	X

Technical Advisory Committee

David Briefel, Gensler

Andy Bruch, EMCOR

Chris Corcoran, NYSERDA

Noel Corral, ComEd

Al Gaspari, PG&E

Jaxon Love, PayPal

Emily McLaughlin, ULI

Bruce Murdock, Therma

Gwelen Paliaga, TRC

Dipal Patel, CBRE

Marc Rausch, EDF



Initial meeting in February 2019 showed *strong engagement* by TAC members.

Next TAC meeting slated for late June 2019 to review ISP testing ideas.

Remaining Project Work

IN PROGRESS: Design of integrated systems packages (ISPs) optimized for specific real estate events

STARTING JUNE 2019: Conduct FLEXLAB testing of ISPs to assess energy performance, indoor environmental quality, commissioning and operating procedures.

PLANNED for 2020: Begin field-validation of ISPs to assess energy performance, cost effectiveness and transaction costs in actual real estate events in real buildings.

PLANNED for 2021: Complete field validation and develop a technology transition plan for future market uptake through multiple real estate stakeholder channels.

Task	FY19				FY20				FY21			
	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
Task 1												
Task 1.1 Characterize RE events												
Task 1.2 Design and Specify ISPs												
Task 2 FLEXLAB testing												
Task 3 Field evaluations												
Task 3.1 Site screening, down-selection												
Task 3.2 Planning and implementation												
Task 3.3 Evaluation												
Task 4 Technology Transition												
Task 5 External Review and validation												

Thank You

LBL

Paul Mathew, Principal Investigator
(510) 486 5116 pamathew@lbl.gov

Sponsor:



Research Team:



Demonstration partner:



REFERENCE SLIDES

Project Budget

Project Budget: \$2,731,000 (FY19-21) of which \$825,000 received (FY19)
Variances: None

Cost to Date:

- \$125,442 expended to Feb 28, 2019.
- \$229,023 encumbered in subcontracts FY2019

Additional Funding: \$600,000 cost share (in-kind over the full project)

Budget History

FY 2018 (past)		FY 2019 (current)		FY 2020 – FY2021 (planned)	
DOE	Cost-share	DOE	Cost-share	DOE	Cost-share
N/A	N/A	\$825,000	0	\$1,906,000	600,000

Project Plan and Schedule

Project is underway and on schedule:

- Project began October 2018, with a planned completion date of September 2021

Project Schedule													
Project Start: October 2019													Completed Work
Projected End: September 2021													Active Task (in progress work)
													◆ Milestone/Deliverable (Originally Planned) if missed
													◆ Milestone/Deliverable (Actual)
		FY2019				FY2020				FY2021			
Task		Q1 (Oct-Dec)	Q2 (Jan-Mar)	Q3 (Apr-Jun)	Q4 (Jul-Sep)	Q1 (Oct-Dec)	Q2 (Jan-Mar)	Q3 (Apr-Jun)	Q4 (Jul-Sep)	Q1 (Oct-Dec)	Q2 (Jan-Mar)	Q3 (Apr-Jun)	Q4 (Jul-Sep)
Past Work													
Date													
1.1 Real estate life-cycle events characterized and technology constraints defined.			◆										
Current/Future Work													
1.2 Suite of 3-5 ISPs designed and specified.	6/30/19			◆									
2.1. FLEXLAB and simulation testing of ISPs completed.	3/31/20							◆					
3.1. Field validation sites for 4-5 unique events identified.	3/31/20							◆					
3.2. Field evaluation report completed.	6/30/21												◆
4.1. Technology transition plan completed.	9/30/21												◆
5.1. Summary report from external review panel	9/30/21												◆
Go/No-Go Decisions													
Each ISP is designed to meet 20% savings	7/31/19				◆								
Real estate partner reconfirms commitment to collaborate on field validation	9/30/19				◆								