
# U.S. DEPARTMENT OF ENERGY

Office of ENERGY EFFICIENCY & RENEWABLE ENERGY

#### **Building-Level DC Distribution Systems**

NREL (WBS# 2.2.2.40) and LBNL: (WBS# 2.2.2.46)

Willy Bernal (NREL), Rich Brown (LBNL)



### Project Summary: NREL (WBS# 2.2.2.40) and LBNL: (WBS# 2.2.2.46)

#### Timeline:

Start date: October 1, 2018

Planned end date: September 30, 2021

#### **Key Milestones:**

- 1. Project Work Plan; 12/15/2018
- Establish performance metrics and measurement methods; 9/30/2019

#### **Budget:**

Total Project \$ to Date: \$45,244

DOE: \$33,244

Cost Share: \$12,000

Total Project \$: 2,395,000

• DOE: \$2,200,000

• Cost Share: \$195,000

#### **Key Partners**:

⇒ eMerge Alliance



 $\Rightarrow$  GSA



⇒ American Geophysical Union



#### **Project Outcome:**

Quantify the performance of DC distribution systems in buildings and further validate energy models for electrical distribution systems in buildings. Accelerate the development and adoption of DC distribution technology by identifying technical barriers for installing, operating, and maintaining DC distribution systems and documenting targeted future research and development needs to overcome these challenges.



#### **Team**





Michael Deru

Mechanical engineer with expertise in integration and validation of high efficiency building systems



**Richard Brown** 

Systems engineer with expertise in integration and validation of networked controls and power systems in buildings



Willy Bernal

Electrical engineer with expertise on benchmarking emerging green technologies and microgrids configuration and operation



**Bruce Nordman** 

Architect focused on networked controls and local power distribution in buildings



Stephen Frank

Electrical engineer focused on controls and optimized electricity distribution systems for buildings



Vagelis Vossos

Physicist focusing on efficiency versus cost-effectiveness in building systems and equipment, with several publications on DC systems.



Omkar Ghatpande

Electrical engineer with expertise in design and manufacturing of renewable power distribution systems




**Daniel Gerber** 


Electrical engineer with expertise modeling and prototyping efficient power electronics for DC power

## Challenge

- Buildings use alternating-current (AC) power distribution systems
- Most equipment uses direct-current (DC) electricity internally
- AC-to-DC converters are required at each device
- Expanding use of DC loads and sources in buildings
- Conversion stages and equipment incur in energy losses and maintenance cost
- 5.6 million commercial buildings in the US in 2012










Sources: EIA (2012); DOE Power America website (2018); Garbesi, Vossos, and Shen (2011); Perea et al. (2018)

## Related BTO-Funded Projects on DC Power

- US-China Clean Energy Research Center (CERC) Smart Grid & DC Power (FY16-FY20)
  - Model energy savings from DC power and validate with lab measurements
  - Conduct techno-economic analysis of DC systems and their life-cycle performance
  - Analyze savings and benefits from communications and control in networked DC systems
  - Transfer results to global technology standards



- DC Design Tool (NREL-led, FY18-FY20)
  - Develop simulation-based design tool for comparing AC and DC building distribution
  - Validate models with lab measurements, including indirect effects on internal gains

## **Approach**



**Define challenges and opportunities** to overcome the technical and market barriers.

Lead: LBNL



**Develop metrics and methods** to accurately and comprehensively quantify the performance of electrical distribution systems

Lead: NREL



Field validation of DC distribution systems to reduce the uncertainty for DC systems and make recommendations for improved performance


Lead: NREL

### **Approach:** Task 1 – Define challenges and opportunities

#### a. Challenge:

Uncertainties in changing from AC to DC power distribution systems

- ⇒ Design and implementation
- ⇒ Energy and cost performance
- ⇒ Availability and performance of DC products
- ⇒ Lack of DC standards
- ⇒ Lack of proven performance




#### b. Mitigation:

We will work with our partners and the industry to clearly define the state of the industry and the challenges and opportunities

### **Approach:** Task 2 – Develop metrics and methods

- a. Performance predictions for DC systems vary widely and are based on
  - ⇒ Inconsistent assumptions
  - ⇒ Poor measurement and analysis approaches
  - ⇒ Questionable claims
  - ⇒ Conflicting results
- b. We will define clear and consistent
  - ⇒ Performance metrics for energy and nonenergy benefits
  - ⇒ Measurement methods
  - ⇒Analysis methods



DC Microgrid


Source: Illustration by Marjorie Schott, NREL

c. We will build on previous research of DC system

### Approach: Task 3 – Field validation of DC systems

Validating performance in real buildings will reduce the uncertainty and risks for building owners, utilities, policy makers, and manufacturers


- ⇒ 2 to 4 Field Evaluation Sites
- ⇒ New or existing DC distribution power-system installations



Source: Illustration by Marjorie Schott, NREL


### **Impact**

This project will help define the benefits of DC power distribution systems in buildings and accelerate its adoption.



building electricity savings for buildings with no on-site renewables or storage

buildings with onsite renewables or storage



DC electrical system more adept to connect with renewables and batteries



Increase reliability due to reduced number of conversion stages and thus equipment



Low voltage circuits for lighting and plug loads are safer for operators and maintenance staff

### **Progress**

We have completed six months of a three year project and are on track with our milestones and deliverables.

#### Task 1



Completed some background research



Developed outline and started preparing the draft report due to DOE 6/30/2019

#### Task 2



Completed some background research: reviewed 20+ articles and reports.



Developed outline and started preparing the draft report due to DOE 6/21/2019

#### Task 3




Developed a site selection criteria for working with GSA and have a list of potential field validation sites



Working with American Geophysical Union to prepare for monitoring and validation of their building:

### Stakeholder Engagement





- ⇒ More than 100 member organization
- ⇒ Develops technical application standards



# Federal building manager and field validation partner

- ⇒ Assess innovative tech in real world environment
- ⇒ Accelerates market acceptance




# Field validation partner in their net zero building retrofit







# Remaining Project Work



#### Major Milestones:

- M1. Complete development of performance metrics and measurement methods for electrical distribution systems
- M2: Identify at least two field test sites and develop project M&V plans
- M3: Preliminary report on performance for technologies and test sites
- M4: Report on opportunities for improved performance and energy savings for DC distribution systems

# Thank You



#### Willy Bernal



720-326-0841



willy.bernalheredia@nrel.gov



#### **Richard Brown**



510-486-5896



rebrown@lbl.gov

# **REFERENCE SLIDES**

## **Project Budget**

⇒ Project Budget: Table below

⇒ Variances: Project on track

 $\Rightarrow$  Cost to Date: \$49,000

⇒ Additional Funding: None.

Budget History											
Oct. 1 <sup>st</sup> 2018 – FY 2019 (current)		FY 2020	(planned)	FY 2021 - Sept. 30 <sup>th</sup> 2021 (planned)							
DOE	Cost-share	DOE	Cost-share	DOE	Cost-share						
\$725,000	\$65,000	\$750,000	\$65,000	\$725,000	\$65,000						

# **Project Plan and Schedule**

Project Schedule													
Project Start: Oct. 1st, 2018	Completed Wo				rk								
Projected End: Sept. 30th, 2021		Active Task (in progress work)											
			Milestone/Deliverable (Originally Planned) use for missed										
	•	Milestone/Deliverable (Actual) use when met on time											
		FY2019			FY2020				FY2021				
Task	Q1 (Oct-Dec)	Q2 (Jan-Mar)	Q3 (Apr-Jun)	Q4 (Jul-Sep)	Q1 (Oct-Dec)	Q2 (Jan-Mar)	Q3 (Apr-Jun)	Q4 (Jul-Sep)	Q1 (Oct-Dec)	Q2 (Jan-Mar)	Q3 (Apr-Jun)	Q4 (Jul-Sep)	
Task 1: Define Challenges and Opportunities													
Report: State of technology & market (6/30/2019)													
Journal-ready Article(10/31/2019)													
Final Report: State of technology & market (9/15/2021)													
Task 2: Develop Performance Metrics and Methodology													
Report: Methods and Methodology (6/21/2019)								Ц_					
inal Report: Methods and Methodology (9/29/2019)						Go	o-No	Go					
Task 3: Field Testing of DC Distribution System													
Report: Field test site selection criteria and technology descriptions (9/15/2019)													
Two field test sites have been selected, building owner and staff indicate full support, draft M&V plan with schedule developed (12/15/2019)						Go	)-No (	Go					
Report on the analysis and results from the test sites (09/20/2020)													
Final Report: performance, lessons learned, and recommendations for technologies and test sites (8/30/2021)													