

## **Lighting and Grid Integration Research**



Pacific Northwest National Laboratory Michael Poplawski, Principal Investigator michael.poplawski@pnnl.gov

## **Project Summary**

#### **Timeline**

Start date: 10/1/2018 New Project

Planned end date: 9/30/2021 **Key Milestones (FY 2019)** 

1. CLS grid services report 5/31/2019

2. CLS modeling report 8/31/2019

### <u>Budget</u>

### **Total Project \$ to Date:**

DOE: \$500k

Cost Share: \$0

### **Total Project \$:**

DOE: \$1500k

Cost Share: \$0

### **Key Partners**

Technology Developers	
End users	
Electric Utilities	
Agencies, Power Authorities	NYSERDA

#### **Project Goals and Outcomes**

The ability of Connected Lighting Systems (CLS) to deliver potential grid services while simultaneously delivering sufficient lighting service and occupant satisfaction has not yet been proven or quantified. This project will quantify and advance the ability of CLS to provide grid services through modeling and simulation, laboratory testing, and field testing. Project results will be disseminated via targeted mechanisms to technology developers, lighting manufacturers, building owners and operators, system integrators, industry standards organizations, and other researchers.

### **Team**




Michael Poplawski EE/SS-Physics/Pl 20/10 years



Michael Brambley ME/Control/PI 28/22 years



Kelly Gordon
Public Policy/PM
30/19 years



Yan Chen EE-AE/Mod-Sim 4/4 years



Michael Myer LE/Codes-Standards 14/12 years



Peng Wang EE-CS/Mod-Sim 1/1 years



Abhishek Somani Economics/Grid 8/8 years



David Anderson Economics/Grid 28/24 years



Jianming Lian EE/Control-Grid 10/8 years




Mallikarjuna Vallem EE/Power-Grid 10/6 years

### Challenge

Connected Lighting Systems in GEBs have the potential to deliver improved lighting performance (energy, lighting quality, occupant satisfaction), improved performance of other (e.g., HVAC energy, security) building systems, other valuable data-enabled services, AND grid services. However, at this early stage in their development, their grid service potential is largely not being pursued for many reasons. At or near the top of this list are two key challenges:

- 1) Lighting systems have not received as much attention from lighting and grid service stakeholders to date as their HVAC counterparts due to perceived limitations. While their portion of building energy consumption is also significant, they typically cannot shift their consumption, and maintaining occupant satisfaction is more dependent on a variety of building and occupant factors.
- 2) While the financial benefits for GEBs participating in the nascent grid service market are still very much unknown, much uncertainty exists as to whether lighting systems could, even theoretically, provide significant or unique grid services.




## Approach - Cross stakeholder education

Simple power-light relationship Complex lighting Lighting application needs Grid Complex occupant Technology Complex powersatisfaction criteria thermal relationship Service developers Very fast device Simple thermal response time; varying Early application needs GEB system response time adopters Simple occupant Utility Need integrated satisfaction criteria Industry storage to time-shift Service vs. Varying device and Integral network consortia system response time result of interface(s), Inherent ability to intelligence, energy service time-shift reporting Thermal Add-on network interface(s) and centric integral intelligence

Goal: Define CLS characteristics that enable grid services, performance metrics key to the delivery of specific services, and methods for quantifying services.

## **Approach – Simulation based analysis**



Goal: Quantify the potential for CLS to provide substantial or novel grid services under a range of building and electric grid operating conditions.

### **Approach – Laboratory & virtual test beds**

### **Connected Lighting Test Bed**







### **Early Adopter Deployment(s)**



- Goal: Develop field evaluation plan
  - Project criteria and, if possible, potential project sites (not pilot studies)
  - Validate laboratory results
  - Characterize stakeholder (owner, operator, occupant, other) satisfaction
- Goal: Initiate field evaluation, if suitable site identified

### Impact - Technology development


#### **Near term**

- CLS configurable for providing grid services
  - Grid service type
  - Occupant satisfaction sensitivity
- CLS capable of receiving and interpreting grid service signal
  - o API
  - OpenADR, other protocols
- CLS capable of verifying delivery of grid service
  - Energy reporting
  - Accuracy, resolution, latency

#### Future term

- CLS with incremental ability to provide grid services via integration of incremental/modular storage
- CLS capable of real-time discernment of occupant satisfaction
  - Current, predictive occupancy
  - Current, predictive task
- CLC capable of incorporating specific occupant needs/preferences into grid-service capability
  - Configurable, occupant opt-in
  - Cybersecurity and privacy

### **Impact – Early adopter success**



Source: Douglas Rath, Marriott International

### Impact - Industry consensus

#### **Near term**

- Substantial/unique grid service capabilities of CLS
  - Focus for CLS technology developers
  - Design focus for GEB system integrators
- Grid service signaling interoperability with CLS
  - Applicable API resources
  - OpenAPI Initiative or other

#### Future term

- Substantial/unique grid service capabilities of storage-enabled CLS
- Grid service signaling interoperability with CLS
  - Embedded protocol support
  - OpenADR or other

## **Progress - Project coordination**


#### **CLS** types

Advanced Adaptive Lighting Control Algorithms


**Integrated Batteries** 


DC LEDs Luminaires

Hybrid Sunlight LED Systems SSL Displays









### **Progress - Consensus grid services**

# GEB framework (draft)

- 1. Reduce generation operating costs
- 2. Reduce generation capacity costs
- Provide contingency reserves (nonspinning)
- 4. Provide distribution voltage support
- Provide frequency regulation
- 6. (Provide ramping)
- 7. Reduce transmission upgrade costs
- 8. Reduce distribution upgrade costs

## Project proposal (Focused on limited set)

- 1. Energy service
- 2. Peak demand limiting
- 3. Regulation
- 4. Frequency response

# PNNL cross-project analysis (in-progress)


- 1. Long-term Capacity or Resource Adequacy
- 2. Regulation Up/Down
- 3. Operating Reserve
  - a) Spinning
  - b) Non-spinning
- 4. Other Market Products and Services
  - a) Flexible Ramping
  - b) Voltage Support
  - c) Fast Frequency and primary frequency response
  - d) Black Start
  - e) Distributed system services


### **Progress – Lighting model parameters**

## Lighting profile (Space types)

## DOE commercial prototype building models


- Small, Medium, Large Office
- Standalone Retail
- Strip Mall
- Primary, Secondary School
- Outpatient Healthcare, Hospital
- Small, Large Hotel
- Warehouse
- Quick-service, Full-service Restaurant
- Mid-rise, High-rise Apartment





## Lighting load (Power)

- ASHRAE 90.1-2019 lighting power density (LPD) values
- Up to four luminaire types per space
- ASHRAE 90.1 Lighting Subcommittee luminaire type power data



## Lighting schedule (Hours-of-use)

- ASHRAE 90.1-2009
   Advanced Energy Design Guides, Technical
   Support Documents
- ASHRAE 90.1-2004
   User's Manual Section G
- ASHRAE 90.1-1989
   Section 13 Energy Cost
   Budget Method
- Apartment study (Gowri 2007)



## **Progress – Lighting model parameters**


- Nominal illumination (power, per hour of day)
- Maximum illumination (power, per hour of day)
- Minimum illumination (power, per hour of day)
- Illumination (power) ramping (up/down) rate
- Delay (grid service signal → onset of service)
- Response time (initiation of service -> full activation of service)
- Duration of service


## **Progress – Lighting parameters**


Small Office Building (5,500 square feet)





























### Stakeholder Engagement - PAG (Project Advisory Group)

### Approximately six representatives

- External stakeholders from the lighting, building, and electric-grid industries with the knowledge and background that enable them to judge market relevance of the project work
- Assess the marketplace relevance of the project work, and make recommendations for increasing the market relevance

### Quarterly teleconference meetings

- Updates on current project activities and approaches, preliminary research findings, upcoming planned activities, and summaries of other stakeholder interactions (e.g., webinars, presentations, reviewer feedback on papers)
- DOE management invited

### Yearly DOE briefings

- Summarizes teleconference meetings and the anticipated market relevance of the research as of that time
- Include notable feedback from stakeholders responding to presentations, research reports, journal articles, and other outreach activities

## Stakeholder Engagement – PAG recruitment

<u>Technology developers (TBD): Lighting, Storage, Other?</u>







End users (TBD)



Electric utilities (TBD): Large/typical, forward-looking, medium/small, municipal, cooperative























Electric utility agencies



Power Authorities (TBD)





## Remaining Project Work - Work Plan

Task	Description	Due Date			
1	Characterize CLS Opportunity for Providing Grid Services				
2	Develop CLS Models and Integrate into Existing Co-Simulation Platform				
3	Quantify CLS Potential Contributions to Grid Services Using Simulations	M06-M30			
	1) Prepare the co-simulation environment				
	2) Develop Simulation Test Plans				
	3) Perform Simulations and Analyze Results				
4	Evaluate CLS Ability to Provide Grid Services in a Laboratory Environment	M06-M30			
5	Develop Plans for Field Evaluation of CLS Ability to Provide Grid Services	M30-M36			
6	Externally Validate Marketplace Relevance	M01-M36			

## Remaining Project Work - Key Milestones

	Task	Description	Due Date
FY19	1	Complete report characterizing CLS opportunity to provide grid services	3/2019
	2	Complete report on CLS models, integration into co-simulation platform	8/2019
	6	Complete DOE briefing on external validation of marketplace relevance	9/2019
FY20	3	Complete report on grid services provided only by CLS based on building-grid simulation results	3/2020
	3	Complete report on grid services provided by coordinated CLS and HVAC based on building-grid simulation results	8/2020
	6	Complete DOE briefing on external validation of marketplace relevance	9/2020
FY21	3	Complete report on grid services provided by coordinated CLS, storage-enabled CLS, and HVAC based on building-grid simulation results	2/2021
	4	Complete report on laboratory testing results	5/2021
	5	Complete report on field-testing plan	8/2021
	6	Complete DOE briefing on external validation of marketplace relevance	9/2021

## **Thank You**

Pacific Northwest National Laboratory

Michael Poplawski, Director, Connected Lighting Systems Research

503-417-7561

michael.poplawski@pnnl.gov

## **REFERENCE SLIDES**

## **Project Budget**

**Project Budget**: New project starting in FY 2019.

Variances: Lower than anticipated spending in first half of FY; will

increase in Q3 and Q4 FY19

Cost to Date: as of March 2019 month end: \$62k cumulative cost to date

**Additional Funding: None** 

Budget History										
FY 2018 (past)		FY 2019 (current)		FY 2020 – FY 2021 (planned)						
DOE	Cost-share	DOE	Cost-share	DOE	Cost-share					
N/A	None	\$500k	\$0k	\$1000k	TBD					

### **Project Plan and Schedule**

