## **BTO Program Peer Review**





Roof Testing Facility at ORNL Building Technologies Research and Integration Center

PM: Andre Desjarlais

PI: Meng-Dawn Cheng, Ph.D.

David Graham, Ph.D.

Sue Carroll

Steve Allman

Dawn Klingeman

Susan Pfiffner, Ph.D. (FY12)

Karen Cheng (FY12)

Partner: Joe Rokowski (Dow)

New Cool Roof Coatings and Affordable Cool Color Asphalt Shingles Meng-Dawn Cheng


Oak Ridge National Laboratory chengmd@ornl.gov; 865-241-5918 April 4, 2013

#### Relevance to BTO Missions



- Building accounted for 41% of the US energy consumption in 2010 greater than either transportation (28%) or industry (31%).
- Building is responsible for 40% CO<sub>2</sub> emission in the US.
- Emerging Technologies (ET) is one of the three-pronged strategies of BTO to meet its goal in energy saving, energy efficiency improvement, and reduction of greenhouse gas emissions.
- Cool roof technology for building envelop is supported by BTO missions under its ET program aiming for high-impact energy saving and reduction of greenhouse gas emissions.







Thermal Imaging

Residential Building


# Purpose & Objectives



- Problem Statement: To meet product standards (EPA EnergyStar and International Energy Conservation Code) require cool roofing products must undergo an evaluation of their surface properties (solar reflectance and thermal emittance) after 3 years of exposure to natural environments. Microbial degradation of coating performance is prevalent throughout the US and world.
- Impact of Project: The results will enable US-based roofing and coating industry to accelerate performance testing of their products from 3 years to a month or so, and enhance the market penetration and economic competitiveness.
- Project Focus: Significantly enhance the next generation of polymers for roof coatings and asphalt shingles to reduce energy consumption of new and existing roofs. The BTO's goal impact for this technology is estimated at \$3.71/MMBtu.

# Key Issue – Microbial Contamination






Analysis of elemental and carbon profiles of roof samples on coupons collected at 1.6 (in 2006) and 4 (@2008) years of elapsed time.

Comparison of the 2 time points suggests Si and OC were the two major species accumulated over time

PLFA suggests OC is associated with biomass, possibly mixed microbial communities




clay

Concrete

**PVDF Metal** 





- Cheng, Pfiffner, Miller, and Berdahl (2011) Building and Environment, 46: 999-1010
- Cheng, Miller, New, and Berdahl (2012) Construction and Building Materials, 26: 516-526

### **Project Objectives**



- New Cool Roof Coating Microbial
  - Identify microbial communities on roof samples
  - Establish an aging procedure using microbial communities
  - To allow products to be tested and moved to market more quickly than current testing methods which require exposure of roof to ambient conditions for three (3) years.
- Cool Color Asphalt Shingles
  - Determine first estimate of cost limitations for coating shingles



# Approach



#### New Cool Roof Coating – Microbial


- Develop a sampling protocol for taking environmental microbial samples, Seek industrial acceptance
- Establish geographical distribution of microbial communities, Map to guide the design of microbial testing procedure
- Devise a microbial cocktail for accelerated testing
- Design a practical incubation system
- Establish a quantitative relationship between physical parameters like surface reflectance, temperature, relative humidity (or moisture), etc. and microbial activities

#### Cool Color Asphalt Shingles

- To develop a cost effective retrofit coating for shingles











# Accomplishment — Microbial Field Sampling Protocol








- A field microbial sampling protocol was developed.
- The protocol was applied to a number of cool roofing materials and coatings.
- Protocol was distributed widely and freely to industrial partners.

# Accomplishment –

#### Fungal isolate identification






- From the sequenced fungal DNA, 26 were successfully sequenced.
  NCBI BLAST analysis was used to determine proper fungal genera for each sequenced isolate.
- Penicillium was the most dominant fungal genus presented across all locations regardless of environmental and weathering factors.

# Accomplishment -

#### Bacterial distribution using 454 pyrosequencing





- FL samples showed much higher abundance of Cyanobacteria/Chloroplast and Proteobacteria.
- TN samples rich in Actinobacteria, Proteobacteria, and other phyla.
- PA samples is dominated by Proteobacteria, followed by cyanobacteria and other phyla.
- Geospatial bacterial diversity is a critical finding.
- 3 separate phyla (categories) could form a start-up bacterial community.

### Project Plan & Schedule



Plans and milestones for projects: New Cool Roof Coating Microbial Testing and Cool Color Asphalt Shingles are combined in the schedule.

Summary						Legend						
WBSiNumberioriAgreementiNumber:i19905/22296						Workitompleted						
ProjectiNumber						Active@ask						
AgreementiNumber: BT0304020länd: BT0400000						Milestonesl&Deliverablesl(OriginallPlan)						
						Milestones(&f/Deliverables((Actual)						
	FY2012				FY2013			FY2014				
	(aoctt-Dec)	il(Jan-Mar)	34(Apr-Jun)	44(Jul-Sep)	1¶Octt-Dec)	2 (Jan-Mar)	3∄Apr-Jun)	4項Jul-Sep)	14Octt-Dec)	2 (Jan-Mar)	34Apr-Jun)	4 (Jul-Sep)
Task #Event	0.1	Q2	03	0.4	Q1	02	63	Q4	0.1	02	8	ο 4
Project Name: NewCool Roof Coatings and Affordable Cool Color Asphalt Shingles												
FY2012: Complete geospatial microbial identification, exposure chamber				4								
Q1fMilestone:fGrowthioninon-biocide/substrate/fMicrobial												
Q1@Milestone:@nitiate@ost@nalyses@Cool@olor@hingles												
Q28Milestone:Quantification,@nicroincubator@lesign@Microbial							•					
Q2@Milestone:Complete@cost@nalyses@Cool@olor@hingles												
Current work and future research												
Q33Milestone:@ontrolled@rowth,@nicroincubator@abrication@Microbial						<b>-</b>						
Q3:Milestone:[NofActivity]:#Cool@olorfShingles												$\Box$
Q4:EQuantification, if esting protocolide velopment complete EdMicrobial									<b>-</b>			
Q4:ICompleteimeasurementiofilygrothermalipropertiesIICooliColoriShingles								•				

### Cool Roof Project Budget



Project Budget: FY13 project budget is \$383K.

Variances: No variances from planned budget.

Cost to Date: As of 20 March, \$100K or 26% of budget expended.

Additional Funding: No other funding sources beyond inkind contributions.

Budget History								
FY2010		FY2	2011	FY2012				
DOE	Cost-share	DOE	Cost-share	DOE	Cost-share			
0	0	\$500K	\$500K	\$600K	\$600K			

# Latest Progress, March 2013



- New Cool Roof Coating Microbial
  - Microbial cocktail has been assembled
    - ♦ 4 fungal species
    - ♦ 3 algal species
    - ♦ N bacterial species; N remains to be determined
  - Specialized incubator technology has been designed
    - ♦ Optimal growth of each microbial community for precision replica
    - ♦ Continuous growth and growth stimulation allowed
    - Climatic simulation programmed
- Cool Color Asphalt Shingles
  - LBNL model to predict energy savings from retrofit shingle coating
  - All parties contributed to model inputs
    - ♦ Baseline solar reflectance, target solar reflectance, service life
  - Dow and CertainTeed estimated costs of coating
    - ♦ Production and application, reasonable payback period of 5-7 years
    - ♦ Estimated paybacks of 10-15 years exceed what market will absorb

# Project Integration, Collaboration & Market Impact: CRADAs



- New Cool Roof Coating Microbial: Dow, LBNL and ORNL
  - Dow develops more efficient coating
  - LBNL develops accelerated dirt pickup test
  - ORNL develops accelerated microbial test

- Cool Color Asphalt Shingles: Dow, LBNL, CertainTeed and ORNL
  - Dow develops coating and cost data
  - CertainTeed develops coating criteria and market cost data
  - LBNL and ORNL perform cost analyses







**Building Solutions** 



# Project Integration, Collaboration & Market Impact: Communications



#### <u>2011</u>

- Cheng, Pfiffner, Miller, and Berdahl (2011) Building and Environment, 46: 999-1010
- Cheng et al. (2011) DOE meeting, Berkeley, CA, July

#### 2012

- Cheng, Miller, New, and Berdahl (2012) Construction and Building Materials,
  26: 516-526
- Pfiffner et al. (2012) RRCI Conference, Orlando, FL, February
- Cheng et al. (2012) ASM Conference, San Francisco, CA, June
- Cheng et al. (2012) IRCC Conference, Baltimore, MD, July
- Cheng et al. (2012) COBEE Conference, Boulder, CO, August.
- Pfiffner et al. (2012) ASM KY-TN Branch Meeting, Maryville, TN, October


#### 2013

 Cheng, Cheng, and Pfiffner (2013) Geospatial Characterization of Microbial Communities on Environmentally Aged Roofing Materials, to be submitted to Building and Environment, Status: Internal Review

### Next Steps and Future Plans



- New Cool Roof Coating Microbial
  - Optimize microbial growth process
  - Evaluate biomass accumulation and surface reflectance for selected climate zones
  - Evaluate microbial testing protocol on advanced coatings and roofing materials
- Cool Color Asphalt Shingles
  - Complete Project Partners chose not to pursue further





USA News Brief, 11/9/2012