



Solid Oxide Fuel Cell Manufacturing Overview

**Hydrogen and Fuel Cell Technologies
Manufacturing R&D Workshop**

August 11-12, 2011


Washington, DC

Mark Richards, Eric Tang, Randy Petri


Contents

- ▶ Manufacturing development dependencies
- ▶ SOFC elements
- ▶ Cell manufacturing processes
 - Materials
 - Forming
 - Conditioning
- ▶ Stack assembly
- ▶ Quality control and testing
- ▶ VPS projected cost reductions in SECA

The Solid Oxide Fuel Cell Electrochemistry




Stack Manufacturing Development



Influencing Factors


- ▶ **Manufacturing**
 - Selection of fabrication process
 - Evolution of desired microstructure
 - Cell-to-cell variability as manufactured (high yields necessary)
 - Stack (cell-to-cell variation)
- ▶ **Design**
 - Cell architecture
 - Stack design
 - Material stability
 - Oxidation behavior of steels
 - Sintering at operating conditions
 - Interdiffusion of cations
 - Phase changes/phase separation
 - Creep → warpage
- ▶ **Operation**
 - Fuel composition (U_f , H/C ratio, contaminants, $f(t)$)
 - Oxidant (U_o , contaminants, pO_2)
 - Temperature (max)
 - Temperature gradient ($^{\circ}C/cm$)
 - Temperature variation: x, y, z



SOFC Elements: Independent of Construction

- ▶ Need to create and join the electrochemical elements (cells)
 - Anode, cathode, electrolyte
 - Ceramics
- ▶ Need to bring reactants to (and from) the cells and keep them where they belong
 - Flow fields, seals, manifolds
 - Ceramics or metallics
- ▶ Need to move electricity from cells
 - Interconnects, current collection
 - Ceramics or metallics
- ▶ Need to move heat from cells and stacks
 - Active and passive thermal management

SOFC Stack Elements



- ▶ Fuel cell
 - Electrolyte, cathode, anode
- ▶ Interconnects
 - Deliver gases, transfer electrons, mechanically support cell
- ▶ Seals
 - Keeps gases where they belong
- ▶ Compression system
 - Hold it all in place
- ▶ Current collection
 - Get the electrons out

Common Ceramic Manufacturing Steps

- ▶ Raw material preparation
 - Powder production
 - Powder preparation
 - Sizing
- ▶ Forming
 - Tape casting, slip casting, pressing, extrusion, calendaring, dispensing...
 - Printing, dip coating, spraying, vapor deposition...
- ▶ Conditioning
 - Drying, bisqueing, sintering


Ceramic Raw Material Preparation

- ▶ Generally, most powders will be procured from suppliers
 - May require in-house processing such as sizing or purification
 - Inbound quality control
- ▶ Further preparation prior to forming or deposition
 - Additional functional materials may be added as well as binders or slurry agents
 - Milling is commonly used to refine and mix materials

Ceramic Forming: Primary Layer

- ▶ Extrusion
 - Ceramic with a binder is forced through a mandrel forming the desired green shape (which can be closed at the leading end)
- ▶ Tape Casting
 - Ceramic tape is made by uniformly spreading slurry onto a smooth surface
- ▶ Drying
 - Both extrusions and tapes need to be dried to allow for handling and application of other functional elements prior to sintering
- ▶ Cutting
 - With extrusions, cutting may result in nearly no loss of material
 - In a planar cell, tape lost to cutting is a function of cell geometry and tape size
 - Recycling of tape lost to cutting is possible

Tape Casting




Anode Tape

Ceramic Forming: Additional Layers

- ▶ In either a planar or tubular configuration, additional layers are applied to the primary (usually support) layer
- ▶ Screen printing
 - Thickness can be limited, reasonable cycle times and cost, planar only
- ▶ Thermal spraying
 - Typically uses a flame or plasma, can provide thick coatings, higher deposition rates than vapor deposition
- ▶ Vapor deposition
 - Chemical processes use a fluid precursor which undergoes a chemical change at a solid surface, leaving a solid layer
 - Physical processes tend to require a low-pressure vapor environment to function properly
- ▶ Dip coating
 - Coating thickness a function of coated surface characteristics, ceramic paint properties, and number of applications
 - Equipment is inexpensive but cycle times can be relatively long

Screen Printing




Unfired Cell


Ceramic Conditioning

- ▶ Drying
 - Typically done at temperatures up to a few hundred C
 - Yields a flexible green ceramic
- ▶ Bisque firing
 - 300 to 500 C
 - Yields a stable but brittle shape
- ▶ Sintering
 - Ceramic powders are partially melted allowing particles to partially fuse
 - Time and temperature dependent
- ▶ Co-firing is possible but varying shrinkage rates make it challenging
- ▶ Low volume production tends to use batch furnaces, continuous furnaces are available for high volume firing

High Temperature Firing



Fired Cell





Common Metallic Manufacturing Steps

- ▶ Metallic fabrication processes are well established and not unique to SOFC manufacturing
 - Stamping, punching, rolling, brazing, welding
 - Powder metallurgy, casting
- ▶ In some instances, coatings are applied to metallic stack components to improve oxidation characteristics

Assembly


- ▶ Planar
 - Layering of cells, flow fields, interconnects, seals, etc. bounded by end plates/manifolds and compressed
 - Leak check and initial conditioning
- ▶ Tubular
 - Tubes and interconnects assembled with manifolds and enclosed
 - Leak check and initial conditioning
- ▶ Automated assembly equipment can require significant volumes to justify its development and expense
- ▶ Conditioning and test equipment are nearly like full-featured development test stands




Quality Control

- ▶ Physical properties
 - Dimensions
 - Density or porosity
 - Flatness
 - Uniformity
 - Discontinuity
 - ▶ Chemical properties
 - Compositions
 - Phases
 - Impurities
 - ▶ Electrochemical properties
- ▶ **Some QC activities are amenable to automation on non-operating parts, others are not to either or both**

Pareto Chart for Failure Reas



Process Capability - 28 Cell Stacks
Based on 102 Stacks (2856 Cells)



Cell Manufacturing Process Development



Global ThermoElectric - SOFC Production Tracking - [Green Tape Cutting Process]

File Production Inventory Administration Window Help

Tape ID: _____ Container: _____ Operator #1: _____ Process Start: _____
Operator #2: _____


Tape Cutting Process Instructions

1. latex gloves are to be worn at all times when cutting the tape.
2. Turn on wind motor on back of caster.
3. Start and advance tape so that 2m is accessible to cut.
4. Remove the first two feet of tape and recycle.
5. Align the cutting die so that its edges are perpendicular to the edge of the cast.
6. Using the die score along the center of the die.
7. Score along the middle edge of the cutting die.


Width of Tape (cm): _____
Starting Cell Serial #: _____
Ending Cell Serial #: _____

ACCEPT CANCEL

Process Tracking Database




SECA Projected Stack Cost Reduction



The fuel cell stack cost has decreased substantially mainly due to the R&D activities in the SECA project

Cost Reduction Focus Areas



1. Stack Performance Increase
 - Peak Power Increase
 - Resolved thermal management issues
2. Material Reduction:
 - Thinner stack components
 - Interconnect material reduction
 - Reduced number of intermediate plates
3. Manufacturing Process Changes
 - Interconnect manufacturing development
 - Improved material utilization
4. Process Optimization
 - Automation
 - Elimination of process steps



Stack Cost by Components and Category



96-cell Stack:
\$2,658 (2000 USD)



- **The majority of stack cost is driven by the cost of materials**
- **The relatively low labor cost is attributed partly to the fact that cells and seals are produced by VPS in-house**

Manufacturing Automation Strategies

- ▶ Manual operation
 - Production volumes from 5 MW to 25 MW
 - Use manual equipment with longer cycle times and smaller batch size

- ▶ Semi-automatic operation
 - Production volumes from 25 MW to ~100 MW
 - Use medium size equipment and has partial automation in key stations

- ▶ Automatic operation
 - High volume production from ~100 MW to 250 MW
 - Workstations and material handling system are automated

Cost and Manufacturing Initiatives

- ▶ **Materials**
 - Materials reduction in cell and stack
 - Low cost materials
 - Interconnect coating
- ▶ **Fabrication and assembly**
 - Cell co-sintering
 - Sealing technology
- ▶ **Quality control and testing**
 - On-line QA/QC with real time feedback
 - Stack conditioning

Questions?

**Portions of this material are based upon work supported by the
Department of Energy under Award Number
DE-FC26-04NT41837**

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.