

## Solutions for Curbside-Charging Electric Vehicles for Planned Urban Growth



### PI & Presenter: Professor Robert Cox DE-EE008472 | TI091 This presentation does not contain any proprietary, confidential, or otherwise restricted information.

# **Overview**

### Timeline

- Project start date: 10/1/18
- Project end date: 12/31/21
- ~45% complete

### Budget

- Total project funding:
  - DOE share: \$942,757.00
  - Cost share: \$942,757.00
- Budget Period 1:
  - DOE share: \$426,181
  - Cost share: \$569,190
- Budget Period 2:
  - DOE share: \$354,380
  - Cost share: \$223,817
- Budget Period 3:
  - DOE share: \$162,196
  - Cost share: \$149,750
- Expended (as of 3/31/2020):
  - DOE share: \$315,030.24
  - Recipient share: \$288,040.07

#### **Barriers Addressed**

- ~90% of charging expected to occur at home; only about 50% of vehicles have access to dedicated off-street parking
- Installing dedicated curbside EVSEs can be challenging, both in terms of cost and access
- Limited understanding of the ability to integrate EVSEs into existing street light infrastructure





# **Project Objectives**

### **Project Objectives**

- Develop, deploy, and test a protype EVSE that can be retrofit into existing streetlight infrastructure
  - Prototype includes hardware, software, enclosure, and integration
- Understand the market need for such retrofit EVSEs
- Document the challenges associated with installing retrofit EVSEs into streetlights:
  - Technical (i.e. control, power, etc.)
  - Policy (i.e. permitting, right-of-way, etc.)

### **Impact on Addressing Barriers**

- Detailed study of existing streetlight infrastructure in the Charlotte metro region
  - How scalable is the solution, technically?
- Comparing policy issues associated with retrofit solution vs. dedicated EVSE
  - Does the solution streamline implementation?
- Developing a commercialization-ready
   EVSE to address market need

### VTO TI Goals Addressed

- Success means:
  - Greater use of domestic electricity for fuel (National security)
  - EVSE products made in the USA (Economic growth)
  - Lower cost/more accessible charging solutions (Affordability for business and consumers)
  - Greater access to diverse fuel set (Reliability/resiliency)



## **Project Approach: Task Development**

### Prototype Development

- Hardware
  - Enclosure design
  - Cable management
  - Attachment
- Software
  - Development
  - Testing
- Integration & testing



### Community Engagement

- Secure partnership for pilot
- Manage permitting & related issues
- Engage community stakeholders & users



### Techno-Economic Analysis

- Understand market potential
- Understand technical integration issues:
  - Power-system impacts
  - Streetlamp integration issues





## Project Approach: Prototype Development Tasks

Technical development has four phases:





Development of basic requirements & specifications



**Off-Grid** 





Source: Direct-to-grid Load: Real EV Location: Lab (Duke)





## **Project Approach: Timeline**

2019				2020				2021				
Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	
Task 1: Prototype Engineering												
Task 2:	Communi	ty Engage	ement & F	Pilot Site	Determina	ation	-					
Task 3: needs	Techno-eo	conomic a	analysis o	f market	uptake &	infrastruc	ture					
			Task 4: 0 Develop									
					Task 5: Develop	On-Grid oment						
					Task 6: Field Test Deployment							
					Task 7: Field Testing and Evaluation							
									Task 8: Comme	rcializatio	n	



# **Project Approach: Milestones**

Milestone	Description	Туре	Target Date	Status
Prototype Engineering	Design specs & requirements	Technical	7/19	Complete
Prototype Engineering	Detailed design package	Technical	9/19	Complete
Techno-economic analysis	Report on market potential	Technical	12/19	Complete
Community	Selection of field demo partners	Go/No-Go	12/19	Complete
Off-Grid development	Complete laboratory testing	Technical	4/20	Complete
Field test deployment	Complete final site design	Technical	8/20	In-progress
Field test deployment	Complete commissioning of field demo	Technical	12/20	Not started
On-grid development	Complete testing at Duke Energy Mt. Holly	Technical	10/20	Not started
Cost-effectiveness determination	Determine cost-effectiveness of solution	Go/No-Go	10/20	In-progress
Field test launch	Field test initiated	Technical	1/21	Not started
Commercialization strategy	Determination of likely manufacturer and strategy	Technical	11/21	In-progress
Field test effectiveness	Field test evaluated	Go/No-Go	12/21	Not started

UNC CHARLOTTE Energy Production and Infrastructure Center

## **Project Approach: Enabling Technology**

- The key enabling technology is the Energy Management Circuit Breaker (EMCB) from Eaton
- Breaker occupies 4 positions in a standard cabinet
- Key features
  - Solid-state disconnect
  - WiFi addressable
  - Provides full monitoring and control
- Two versions of the breaker to be on the market:
  - EMCB: Simple breaker
  - EMCB-EV: Includes additional Level 2 EVSE feature set
- Metering accuracy greater than required for utility-grade metering





# Project Accomplishments: SystemLevel 2Specifications & Design





Beta Prototype

- Fundamental hardware requirements:
  - Level 2 EVSE
  - Cellular network connectivity
  - NEMA 3R rating
- Requires electrical meter in standalone form
- Minimal footprint
- Cable management system required on pole in most cases
- Accessibility via smart phone using mobile web

EMCB is essentially an IoT device!



## Project Accomplishments: Demonstration and Deployment



Alpha Prototype

- EMCB-EV not commercially ready until end of 2020
- Prototype stages:
  - Alpha Prototype: Uses EMCB & standalone Level 2 EMCB
    - Complete: Deploy 2 units on UNC Charlotte campus for public use in May 2020
  - Beta Prototype: Uses EMCB-EV
    - In-Progress: Deploy up to 3 units for public use in City of Charlotte in late 2020/early 2021
    - Working on cable attachment at Duke Mt. Holly
  - Final Design:
    - Working with Eaton to develop licensing agreement
    - UNCC to provide design files for manufacture at US-based facility
- Original SOPO: Deploy 1 unit in the field



## Project Accomplishments: Prototype Demonstration



Energy Production and Infrastructure Center

### Project Accomplishments: Communications Infrastructure



Solution leverages cloud technology, which poses new challenges for implementation



## Project Accomplishments: Understanding Infrastructure



**Transformer Base** 



**Direct-Buried Support** 



Anchor-Base Support



Overhead Poles

- Extreme diversity in terms of available technical infrastructure.
- Key technical questions:
  - How are existing lighting circuits controlled?
  - What is the voltage of the source feeding the pole?
  - Is there space existing in the underground conduit?
  - Is there spare capacity to support Level 2 EVSE charging, and how much?
  - Can power be provided to unit without replacing the pole?
- Four basic types of poles exist:
  - Wooden poles with overhead circuits are the utility's preferred solution
- Developed comprehensive review paper on charging needs in dense urban environments
- Developing a rubric for site evaluation



## Project Accomplishments: Understanding Infrastructure

- Numerous questions exist on policy/community needs:
  - Desired cable management approach
  - Encroachment into right-of-way
  - Permitting process
  - ADA accessibility
  - Signage
- Longer term questions related to Smart City goals
  - Curbside interface and access
  - Business models for EVSE integration and ownership
- Team is engaging with City of Charlotte and Clean Cities Coalition to document









### **Collaboration and Coordination**



## Collaboration and Communication: Roles and Responsibilities

- Project lead (UNC Charlotte)
  - Overall coordination and project management
  - Leading prototype development for hardware and software
  - Coordinating with CCOG, UNCC, and City on deployment
  - Funding: Receiving federal share and providing cost share
- Community outreach (CCOG)
  - Coordinating with the City of Charlotte for deployment issues and marketing
  - Funding: Receiving federal share and providing cost share
- Commercialization partner (Eaton)
  - Supporting UNC Charlotte with commercialization effort & station design
  - Funding: Providing cost share
- Utility partner (Duke Energy)
  - Supporting UNC Charlotte with:
    - Testing services
    - Deployment assistance
    - Understanding street lighting infrastructure
    - System evaluation
  - Funding: Providing cost share
- Deployment partners (UNC Charlotte & City of Charlotte)
  - Pilot site hosts
  - No direct funding
- Communications:
  - Quarterly calls with UNC Charlotte, CCOG, Eaton, and Duke Energy
  - Bi-weekly calls with UNC Charlotte and CCOG
  - Separate bi-weekly calls with UNC Charlotte/Duke and UNC Charlotte/Eaton



# **Overall Market Impact**

- Project directly addresses the need to investigate cost-effective charging station deployment in dense urban and multi-family areas
- Accomplishments to date:
  - Developed and field-deployed alpha prototype units on UNC Charlotte campus
  - Developed alpha version of smart-phone interface
  - Developed report on available literature and studies on needs and costs for urban charging infrastructure
- Upcoming/In Progress:
  - Completing beta prototype development and testing at Duke Energy Mt. Holly Laboratory
  - Reviewing numerous potential locations for installation and documenting technical integration process
  - Thoroughly documenting policy / permitting issues
  - Deployment at up to 3 pilot locations throughout the City of Charlotte with test data for up to one year
- Sustainability:
  - UNC Charlotte and Eaton working on commercialization agreement for EVSEs
  - Eaton directly supporting UNC Charlotte team with industrial design expertise
  - UNC Charlotte to provide Eaton with manufacturing-ready design
  - Commercial deployment in 2021 for parking lots



# Summary

Goals	Develop, deploy, and test a low-cost EVSE solution for retrofit deployment into existing street lighting infrastructure Understand market potential and implementation issues associated with streetlight				
	<ul> <li>integration</li> <li>Establish a path to commercialization</li> </ul>				
Approach	<ul> <li>Select strong set of commercialization, utility, and community partners</li> <li>Develop solution around an emerging IoT technology</li> <li>Develop and test in phased approach (university lab, utility lab, field)</li> <li>Work with utility &amp; community partners to understand implementation challenges</li> </ul>				
Collaborations	<ul> <li>Partners: UNC Charlotte (lead), Centralina Council of Governments, Eaton, Duke Energy</li> <li>Working with UNC Charlotte and City of Charlotte for pilot deployments</li> </ul>				
Accomplishments	<ul> <li>Developed alpha prototype and launched field deployment</li> <li>Designed beta prototype and beginning on-grid testing at Duke Energy laboratory</li> <li>Working to deploy up to 3 stations in City of Charlotte</li> <li>Documenting integration process</li> </ul>				





## Thank You! Questions?



### PI & Presenter: Professor Robert Cox DE-EE008472 | TI091 This presentation does not contain any proprietary, confidential, or otherwise restricted information.



## **Reviewer-Only Slides**



### PI & Presenter: Professor Robert Cox DE-EE008472 | TI091 This presentation does not contain any proprietary, confidential, or otherwise restricted information.

# **Publications and Presentations**

- M. Rahman, B. Papari, J.C. Thill, and R. W. Cox, "Current Status of Electric Vehicle Adoption: A State-of-the-Art Review," *Transportation Research Part D: Transport and Environment* (under review)
- Prototype displayed at Distributech 2020 in San Antonio, Texas.



# **Critical Assumptions and Issues**

- Project schedule:
  - Deployment is on schedule. Unless unforeseen issues arise, team should meet all milestones
    - Covid-19 could pose supply-chain challenges in obtaing UL-approved breakers from Eaton
  - Spending lagged behind because of time taken to negotiate agreements with Duke Energy and Centralina Council of Governments. Spending ticking upwards in 2020 as deployment and commercialization efforts intensify.
- Original project assumed that significant de-risking might be required for structural testing on pole and wireless communications, such issues have not been significant
- Team did not expect Eaton to take as large a role. Duke Energy was the original intended deployment channel. Duke Energy remains heavily involved in the project. Duke envisions themselves as a potential customer for an EVSE solution rather than as a provider of an EVSE solution.
- Covid-19 has not presented major slowdowns. Project was granted a "research exception" by UNC Charlotte Vice Chancellor for Research and Economic Development.
  - Team members can come to campus as needed for laboratory work.

