

Project Overview

Ron Melton, Ph.D., Project Director

Don Hammerstrom, Ph.D., Principal Investigator

Battelle, Pacific Northwest Division

Presented at DOE-OE Smart Grid R&D Peer Review

June 8, 2012

PNWD-SA-9876



What:


- \$178M, ARRA-funded, 5-year demonstration
- 60,000 metered customers in 5 states

Why:

- Quantify costs and benefits
- Develop communications protocol
- Develop standards
- Facilitate integration of wind and other renewables

Who:


Led by Battelle and partners including BPA, 11 utilities, 2 universities, and 5 vendors



Project Basics

Transactive Control Operational objectives

- Manage peak demand
- Facilitate renewable resources
- Address constrained resources
- Improve system reliability and efficiency
- Select economical resources (optimize the system)



Aggregation of power and signals occurs through a hierarchy of interfaces






What is it?

 Transactive control is a distributed method for coordinating responsive grid assets wherever they may reside in the power system.

Incentive and feedback signals

- The incentive signal sends a synthetic price forecast to electricity assets
- The feedback signal sends a consumption pattern in response to the incentive.







Getting services out of loads and assets

- Peak Shaving
- Load Balancing
- Balancing Renewables
- Smart PHEV Charging

Allows enabling assets and responsive loads to collaborate, ensure reliability and save energy!




Benefits already in action

 Peninsula Light Power sharing program saved residents from blackouts during winter 2010-2011

TC keeping the lights on in Fox Island since 2011!

Technical / Project Management Approach





Phase 1: Planning and Initial Design Phase 2: Detailed Design, Implementation, & Installation

Phase 3: Operations Phase 4: Analysis and Reporting



Progress Towards Project Objectives

Project Objectives





Lay the foundation for a regional Smart Grid



Measure and validate costs and benefits



Develop Standards for interoperable Smart Grid



Integrate renewable Energy



Develop and validate two communication





2010	2011	2012		2013	2014	2015			
Phase 1 - Concept Design and Baseline Functionality	Project-level In	ed Design; Subprojec nfrastructure Installat lementation; and Tes Design	ion,	Collection and	st Case Execution, Data I Analysis, and Enhanced Releases	Phase 4 - Technical Reporting and Project Closeout			
Objective 1: Cres	to foundation of a	austainahla vasianal		·		:			
smart grid	te roundation of a	sustainable regional							
Siliait griu					<u> </u>				
Objective 2: Deve and control infras		le communication		Validate an intero infrastructure	perable communication and	control			
			T			:			
	Objective 3: Measure and validate smart grid cost and benefit								
		:	I	:	:	:			
Objective 4: Cont	ribute to the devel	opment of standards	for trai	nsactive control					
Objective 4: Cont	ribute to the devel	opment of standards	for trai	nsactive control	<u> </u>	:			
	:	opment of standards	•	nsactive control	:	:			



Pacific Northwest
SMART GRID
DEMONSTRATION PROJECT


	Transactive Control	Reliability	Conservation /Efficiency	Social	Totals
Avista Utilities	4	3	5	3	15
Benton PUD	1	1	1	0	3
City of Ellensburg	1	0	8	0	9
Flathead Electric	6	2	0	0	8
Idaho Falls Power	8	2	3	3	16
Lower Valley Energy	3	2	6	1	12
Milton-Freewater	3	0	0	0	3
NorthWestern Energy	4	1	3	1	9
Peninsula Light	2	1	1	0	4
Portland General					
Electric	4	1	1	2	8
UW/Seattle City Light	5	0	3	0	8
Totals	41	13	31	10	95

Select Events 2012



SMART GRID

DEMONSTRATION PROJECT





Lessons Learned / Surprises / Challenges



 Many examples of vendors over-promising & und delivering



- Getting access to needed data much harder than expected
- Each utility has different challenges in relating "smart grid" to their customers meet people where they are
- Customer questions:
 - How will this benefit me?
 - What will it cost me (time and/or money)?
- Students are pushing for adoption
- Customers are more tolerant of cold than heat
- R&D with deployment to utilities is challenging!

Unexpected Benefits to Date



- Fox Island recovery from unexpected underwater feeder failure benefited from load controls
- Cold-load pickup facilitated by load controls
- Cyber security trickling throughout the utility in a positive way
- Truck rolls surprisingly reduced with remote connect / disconnect capability
- Better integration / collaboration across internal organizations of the utility
- Dedicated customer representative has helped educate consumers make them more aware of the challenges of operating a utility

Pacific Northwest SMART GRID DEMONSTRATION PROJECT

To Recap - Why is BPA Involved?

- Opportunity to leverage smart grid assets installed by regional utilities using an innovative incentive structure
- Extend and validate the concepts demonstrated in Oly-Pen project
 - Flexible approach to integrating BPA's and Utility's operational objectives and responsive resources
 - Standardized, interoperable approach to facilitate broad application
- Prove and refine the transactive approach
 - Gather regional cost-benefit information
 - Understand scale-up challenges and opportunities
- Continue the region's legacy of national leadership in power system innovation

2015 and beyond



- At the end of the demo project:
 - ~ 100 Megawatts of distributed responsive assets engaged
 - Transactive control validated as a means of balancing intermittent renewable resources
 - Base of smart grid equipment installed at 11 utilities
- Beyond the demo project
 - Scale up to engage additional responsive assets
 - Transition from R&D to operations
 - Operationalize for balancing authorities (regional value)
 - Further deployment with energy service providers to enhance value to their operations (local value)



For further information

Dr. Ron Melton
ron.melton@battelle.org
509-372-6777

www.pnwsmartgrid.org

- "Annual Report"
- Quarterly newsletters
- Participant summaries
- Background on technology