

# Temporary Bridging Agents for Use in Drilling and Completions of EGS

May 18, 2010

Principal Investigator – Larry Watters Presenter – Jeff Watters CSI Technologies LLC

Track Name

#### Overview



- Project Title Temporary Bridging Agents for Use in Drilling and Completion of Engineered Geothermal Systems
- Timeline
  - Project Start Date May 1, 2010
  - Project End Date May 1, 2011
- Budget
  - Total Project Funding \$1.352 Million
  - DOE Share \$766,600
  - Awardees share \$566,600
- Partners
  - AltaRock Energy
  - University of Utah

## Relevance/Impact of Research



### Objective of Project:

Develop materials or systems that bridge to seal or divert flow from fractures existing while drilling EGS wells or in injection formation and that eventually decompose thereby leaving the fractures unsealed and undamaged

#### Problem:

Loss of drilling fluid to fractures during drilling process

High cost of drilling fluid

Potential damage to injection formation

Loss of stimulation fluid to initial fractures opened during hydraulic stimulation of EGS formation

Unable to open up new fracture system

## Relevance/Impact of Research



The commercial success of EGS requires:

Injection formation be drilling with fluids that allow adequate hole cleaning and minimize the losses. The volumes of fluid losses can be excessive that the financial impact could be excessive. These losses must be controlled during drilling

That large surface areas of reservoir formation are accessible to injected fluids so that hear transfer from the formation can be maximized. Without the ability to perform multiple fracturing treatments the commercial success will be limited.

If successful the development of these diverter created fracture systems could multiply the amount of produced steam from said EGS wells

# Scientific/Technical Approach



### Focus on developing materials that:

Seal on the fracture face with only moderate leakage of fluid past materials during drilling and fracturing

Combination of particle sizes and sealing efficiencies (plastic deformation) to seal for the duration of time required but also maintain seal at the temperature seen in these applications

Materials must degrade at the appropriate time at elevated temperature without leaving any damage to the fractures in the injection formation

# Accomplishments, Expected Outcomes and Progress



Expected outcomes:

Identification of the candidate materials

Test sealing of various materials in specially developed laboratory equipment

Static slot tester

Measure diversion efficiencies for different fracture apertures Develop empirical correlations of PSD and Diversion Efficiency

Dynamic Flow Diversion Reactor

Dynamic measure of deposition and sealing efficiencies

# Accomplishments, Expected Outcomes and Progress



Expected outcomes continued:

LCM and Diverter durability and degradation kinetics under static condition

Long term degradation tests in static conditions submerged in water

Long term degradation tests in simulated fracture scenario under differential pressure and application temperature

Focus will be on degrading but also potential damage to the fracture network

# Project Management/Coordination



The project is divided by the following:

CSI will perform screening, develop correlations, perform long term studies on sealing and degradation kinetics


EGI (U of U) will design lab-scale dynamic apparatus and conduct tests to confirm initial static tests

AltaRock will implement viable material candidates in field applications

# Project Management/Coordination

| ID | Notes         | Name  | Total Cost     |
|----|---------------|---|----------------|
| 1  | Phase 1       | Material Identification, Initial Laboratory and Field Studies |                |
| 2  | Task 1.0      | Identification of Candidate Materials or Processes            | \$50,973.74    |
| 3  | Task 2.0      | Preliminary Screening Materials                               | \$203,797.26   |
| 4  | Task 3.0      | Fabricate Slot Tester Apparatus                               | \$101,796.01   |
| 5  | Task 4.0      | Optimize PSD for Different Fracture Apertures                 | \$110,283.66   |
| 6  | Task 5.0      | Material Degradation Kinetics at HTHP Static Conditions       | \$192,573.22   |
| 7  | Task 6.0      | Develop Lab-Scale Dynamic Flow Diversion Reactor              | \$231,421.99   |
| 8  | Task 7.0      | Field Test Successful Materials                               | \$460,751.67   |
| 9  | Project Total |   | \$1,351,597.55 |

# Project Management/Coordination



### **Future Directions**



### Future plans for project:

Determine new materials for potential application

Test materials as to set performance characteristics

Select materials to go to next level of testing

Develop correlations to predict seal and durability in real well scenario

Get materials made in large enough quantities to conduct field job

Use material in real well scenario

## Summary



- Project to investigate sealing materials for both Drilling and Fracturing in EGS wells underway
- Potential materials being evaluated as we speak
- Most of project still left to be performed
- Preliminary results have identified several new materials that meet the criteria for application
- Many companies are interested in this work and CSI has been contacted by many manufacturer to supply materials to test