


CO₂ Heat Pump Water Heater

2014 Building Technologies Office Peer Review







U.S. DEPARTMENT OF ENERGY

Energy Efficiency & Renewable Energy

Kyle Gluesenkamp, gluesenkampk@ornl.gov Oak Ridge National Laboratory

Project Summary

<u>Timeline</u>:

Start date: Oct 1, 2009

Planned end date: Sep 30, 2015

Key Milestones

1. Optimize wrap-around coil; Dec 2013

2. Achieve EF>2.0; March 2014

Budget:

Total DOE \$ to date: \$2,147k

Total future DOE \$: \$200k

Target Market/Audience:

Residential electric water heating

Key Partners:

GE Appliances

CRADA partner



Project Goal:

Develop CO₂ heat pump water heater that meets Energy Star standards for HPWHs at an installed cost that will enable widespread adoption in US residential market.



Purpose and Objectives

Problem Statement:

- Heat pump water heaters can save significant energy, however they currently use refrigerants with high GWP.
- Low-GWP heat pump water heaters based on CO₂ exist, but first cost of existing products is too high to enable widespread adoption in the US residential market.

Target Market and Audience:

Electric water heaters currently use 1.4 Quads/yr.

Impact of Project:

- CO₂ heat pump water heater at price point viable for the US residential market
- Technical potential of increasing EF from 0.92 to 2.0 is savings of 0.8 Quads/yr
- Using CO₂ as a refrigerant, this can be done with near-zero GWP and zero ODP



Approach

Approach: Utilize low cost components; maintain Energy Star performance

- Single-speed compressor, single expansion device
- Optimized wrap-around gas cooler instead of double-wall external gas cooler

Key Issues: Cost of CO_2 components, thermodynamic characteristics of CO_2 , need for careful gas cooler wrap-around coil design

Distinctive Characteristics: Heat pump water heater with natural refrigerant (inexpensive with GWP=1)

Characteristic	External heat exchanger	Wrap-around heat exchanger
Cost	High	Low
Water fouling	Significant challenge	None
Water pump	Required	Not required
Additional tank water inlet/outlet ports	Required	Not required
Performance	Good	? Needs research



Approach


Context:

- EcoCute CO₂ water heaters (a few million units in Japan, Europe and Australia)
 - First cost: ~6,000 \$US, plus installation (4-5 kW heat pump heating capacity)
 - Variable speed compressor
 - External heat exchanger and circulation pump; stratified tank
 - Electronically controlled expansion valves and sophisticated controls
- HFC-based HPWHs
 - Available in US from various manufacturers, ~\$1,000 (2-3 kW heat pump heating capacity)
 - Wrap-around condenser coil; non-stratified tank
 - Max water temperature limited



Approach

This project:



EcoCute:





Additional elements:

- Split system (high installation cost)
- Inverter-driven compressor
- Electronic expansion valves
- Variable speed pump
- External gas cooler




Accomplishments: Constructed coupled tank-heat pump design tool in ANSYS to evaluate wrap-around coil designs











Accomplishments: Validation of design tool


- Thermal conductivity of CFD mesh's thermal paste treated as free variable (representing contact resistance)
- Experimental data from second WAGC (improved construction)
- Good agreement found at 0.4 W/m-K







Accomplishments: Evaluation of designs with CFD




Design cases



CO2 Coil Height

Accomplishments: Progressive improvements in wrap-around gas cooler (WAGC)



Temperature approach at the pinch: ~10 K



Temperature approach at the pinch: ~5 K



Temperature approach at the pinch: ~2.5 K



Lessons Learned:

- CFD validation is not a straightforward problem; especially with a dynamic system coupled with nonlinear boundary condition
- CO₂ system components are not readily available, e.g. low cost compressors at desired capacity

Accomplishments:

- Development of validated CFD model
- Fabrication and validation of optimized wrap-around gas cooler design
- Achieving EF of 2.1 with prototype CO₂ HPWH based on low cost components (single speed compressor, single XV, wrap-around gas cooler)

Market Impact:

- We have demonstrated a more affordable path to ENERGY STAR rated CO₂
 HPWH (low GWP no direct environmental impact)
- Sentech/SRA market assessment showed an estimated 37,000 112,000 total unit shipments one year following commercial viability, and 72,000 180,000 total unit shipments five years following commercial viability to account for 0.037 Quads in annual national primary energy savings

Awards/Recognition:

None yet



Project Integration and Collaboration

Project Integration:

- Participate in "2013 ACEEE Hot Water Forum"
- Discuss with industry partners
- Participate in different venues and activities like the DOE water heating roadmap workshop

Partners, Subcontractors, and Collaborators:

- General Electric Appliances
 - Natarajan Venkatakrishnan, Director Advanced Technologies
 - Craig Tsai, Pl

Communications: Publication in progress for wrap-around coil CFD design tool



Next Steps and Future Plans

Next Steps and Future Plans:

- Evaluate cold climate performance
- Evaluate performance at different air temperatures without high side pressure management
- Develop next generation prototype
- Optimize design for fixed charge



REFERENCE SLIDES



Project Budget

Project Budget: DOE total \$2,347k FY2010 - FY2015

Variances: None

Cost to Date: \$2,010k through Feb 2014

Additional Funding: None expected

Budget History								
	– FY2013 ast)		014 rent)		015 nned)			
DOE	Cost-share	DOE	Cost-share	DOE	Cost-share			
\$1,797k	*	\$350k	*	\$200k	*			

^{*} In-kind contribution from CRADA partner – exact total is confidential information



Project Plan and Schedule

- Delays in FY2013 under transition of ORNL PI and CFD validation issues
- Go/no-go decision point met with EF>2.0

Project Schedule												
Project Start: Oct 1, 2009		Completed Work										
Projected End: Sep 30, 2015		Active Task (in progress work)										
	•	Milestone/Deliverable (Originally Planned)										
	Milestone/Deliverable (Actual)											
		FY2013 FY2014				FY2	FY2015					
Task	Q1 (Oct-Dec)	Q2 (Jan-Mar)	Q3 (Apr-Jun)	Q4 (Jul-Sep)	Q1 (Oct-Dec)	Q2 (Jan-Mar)	Q3 (Apr-Jun)	Q4 (Jul-Sep)	Q1 (Oct-Dec)	Q2 (Jan-Mar)	Q3 (Apr-Jun)	Q4 (Jul-Sep)
Past Work												
Q2 Milestone: Validated CFD model		•			>						Т	
Q4 Milestone: Wrap-around coil design tool					•							
Q1 Milestone: Fabricate wrap-around coil					•	•						
Q2 Milestone: EF>2.0						•	•					
Current/Future Work												
Q3 Milestone: Design for meeting targets							*	>				
Q4 Milestone: Next generation prototype									>			