

# **Development of an Improved Cement for Geothermal Wells**

Project Officer: Eric K. Hass Total Project Funding: \$2,154,238

May 13, 2015

Principal Investigator George Trabits Trabits Group, LLC

High Temperature Tools, Drilling Systems

## Relevance/Impact of Research



#### **Project Objective**

 Develop a novel, zeolite-containing lightweight, high temperature, high pressure geothermal cement, which will provide operators with an easy to use, flexible cementing system that saves time and simplifies logistics.

#### **Impact of New Cement Development**

- Eliminate the requirement to "sterilize" pumping equipment before use.
- Eliminate the need to foam the slurry to achieve lightweight qualities.
- Eliminate incompatibility issues in the selection of retarders and accelerators.
- Provide predictability and minimize the effect of down-hole temperature fluctuation.
- Facilitate the development of geothermal resources in remote locations.



#### Methodology

- Build on existing zeolite-containing cement technology for low temperature, weak formation applications.
- Systematic, scientific approach on trial cement blends to consider the variables of:
  - Zeolite type
  - Zeolite particle size
  - Zeolite percentage by weight of cement
  - Additives for thermal stability and resistance to carbonation
- Clear and concise performance characteristics provide a systematic method for initial screening, second stage development and ultimately for the final stage of cement development.
- Involvement of industry for guidance on actual cementing practices.
- Solicit industry expert peer review on research methods and results.
- A logical progression of scientific study results in five Tasks that lead to realistic project milestones and go / no-go decisions points.



#### TASK 1 - RESEARCH

- Literature Search
- Geothermal Cementing Practices and Constraints
- Mechanisms of Geothermal Well Failure

#### TASK 2 - DESIGN

- Compile Research Findings
- Modification of Project Tasks 3 and 4

#### TASK 3 - DEVELOP

- Zeolite Sample Acquisition
- Zeolite Type Confirmation
- Zeolite Particle Size Preparation
- Initial Screening of Cement Formulations

#### TASK 4 - TEST

- Second Stage Cement Development
- Final Stage Cement Development

#### TASK 5 - DEMONSTRATE

- <u>Laboratory Scale Demonstration</u>
- <u>Logistics and Ease of Use Field</u>
   <u>Demonstration Chena Hot Springs</u>
   <u>Resort</u>
- High Temperature EGS Well
   Demonstration Ormat Technologies



# Zeolites Used in Development

- Four different zeolites were evaluated.
  - Clinoptilolite (California)
  - Clinoptilolite (New Mexico)
  - Chabazite (Arizona)
  - Ferrierite (Nevada)
- One thousand pounds of each zeolite type was collected to ensure repeatability and sufficient volume for all Screening and Second Stage Cement Development.
- Each sample type was field crushed to a uniform minus US 8 Mesh product.





# **Zeolite Preparation**

- Following XRD, XRF and SEM confirmation of zeolite type three hundred pound bulk samples were shipped to CCE Technologies for preparation.
- Micronized using Jet Mill Technology.
- Prepared sizes with 80% in range:
  - 5 micron
  - 10 micron
  - 44 micron





#### **Developed Cement Performance Criteria**

- Thermal stability with little strength retrogression to 300° C.
- Tensile strength to withstand temperature and pressure changes.
- Low-density, low-viscosity slurries with low equivalent circulating densities (ECD) without the need for air or nitrogen foaming.
- A single cement blend allowing density adjustments without adversely affecting slurry properties to eliminate the need for separate blends for lead and tail slurries.
- Resistance to carbonation.
- Accurate downhole densities throughout cement placement without significant changes in viscosity.
- Water absorption capacity without retaining free water.
- Good bonding to casing and formation.
- Adequate compressive strength.



Original Planned Milestone/ Technical Accomplishment		Actual Milestone/Technical Accomplishment	Date Completed
Task 1	Research	Completed as planned	July 2011
Task 2	Design	Completed as planned	Sept. 2013
Task 3	Develop	Completed as planned	Oct.2012
Task 4	Test	Completed as planned	Sept. 2013
Task 5	Demonstrate	Low temp, ease of use completed	Jan. 2015

#### Variances

- Industry partner ThermaSource failed to participate as committed resulting in loss of cost share and lab testing equipment availability.
- Schedule slippage resulting from delays in the fabrication of Chandler Engineering specialized high pressure/high temperature cement testing equipment.
- Suitable high temperature demonstration well did not become available before the end of the Period of Performance.

8 | US DOE Geothermal Office eere.energy.gov



### Blended Zeolite-Containing High Temperature Cement


Mechanical and material properties at 300°F and 400°F.

Temp	Cure	Density	Density	$q_{\mathrm{u}}$	Е	ν	Tensile	Thermal	Permeability
(°F)	time	(ppg)	$(g/cm^3)$	(psi)	(ksi)		strength	conductivity	(mD)
	(days)						(psi)	(W/m°C)	
300	2	13.5	1.61	6484	1243	0.33-	990	1.11	0.005
						0.38			
300	3	13.5	1.61	5533	1112	n/a	572	n/a	n/a
400	5	13.5	1.62	3205	1185	n/a	341	1.66	0.003

Blended High Temperature Zeolite-Containing Cement is lightweight with high compressive strength, good ductility and tensile strength with extremely low permeability. This dry blend was intended for use in an Ormat well.



#### Carbonation Resistance



Three week cure in brine/ $CO_2$ . Right sample is treated with phenolphthalein. No color change indicates pH < 10.

Permeability for Ferrierite and Clinoptilolite before and after brine/CO <sub>2</sub> exposure.  Slurry Density - 13.5ppg							
Ferrierite Clinoptilolite							
	Initial	1 week	3.5 week	Initial	1 week	3.5 week	
Permeability (mD)	0.0031	0.010	0.012	0.003	0.012	0.010	

10 | US DOE Geothermal Office



#### How Do We Make This Commercial?

Problem - Micronizing zeolite for a dry blend is expensive.

Solution - Intergrinding Cement Clinker and Whole Rock Zeolite

#### Method

Hot cement clinker and "fist" sized zeolite are blended together in the final grinding mill at the cement plant in a predetermined ratio. Zeolite being softer than clinker preferentially grinds to a smaller particle size.

#### **Benefits**

- Economic gain of replacing a higher cost clinker with a lower cost zeolite.
- Lowering the resulting interground cement environmental cost associated with greenhouse gases during Portland manufacture.
- Increased physical properties of the zeolite intergrind being improved strength, lower permeability and resistance to carbonation.




# Intergrind Number One Completed Lehigh Southwest Tehachapi Plant

1,000 Ton Production Run 60% Class G Clinker 40% Clinoptilolite Zeolite

Blaine = 7640 cm2/g

#### **Particle Size Distribution**







#### **Interground Cement Properties**

- Optimum density 12.73 ppg
- Water requirement 7.214 gal/sk
- Yield 1.469 ft<sup>3</sup>/sk
- Bulk density 79.7 lb/sk

#### Interground Cement Performance

**Thickening Time** 

40Bc	1:19	70Bc	0Bc 2:05		2:29	
Rheology	300 rpm	200 rpm	100 rpm	6 rpm	3 rpm	
125°F	102	97.5	82.5	32.5	16.5	

#### Compressive Strength

8 hours	11:31	12 hours	24 hours	48 hours
319 psi	500 psi	537 psi	1262 psi	1581 psi

13 | US DOE Geothermal Office eere.energy.gov

#### **Future Directions**



# Intergrind Number Two Eagle Materials Nevada Cement Plant

Planned Full Scale Run 65% Type I/II Clinker 35% Ferrierite Zeolite





### Summary Slide



- 1. Successfully developed zeolite-containing lightweight, high temperature, high pressure well cement suitable for geothermal applications.
- 2. Identified and bench scale tested Intergrinding as an economical method for the production of zeolite-containing cement that...
  - Allows for density adjustments within a single blend without affecting slurry properties.
  - Eliminates the need for separate blends for lead and tail slurries.
  - Provides thermal stability with the addition of silica for little or no strength retrogression.
  - Provides resistance to carbonation to maintain compressive strength and low permeability.
- Completed full scale cement plant production run of Interground Lightweight Variable Density Zeolite-Containing Cement as commercial proof of concept.