

Directional Measurement-While-Drilling System for Geothermal Applications

Project Officer: Bill Vandermeer Total Project Funding: \$ 5 M

May 11, 2015

Kamalesh Chatterjee EE0005505
Baker Hughes


Track 3 EGS1 - High Temp Tools, Drilling Systems

This presentation does not contain any proprietary confidential, or otherwise restricted information.

Relevance/Impact of Research



A Directional Drilling System (DDS, EE0002782) and directional Measurement-While-Drilling system (MWD, EE0005505) for geothermal applications will operate in hard rock at depths as great as 10,000 meters and temperatures as high as 300°C.



- Commercial DDS tools are functional up to 175°C/200°C
- Aligned with GTO R & D goals
 - > Directional Drilling of EGS wells at high temperature.
 - Drilling cost a significant part of total budget in geothermal wells.
 - > MWD information needed for precise well placement.


Relevance/Impact of Research



- Prototype directional MWD system for geothermal
 - Deliverables: 3 prototype tools
 - Temperature up to 300°C for 50 hours
 - Hard rock, depths to 10 km (pressure 20 kpsi)
 - 6 ¾ inch tool for 8.5 inch diameter hole
- Major technology modules:
 - 175°C Directional navigation package (electronics and sensors)
 - Telemetry module (pulser)
 - Power module (alternator)
 - Active cooling system (from 300°C to 175°C)

Scientific/Technical Approach Proposed system concept





Cooling system - flask, valve, evaporation control, evaporating fluid, absorbing media

 Pulser
 Alternator
 Electronics
 Directional package
 Water tank
 Zeolite

Scientific/Technical Approach Alternate system concept




- Silicon on insulator 1 μm wafer technology may go up to 275°C/300°C – inadequate for powerful DSP or FPGA
- No availability of sensors at 300°C
- Only Si-C power devices are available, not controller ICs
- Memories limited at 225°C

Cooling system with flask is required

Compressor/Condensation based cooling system inside a flask at drilling vibrations and temperatures has to be an independent project


Proposed active cooling system





Dewar flask challenges






Estimation of heat leakage

Inside the dewar flask





Active cooling demonstration








Evacuation & P-Sensor Zeolite reservoir

Safety Valve & P-Sensor water reservoir

T-Sensors, heating resistors




At Celle, Germany facility
Other funding sources –
GEBO, Lower Saxony program

Outside 250°C Inside 150°C For 50 Hours

Different Dewar flask concepts








Upper side - upper disc

Lower side – upper disc



Upper side – lower disc


Weld seam in lower disc



10 | US DOE Geothermal Office

Pulser and Alternator concepts






Elastomer-free control valve in pulser Ceramic (or Inconel) sleeve in alternator

Directional electronics





Accomplishments, Results and Progress



- Concept evaluation (Phase I) complete. Confident about the feasibility of the proposed system. Active cooling concept has been demonstrated in a laboratory prototype tool
- Significant progress in the detailed design of directional measurement package. We are upgrading an existing design to 175°C operation. The directional unit to be ready in Q3.
- Laboratory tests with available wireline flasks has been conducted and thermal leakage loads has been studied to determine the cooling system capacity.
- Detailed design of high temperature pulser and alternator is underway. FEA of the Pulser design has been performed and crucial parameters like plunger force and current has been studied. FEA of the alternator has been performed to aid in design.

Original Planned Milestone/ Technical Accomplishment	Actual Milestone/Technical Accomplishment	Date Completed
Concept evaluation Phase I	Completed	March 2014
Phase II approval		Jan 2015
Phase II work started		April 2014

Future Directions



- Detailed design of each subsystem started. The subsystems are: pulser, alternator, dewar flask, directional electronics package, water chamber, zeolite tank.
- Complete the detailed design by September.
- Order long lead components by August.
- Subsystem prototypes ready, start testing in the laboratory by 2015 end.
- Complete design iteration based on the outcome of laboratory testing and build a prototype tool, test it at BETA (Baker Experimental Test Area) by October 2016, field trial November 2016.

Milestone or Go/No-Go	Status & Expected Completion Date
Phase II approved	January 2015
Subsystem prototypes ready	November 2015
Prototype tool	July 2016
Field trial	November 2016

Mandatory Summary Slide



- Phase I: Feasibility and Concept evaluation complete.
- Prototype demonstration of active cooling in laboratory.
- Adsorption based active cooling enables the use of robust 175°C electronics inside a flask. The cooling system cools from 300°C ambient to 175°C.
- Significant progress made in the upgrade of directional electronics unit.
- Detailed design of 300°C temperature pulser and alternator started.
- Laboratory prototype of subsystems expected in Q4 2015, Prototype tool ready in Q3 2016.