

### CSP Program Summit 2016

# Acciona Power Plant Hydrogen Mitigation Project

CRADA partners: NREL & Acciona Energy

Project Duration: 2 years

Project Budget: \$1.4M, 50/50 cost share

Greg Glatzmaier

Senior Engineer

National Renewable Energy Laboratory


#### **Problem to Address**

Decomposition of heat transfer fluid (HTF) in parabolic trough power plants generates hydrogen that circulates in the collector field

Free-radical polymerization of biphenyl



Hydrogen permeates into receiver annuli eventually causing a significant decrease in receiver performance and power plant output



### **Value Proposition**

- Process removes hydrogen from the power plant expansion tanks to control hydrogen levels in the circulating heat transfer fluid
- Process has not capacity limits for removing hydrogen getters have limited capacity and eventually saturate
- Creates opportunity to decrease receiver cost by eliminating:
  - barrier coatings
  - getters,
  - xenon capsules
- Ultimately results in increased plant performance and greater profitability

## **Project Objectives**

Overall objective: design, implement, and evaluate a full-scale hydrogen mitigation system at Nevada Solar One (NSO)


- Develop instrumentation to measure the hydrogen partial pressure in the HTF expansion tank headspace gas
- Demonstrate reverse permeation of hydrogen from in-service receivers and performance improvement
- Design and process that purges hydrogen from the NSO expansion tank and maintains HTF hydrogen to target level
- Evaluate system installed costs and estimate payback period for installed system due to increased plant performance
- Implement system at NSO (Phase 2)
- Evaluate system performance at NSO (Phase 2)

#### **Task Structure**

- Task 1.1: develop hydrogen sensor to measure expansion tank hydrogen partial pressure
- Task 1.2: track increase in performance of in-service receiver due to long-term heating
- Task 1.3: specify and design a purge system for removing hydrogen from the NSO expansion tanks
- Task 1.4: estimate installed costs and payback period for installed hydrogen purge system


#### **Task 1.1 Sensor Development**

Establish equilibrium pressure across selective membrane equal to the hydrogen partial pressure in the gas mixture




### **Task 1.1 Sensor Development**

Hydrogen partial pressure in gas mixture determined by measuring pressure response on the permeate side of the selective membrane.



### **Task 1.2 Receiver Heat Loss Testing**

Long-term receiver heating demonstrates hydrogen reverse permeation when HTF has low dissolved hydrogen.




### **Task 1.2 Receiver Heat Loss Testing**

- Long-term heating performed with NREL heat loss test stand
- Absorber temperature during heating is 375°C 385°C
- Observed reduction in heat loss and improved receiver performance



**Heat Loss Test Stand** 





Heat Loss vs. Daily Heating

### **Task 1.3 Full-Plant Modeling**

#### Full Plant Model Features

- Hydrogen material balances on all plant components receivers, cross-over piping, hot & cold header sections, steam train components, expansion tanks, and power block piping
- Material balances for account for:
  - influx due to dissolved hydrogen in HTF flow into component
  - efflux due to dissolved hydrogen in HTF flow out of component
  - efflux due to hydrogen permeation across component walls
  - hydrogen generation due to HTF degradation






### **Task 1.3 Process Specification & Design**

2-step process to remove hydrogen from expansion tank headspace:

- separate hydrogen from headspace gas mixture
- oxidize hydrogen to water vapor before discharging to ambient



### **Task 1.4 Economic Analysis**

- Evaluate installed system costs and operating expenses
- Estimate payback period for installed system based on increased plant performance and electricity production
- Installed system cost for hydrogen purge system needs to pay back within 18 months

#### **Path to Market**

- Phase 2 objectives:
  - install mitigation system at Nevada Solar One
  - demonstrate operation and validate system performance
- Currently working to identify second CRADA partner to establish business unit to commercialize process