

National Museum of African American History and Culture



Brenda Sanchez, FAIA, LEED AP BD+C
Sr. Architect/Sr. Design Manager
Smithsonian Institution



"To help Americans remember, and by remembering stimulate a dialogue about race to help foster a spirit of reconciliation and healing.

To be a beacon for the nation that reminds us of what we were, what challenges we still face, and to point us toward what we can become"

Dr. Lonnie Bunch, Director National Museum of African American History and Culture



- 1865 End of the Civil War 1915 Civil War veterans 1965 Voting Rights










History: Enabling Legislation

December 16, 2003



- Accommodation/Flexibility
- Urban planning context
- Project Cost/Constructability
- Compatibility; Visitation Potential
- Design opportunity/constraints
- Economic opportunities
- Access, Transportation, proximity
- Cultural & Historic Resources
- Environmental/Ecological Factors
- Safety, Security & Risk Management Factors
- Utilities




History: Site Selection

January 2006

- 2004: Smithsonian Institution Board of Regents appoints a 19 member National Museum of African American History and Culture Council
- March 2005: Dr. Lonnie bunch is named Director of the National Museum of African American History and Culture
- January 2006: The Board of Regents selects the Monument Site for the new Museum.









Early Planning Efforts: Budget

2003 - 2015


- Enabling legislation stipulated 50% federal and 50% non-federal funds
- Council starts fundraising efforts
- Budget: \$540M
 - \$270M Federal appropriations from FY2005 through FY2015
 - \$270M Trust fund contribution
 - Includes:
 - Planning and Design
 - Construction and Construction Management
 - Commissioning
 - Exhibit Design and Fabrications



Early Planning Efforts: Schedule

2006

- Goal: Opening 2015
- Concurrent Activities:
 - Public Consultation
 - Historic Preservation Reviews
 - Environmental Impact Statement
 - Building a Collection
 - Master Facilities Planning
 - Exhibit Programming
 - AE Competition and Selection
 - Building Design
 - Gas Line Relocation
 - Selection of Constructor-CM@Risk
 - Construction
 - Commissioning
 - Exhibit Design
 - Exhibit Fabrication and Installation
 - Off-Site Collection Facilities






Early Planning Efforts: Public Consultation Begins 2006





Early Planning Efforts: Historic Preservation and EIS 2006 - 2011





Early Planning Efforts: Public Engagement

2006



Public Engagement

with Stakeholders and General Public

- American Association of Museums
- Organization of American Historians
- National Association of Counties







Early Planning Efforts: Collections Building

2007 - 2008







PRE-DESIGN: Programming

2007-2008

Master Facilities Programming:


- People
- Collections
- Facilities



Freelon Bond: The Freelon Group, Davis Brody Bond, Lord Cultural Resources and Amaze Design

Responsible for:


- Visitation Estimates
- Audience Research
- Public Engagement and Outreach
- Exhibition Master Planning
- Collections and General Museum Requirements
- Site Analysis
- Facilities Program





PRE-DESIGN: EIS Tier 1 - Design Alternatives


2007-2008





PRE-DESIGN: EIS Tier II & Section 106

2008 - 2011



Over 5 years of Consulting Parties and Agency Meetings Development of Design Principles to Guide design Sensitivity to Urban Context Mall Context Washington Monument Context Archeology and Photo Documentation completed

Results:

- Size of Building above ground; 216'x216'
- Height of Building < Commerce Building
- Setback increased to the South for Monument view while respecting McMillan setbacks
- Site/Landscape; fluid movement across site
- Pavilion on a glass base for at grade views
- Corona, porch, water feature designs and materials refined





PRE-DESIGN: Design Competition

2009



"We are not building the Model"

- 60% Design
 Demonstrated understanding of mission, design principles and physical design parameters, program, building technology, security and sustainability.
- 40% Teamwork
 Design process, methodology collaborative process and contribution of all team members.





PRE-DESIGN: Design Competition

2009



Devreaux and Purnell



Freelon Adjaye Bond/SmithGroup



Diller Scofidio Renfro



Moody Nolan/Antoine Predock



Foster and Partners

Smithsonian Institution



Safdie Architects



DESIGN: Design Selection

2009



Place of Inspiration reflecting African American Resiliency and Spirituality

Three Irreducible Elements: Corona

Porch

Color/Materiality

Four Pillars: Learning

American History

International Considerations

Collaboration














Starts: January 2010


Presentations to Agencies: 2010 - 2011

Approval of Concept Design: March 2011



DESIGN: Design Alternatives

2010 - 2011






DESIGN: Site Studies: CFA, NPS

2010 - 2011


















Figure 1 Primary components of corona structure in all three schemes

Main Elements:

- Four Pillars (4 Cores)
- Deep steel trusses spanning between the four cores in the corona
- Corona floor framing and slabs
 supported by the deep steel trusses
- Façade structure supported at roof level
- Two below-grade floors
- Foundations
- Materials: Steel above grade and Concrete below



Sustainability "is not a line item"

Main Goal:

- 1. Passive Design
- 2. Maximize potential of Corona -
- 3. Develop a comprehensive water management strategy
- 4. Understand energy drivers for the Museum
- 5. Specify simple systems that can be maintained efficiently (geothermal later explored but discarded).
- 6. Use daylight

Obtain LEED GOLD at a Minimum!!





Hardscape Gatherings in the Landscape


Shrubs and Perennial Plantings

Views approaching Constitution Avenue from 14th Street





DESIGN: Flood Control 2010 - 2011




Years Later: Final Installation





DESIGN: Presentations to CFA and NCPC

2011





Schedule:

Opening Date established: November 2015

Funding:

First Federal Capital appropriation 2005
Last Federal Capital appropriation 2015
Continuous Fundraising in unpredictable amounts

Challenge:

Find Construction Delivery Method that would allow us to meet the schedule and meet commitments to the Contractor

Solution:

Design team to provide Construction Documents in packages to accelerate schedule and correspond to the funds available.





CHALLENGE: Construction Delivery Methodology

2010 - 2011

| Project Deliver | | | |
|------------------|--|---|--------------------------------|
| Contract Vehicle | Positive Attributes | Negative Attributes | Mitigation Strategies |
| Design | en | 0 1 1 1000/ 1 1 51 | |
| Build | Eliminates most errors and omissions | Owner does not have 100% control of the | Provide a good set of design |
| | Faster design (subcontractor input) | design of the project | criteria and standards |
| | Facilitates fast-tracking (fastest del.) | Owner does not have control of the fix | Req. DB to submit a systems |
| | Facilitates early procurement of long lead | to deal with errors and omissions | narrative with proposal |
| | Items | DB has incentive to reduce quality to gain | Limit the amount of shared |
| | Single source of responsibility (Adm) | additional savings | savings |
| | Greatest flexibility for changes | | Aggressive QA by owner reps |
| | Better integration of proprietary systems | | Req. BIM |
| | Under a GPM - greatest flexibility for cost | | Adequate contingency funds |
| | and budget management | | |
| | Incentives to deliver the project below cost | | |
| | (guarantee maximum price / share savings | | |
| | clauses) | | |
| | Partnering relationship | | |
| CM at Risk | Reduces errors and omissions | Limited or no opportunity for fast tracking | Req partnering sessions |
| | Predictable project costs | Limited flexibility | Req. ADR |
| | Flexibility to pursue a design - bid - build | Some owner responsibility for errors and | Req. BIM |
| | strategy | omissions | Adequate contingency funds |
| | Some incentive to deliver the project | Limited subcontractor input in design | |
| | below cost (GMP -shared savings) | | |
| | Owner has 100% control of design | | |
| | Owner has control of fix to deal with | | |
| | errors and omissions | | |
| | Partnering relationship | | |
| | Faster project delivery (no sol.for GC req.) | | |
| Design Bid Build | Most prevalent (traditional delivery) | Owner responsible for errors and omissions | Req.partnering sessions |
| | 100% control of design | Little flexibility | Reg. ADR |
| | 100% control of fix for design errors and | Little opportunity for fast tracking | Provide for independent peer |
| | omissions | No integration of proprietary systems | review of the design documents |
| | Predictable initial project costs (fixed) | Adversarial relations (greater adm) | Reg. BMI |
| | The state of the s | No subcontractor input in design | Adequate contingency funds |
| | | Little opportunity for early purchase of long | squate containgency funds |
| | | lead items | |
| | | Longest project delivery | |



We also looked at:

• Integrated Project Delivery (IPD) – Contracting Issues


Participated in Forum through Associated General Contractors

Conducted surveys with other owners and owners' reps, and selected:

- Construction Management at Risk (CMc)
 - Construction Manager takes risk of building the project
 - A-E remains under separate contract to the Owner
 - Overlapping phases

Analyzed methods and risks based on Smithsonian past experience as well as that of other agencies/owners

- Schedule Advantage:
 - CMc Delivery:
 - Start late 2012
 - End late 2015/early 2016
 - Design/Bid/Build Delivery:
 - End-to-end design: complete
 late 2013
 - Construction complete 2017
- Cost Control:
 - Pre-Design Services and Reviews
 - GMP
 - Schedule/Cost Control



CMc @ Risk Delivery:

- Issue Concept Design with RFP
- CM selected through "best value" process
- Initial awarded for pre-construction services
- Cost verification for Concept Design
- Multiple package fast track delivery
- Shared savings provision
- Clark Smoot Russell contracted, 2011



DESIGN & CONSTRUCTION: Schedule Check-Up

- January 2010: Concept Design Start
- October 2010: Submission of Concept to SI
- November 2010: Schematic Design Starts

Site Acoustic Reports, Groundwater Sampling

Reports, etc.


- January 2011 65% SD Docs for CxAgent
- March 17, 2011 First Design Package and Concept Approval by CFA/NCPC
- April 1, 2011 Schematic Design Submission to SI




DESIGN: Corona



























DESIGN: Corona

2011








CHALLENGE: Design Assist for Exterior Enclosure

Design assist evolution - panels:





Cast aluminum with PVDF finish





CHALLENGE: Design Assist for Exterior Enclosure 2012





- Reflectance
- Material
- Weight
- Maintenance



CHALLENGE: Design Assist for Exterior Enclosure 2014



"Custom Artisan PVDF Panel Finish"




Commission of Fine Arts & National Capital Planning Commission final approval March 2014



EXHIBIT DESIGN: Selection of Exhibit Designer 2011










- Engagement of Exhibit Designer: Ralph Applebaum
- The Museum acquires a Jim Crow Railroad Car
- Collaboration between David Adjaye and Raph Applebaum begins, and
- In July 2011, a new Concept for the History Galleries is born...



CHALLENGE: History Galleries 2011

- April 2011 Schematic Design Complete
- July 2011 New Concept for History Gallery



- Excavation extends to 70' below grade
- Redesign of Foundation and Sub-grade Exterior Envelope
- Location and Protection of Railroad Car and Angola Prison Tower





CHALLENGE: Relocation of Gas Line 2011


Site Preparation: Relocation of major gas line








CHALLENGE: Relocation of Cooling Towers





Studies to share NMAH capacity



DESIGN & CONSTRUCTION: Schedule Check-Up

2011

| • April 1, | 2011 | Schematic Design Submission to SI |
|------------|------|--|
| • Jan 201 | 12 | Site Utilities Package # 1 |
| • Feb 202 | 12 | Groundbreaking Ceremonies |
| • April 20 | 012 | Support of Excavation Wall/Excavation Package #2 |
| • April 20 | 012 | 35 % Design Submission |
| • May 20 |)12 | Exterior Enclosure Design-Assist Package #3 |
| • June 20 |)12 | Deep Foundation Piles Package #4 |
| • Sept 20 |)12 | Concrete and Vertical Transportation Package #5 |
| • Sept 20 |)12 | 65% Construction Documents |
| • Jan 201 | 13 | Structural Steel Package #6 |
| • Mar 20 | 13 | MEP/FP Package #7 |
| • Aug 20 | 13 | 100% CDs Complete |
| • Jan 201 | L4 | Exhibit Specific CDs 100% Complete |
| • Jan 201 | L4 | Interior Build-out & Site Work Package (GMP) #8 |
| • Feb 201 | 14 | Conformed Set |



CONSTRUCTION: Site Utilities Work Begins

January 2012







• February 22, 2012: President Barack Obama speaks at the Groundbreaking Ceremony with former First Lady Laura Bush, Smithsonian Secretary G. Wayne Clough, First Lady Michelle Obama, and NMAAHC Director Lonnie Bunch





CONSTRUCTION: SOE Wall and Excavation

April 2012








CONSTRUCTION: Design Assist for Exterior Enclosure

April 2012

- Exterior Enclosure was identified early as a long lead system for early procurement. It consists of:
 - Structural framing
 - Corona screen
 - Curtainwall system
- Design Assist for the exterior enclosure was incorporated in both the Design and Construction Contracts
- Design provided "intent" documents before 35%
- Issued to CMc for best value selection





CONSTRUCTION: Design Assist for Exterior Enclosure


April 2012 - 2013

- Resulted in Changes in:
 - Corona
 - Structural Framing
 - Curtain Wall











CONSTRUCTION: Deep Foundation Piles & Concrete and Vertical Transportation June – September 2012







CONSTRUCTION: Excavation and Foundation Walls

2012-2013









CONSTRUCTION: Structural Steel and MEP

January – March 2013







CHALLENGE: Arrival of Large Artifacts

November2013









EXHIBITION DESIGN

2010 - 2014



Segregated Rail Car



Civil War



Military History



Middle Passage





CONSTRUCTION: Corona Production and Finishing 2014-2016
















CONSTRUCTION: Completion Exterior Enclosure October 2016













CONSTRUCTION 2014 - 2016








Installation of Cooling Towers






First Vertical Truss, Dec 2014



CONSTRUCTION: Porch Installation 2014 - 2016







CONSTRUCTION: Roof Installation 2014 - 2016






CONSTRUCTION: Panel Installation 2016

































Credits:

Design Team

Architect of Record: The Freelon Group

Architectural Team:

The Freelon Group, David Adjaye Associates, Davis Brody Bond with the

SmithGroup

Structural Engineering: Robert Silman and Guy Nordenson Associates

MEP/FP Engineering: WSP Flack and Kurtz Civil Engineering: Rummel Keppler & Kahl

Landscape Design: Gustafson Guthrie Nichol Ltd.

Cost Estimating: Faithful + Gould

Security: ARUP

Specifications: Construction Specifications

Blast/CBR/Perimeter Security: Weidlinger Associates

Sustainability: Rocky Mountain Institute

Acoustics/Audio-Visual/Telecommunications: Shen Milsem Wilke

Theatre/Multimedia: Fisher Dachs Associates

Vertical Transportation: Lerch Bates Lighting: Fisher Marantz Stone

Food Service: Hopkins Food Service

Hardware: Erbschloe Consulting Services, Inc.

Façade: R. A. Heintges & Associates

Construction:

Clark/Smoot/Russell

Smithsonian Institution Project Team Leaders:

Design Management: Brenda Sanchez

Construction Management: Steven Christensen

Progran Executive: Jud McIntire

This Presentation:

Professional Photography: Alan Karchmer

Contributors: Brenda Sanchez, Jud McIntire, Sharon Park