



# Improving Transformer Efficiency and Lifetime through Product Selection, System Integration and Dynamic Control



**DISTRIBUTION TRANSFORMERS ARE THE SUBJECT OF THIS PROJECT**

Pacific Northwest National Laboratory  
Jianming (Jamie) Lian, Ph.D., Staff Engineer  
(509) 372-4504  
Jianming.Lian@pnnl.gov

Savannah River National Laboratory  
Klaehn Burkes, Senior Engineer  
(803) 725-2459  
Klaehn.Burkes@srnl.doe.gov

# Project Summary

## Timeline:

Start date: April, 2016

Planned end date: December, 2018

## Key Milestones

1. Transformer control method design complete (4/30/18)
2. Transformer testing and data summary complete (6/15/18)
3. Transformer control method implemented & initial validation complete (7/31/18)
4. Transformer control method validation complete (12/31/18)

## Budget:

### **Total Project \$ to Date:**

- DOE: \$1,200K
- Cost Share: \$0

### **Total Project \$:**

- DOE: \$1,200K
- Cost Share: \$0

## Key Partners:

|                                              |
|----------------------------------------------|
| Pacific Northwest National Laboratory (PNNL) |
| Savannah River National Laboratory (SRNL)    |
| Santee Cooper                                |
| Clemson University                           |
| ERMCO                                        |

## Project Outcome:

Advance the state-of-the-art technologies of transformers with novel approaches

Provide proven guidance for the U.S. concerning the opportunities to reduce transformer losses and to prolong transformer lifetime

- No-load loss reduction from the adoption of amorphous metal core transformers leads to efficiency improvement
- Lifetime improvement from the adoption of transactive coordination and control for transformers and their loads



# Team

- **PNNL (lead)**
  - Design dynamic control for distribution transformers and associated loads to manage transformer lifetime
  - Develop large-scale distribution system simulations using GridLAB-D™ to assess the cumulative impacts
  - Conduct hardware-in-the-loop experimental studies using VOLTRON™ platform on full-scale transformers
- **SRNL**
  - Perform side-by-side testing of distribution transformers with different magnetic core materials
  - Assess the impact of test results to confirm the overall opportunity for energy savings in the U.S.
  - Characterize transformer performance for simulation model calibration in GridLAB-D™
- **Santee Cooper**
  - Support the development of transformer testing plan
  - Share 25 years of field performance and cost data for transformer testing and cost analysis
- **Clemson University**
  - Provide lab facilities for full-scale transformer testing
- **ERMCO**
  - Provide Totally Integrated Grid Energy Router



# Challenge

- Distribution transformer losses consume 2–3% of U.S. generated electricity, losing \$25 billion dollars each year
  - Hysteresis losses
  - Eddy current losses
  - Copper losses
- No-load losses alone from distribution transformers are estimated to account for about 25% of all the energy that is lost in the electric power grid
  - Need new technologies based on high-efficient core materials
- Transformer overloading during peak demand period significantly contributes to transformer loss of life
  - Need new dynamic coordination and control strategies to reduce the variability of transformer loading throughout the day by peak shaving and load shifting





# Approach

- Process utility data on distribution transformers purchases based on capacity, phase, and core material (Amorphous vs Silicon Steel)
- Perform distribution transformer testing for performance characterization in order to calibrate simulation model in GridLAB-D™
- Develop dynamic coordination and control strategies for distribution transformers (substation, feeder, building) and associated loads to manage/increase transformer lifetime
- Validate the effectiveness of developed dynamic coordination and control in increasing transformer lifetime
  - Design large-scale distribution system simulations using GridLAB-D™ to assess the cumulative impacts of control deployment
  - Conduct hardware-in-the-loop experimental studies using VOLTTRON™ platform on full-scale transformers by leveraging existing work under transactive building and campus




# Amorphous vs. Silicon Steel Transformer Cores

- **Amorphous metals don't have crystalline structure so they magnetize with less energy**
  - Creates a very thin hysteresis curve and reduces amount of magnetization losses
- **Amorphous metals saturate at a lower flux density**
  - This requires more material (i.e. larger core sizes) to match the magnetic flux of silicon iron
- **Amorphous Transformer use in America is limited**
  - They have an increased cost versus Silicon Iron because of increase in size and more complex manufacturing processes
- **Amorphous Metal Distribution Transformers (AMDT) have mainly been used in China and India**
  - Higher electricity costs give a better return on investment



Atomic structure of crystals



Atomic structure of amorphous alloys

# Approach: Analysis of Utility Data

Processing over 25 years of utility data on transformer purchases based on capacity, phase, and core material – Amorphous vs Silicon Steel.



- Polled many utilities partners between SRNL and PNNL and only Santee Cooper had record of purchasing Amorphous Metal Distribution Transformers
- Worked with Santee Cooper to categorize their distribution transformers by size and secondary voltage and determined cost to replace entire fleet of distribution transformers with AMDT
- Utilized information to determine value and energy savings for the nation through advanced core material utilization.

| Most Common Distribution Transformer Sizes |    |                  |    |                  |    |
|--------------------------------------------|----|------------------|----|------------------|----|
| 1-Ph Pole                                  |    | 3-Ph Pad 120/208 |    | 3-Ph Pad 277/480 |    |
| kVA                                        | %  | kVA              | %  | kVA              | %  |
| 25                                         | 43 | 75               | 21 | 500              | 20 |
| 50                                         | 23 | 150              | 20 | 300              | 15 |
| 15                                         | 17 | 112.5            | 19 | 75               | 12 |


# Approach: Distribution Transformer Testing

## Comparing Distribution Transformers performance based on different core material – Amorphous vs Silicon Steel.

- Transformers were removed from Santee Cooper's distribution system for testing and have been installed over 25 years.
- Testing to DOE Standard: evaluates efficiency at 50% load through open and short circuit tests.
- Evaluate efficiency over power rating at rated voltage.
- Compare Core performance in presence of harmonics, over and under voltage and frequency, and bidirectional operation.



# Approach: Lifetime Improvement




## Step one: open-loop assessment

- Consider transformer capacity limit as a pre-defined hard limit
- Compare transactive load control to conventional control in improving the transformer lifetime

## Step two: closed-loop co-optimization

- Derive operational cost function for transformer lifetime loss
- Optimize system operational cost with transformer lifetime loss by treating capacity limit as a decision variable

# Approach: Transactive Load Control



- Customer – Building loads

$$\begin{aligned} \max_p \quad & U_i(p_i, \theta_i) - \lambda p_i \\ \text{s.t.} \quad & P_{i,\min} \leq p_i \leq P_{i,\max} \end{aligned}$$

- Supplier – Transformer

$$\begin{aligned} \min_D \quad & T(D) - \lambda D \\ \text{s.t.} \quad & D_{\min} \leq D \leq D_{\max} \end{aligned}$$

- Coordinator – Load aggregator


$$\begin{aligned} \max_{p_i, D, V} \quad & \sum_{i=1}^N U_i(p_i, \theta_i) - C\left(\sum_{i=1}^N p_i\right) - T(D) \\ \text{s.t.} \quad & \sum_{i=1}^N p_i(V) + p_{uc}(V) \leq D \\ & P_{i,\min} \leq p_i(V) \leq P_{i,\max} \\ & D_{\min} \leq D \leq D_{\max} \\ & V_{\min} \leq V \leq V_{\max} \end{aligned}$$

# Impact

- Target market: distribution and building transformers
- Target audience: transformer manufacturers, utilities
- Impacts of project
  - Informs the DOE and utilities of the achievable efficiency improvements and their incremental costs
  - Influences the setting of target efficiency levels for transformers and also utilities' likelihood of adopting new transformer technologies
  - Offers increased reliability and resiliency to not only the transformers, but also the entire distribution systems
  - Contributes to Building Technologies Office and Grid Modernization Initiative goals under “Devices and Integrated System Testing ”
    - Task 2.1.5: Develop innovative grid infrastructure technologies that improve electrical grid efficiency and reliability by 10%




# Progress: Analysis of Utility Data

- Analysis is complete and a report has been issued to BTO
- Transformer efficiency is a function of normalized load and isn't constant
  - During transformer age loading profile changes and therefore costs savings for different transformers are different in the load profile
  - Savings are a function of efficiency, population size, and unit costs
  - Comparison of 30-year costs saving for replacing fleets of transformers shows there is a point when replacement cost is less than savings



# Progress: Distribution Transformer Testing

- Distribution Transformer measured efficiency tracks calculated efficiency from manufacturer-provided data with small reduction due to aging
- Actively testing performance evaluation of distribution transformers




— Traditional      — AMDT  
- - Traditional Measured      - - AMDT Measured

— Traditional      — AMDT  
- - Traditional Measured      - - AMDT Measured


# Progress: Open-loop Assessment

- Consider a feeder system with 1000 controllable residential ACs
- Feeder transformer has a nominal capacity of 3.6 MW (no-load loss is 0.3% of rated capacity and load loss is 1% at full load)
- Select three different capacity limits (4.0 MW, 3.5 MW, and 3.25 MW)

*Feeder total power*




*Hottest-spot temperature*



# Progress: Open-loop Assessment (cont.)

- Transformer lifetime baseline is around 21 years, which is obtained by assuming continuous operation at full load
- Transactive load control increases transformer lifetime by 6.15, 16.24 and 19.13 years, respectively, corresponding to three capacity limits




# Stakeholder Engagement

- Santee Cooper: Public Power Utility, supplied 25 years of distribution transformer purchase data, supplied 4 distribution transformers at scrap costs, and engaged in the results of performance testing to dictate future purchases
- National Rural Electric Cooperative Association: introduced EMRCO's power electronic augmented transformer, represents 42 percent of America's distribution lines
- ERMCO: Transformer manufacturer, supplying power electronic augmented transformer, Totally Integrated Grid Energy Router, invested in the performance testing of comparison of three types of transformers

# Remaining Project Work

- Finish performance testing of distribution transformers under harmonics, over and under voltage and frequency, and bidirectional operation
- Perform performance testing on Totally Integrated Grid Energy Router
- Perform economic analysis to determine the cost function quantifying loss of life of transformers
- Develop transactive control for transformers and associated loads together to systematically manage lifetime
- Calibrate transformer model in GridLAB-D™
- Design large-scale distribution system simulations to assess the cumulative impacts of control deployment
- Conduct hardware-in-the-loop experiments using VOLTTRON™ platform on full-scale building transformer

# Thank You



Pacific Northwest National Laboratory  
Jianming (Jamie) Lian, Ph.D., Staff Engineer  
(509)372-4504  
Jianming.Lian@pnnl.gov

Savannah River National Laboratory  
Klaehn Burkes, Senior Engineer  
(803)725-2459  
Klaehn.Burkes@srnl.doe.gov

---

# REFERENCE SLIDES

# Project Budget

**Project Budget: \$1,200K**

**Variances: No variances**

**Cost to Date: Cost through March 2018, totals \$568K**

**Additional Funding: None**

## Budget History

| 8/2016– FY 2017<br>(past) |            | FY 2018 (current) |            | FY 2019 – 12/31/2018<br>(planned) |            |
|---------------------------|------------|-------------------|------------|-----------------------------------|------------|
| DOE                       | Cost-share | DOE               | Cost-share | DOE                               | Cost-share |
| \$351K                    | \$0K       | \$699K            | \$0K       | \$150K                            | \$0K       |

# Project Plan and Schedule

- Project started in 3/2016 and is scheduled for completion with field testing and validation in 3/2019
- Schedule and Milestones (see table below)
- All milestones and deliverables are on track

| Project Schedule                                                     |                                |    |        |                                                           |    |    |        |    |    |    |        |
|----------------------------------------------------------------------|--------------------------------|----|--------|-----------------------------------------------------------|----|----|--------|----|----|----|--------|
|                                                                      | Completed Work                 |    |        |                                                           |    |    |        |    |    |    |        |
| Project Start: 8/2016                                                | Active Task (in progress work) |    |        |                                                           |    |    |        |    |    |    |        |
| Projected End: 12/2018                                               |                                |    |        | Milestone/Deliverable (Originally Planned) use for missed |    |    |        |    |    |    |        |
|                                                                      |                                |    |        | Milestone/Deliverable (Actual) use when met on time       |    |    |        |    |    |    |        |
|                                                                      | FY2016                         |    | FY2017 |                                                           |    |    | FY2018 |    |    |    | FY2019 |
| Task                                                                 | Q3                             | Q4 | Q1     | Q2                                                        | Q3 | Q4 | Q1     | Q2 | Q3 | Q4 | Q1     |
| <b>Past Work</b>                                                     |                                |    |        |                                                           |    |    |        |    |    |    |        |
| Confirm utility participation in the project team                    |                                |    |        |                                                           |    |    |        |    |    |    |        |
| Complete a report on transformer utilization and performance data    |                                |    |        |                                                           |    |    |        |    |    |    |        |
| Finalize test plan                                                   |                                |    |        |                                                           |    |    |        |    |    |    |        |
| Eight distribution transformers purchased from Santee Cooper         |                                |    |        |                                                           |    |    |        |    |    |    |        |
| Distribution transformers installed at eGRID Center                  |                                |    |        |                                                           |    |    |        |    |    |    |        |
| Complete report summarizing to DOE data collected and analysis of    |                                |    |        |                                                           |    |    |        |    |    |    |        |
| <b>Current/Future Work</b>                                           |                                |    |        |                                                           |    |    |        |    |    |    |        |
| Transformer testing and data summary complete                        |                                |    |        |                                                           |    |    |        |    |    |    |        |
| Transformer control method design complete                           |                                |    |        |                                                           |    |    |        |    |    |    |        |
| Transformer control method implemented & initial validation complete |                                |    |        |                                                           |    |    |        |    |    |    |        |
| Transformer control method validation complete                       |                                |    |        |                                                           |    |    |        |    |    |    |        |