


Innovative Low-Cost Ground Heat Exchanger for Geothermal (Ground Source) Heat Pump Systems



Oak Ridge National Laboratory

Xiaobing Liu, Mingkan Zhang, Kaushik Biswas, Joseph Warner, Tony Gehl, Jerry Atchley

liux2@ornl.gov

Project Summary

Timeline:

Start date: 10/1/2017

Planned end date: 9/30/2019

Key Milestones

1. Lab test of a small-scale prototype: Sep. 2018
2. Numerical models for evaluating long-term performance: Apr. 2019
3. Performance and cost analysis: Sep. 2019

Budget:

Total Project \$ to Date: \$384K

- DOE: \$384K
- Cost Share: NA

Total Project \$: \$510K

- DOE: \$510K (planned)
- Cost Share: NA

Key Partners:



Project Outcome:

An innovative and cost-effective ground heat exchanger with the potential to make highly energy efficient ground source heat pump (GSHP) systems affordable to millions of US homes, which can significantly reduce energy consumption and associated greenhouse emissions in our nation.



Team



- **Xiaobing Liu:** PI, prototype design, modeling, and lab tests. 19 years experience in ground source heat pump related R&D and applications.
- **Mingkan Zhang:** Model development. 16 years experience in numerical modeling of heat transfer and fluid dynamics.
- **Kaushik Biswas:** Characterization and integration of phase change materials (PCMs).
- **Joseph Warner:** Model development and lab tests.
- **Tony Gehl and Jerry Atchley:** Experimental instrument setup, data acquisition.

Challenge: Make GSHPs More Cost Effective


- GSHPs can efficiently heat and cool buildings, but the high cost of ground heat exchangers (GHEs) prevents wider adoption
- Drilling contributes most (~70%) to GHE cost (~\$3K/cooling ton)
- Previous R&D focused on improving borehole heat transfer, which resulted in limited cost reduction



The value of GSHPs could be increased if they could reduce and shift the electric demands of buildings with built-in thermal energy storage capability

Approach

Next-Generation GHE: Underground Thermal Battery (UTB)



Less drilling

- Installed in shallow bores

Larger heat capacity

- Filled with water and PCMs


Rechargeable

- Hybrid with other natural heat sinks/sources




	Soil/rock (typical)	Water	Inorganic PCM
Specific heat [kJ/(m ³ -C)]	2,070	4,200	~3,000
Heat of fusion [MJ/m ³]	NA	334	~300

Invention Disclosure: 201804082, DOE S-138,749

Approach (Continued)




Progress: Designed and Built a Prototype UTB



Experimental apparatus


A small-scale prototype UTB: 4 ft (1.2 m) tall with 8 in. (0.2 m) diameter

Progress: Lab Test Results




- UTB performs much better than alternative compact GHE
- PCM (9% of tank volume) has moderate impact

- Stable UTB performance under moderate loading conditions




Progress: 3D Models of UTB and VBGHE




Simulation domain of the 3D UTB model

Developed and validated 3D models for both conventional VBGHE and the UTB




Validation result of UTB model






Validation result of VBGHE model

Progress: Short-Term Performance

UTB outperforms conventional and PCM-enhanced VBGHEs in daily cooling operation




	Soil	Grout	PCM
λ (W/(m·K))	1.72	0.69	1.09(solid)/ 0.54(liquid)
c_p (J/kg/K)	2121	3106	3140
ρ (kg/m ³)	1900	1210	831
T_{melt} (K)	--	--	296
L (kJ/kg)	--	--	200




Progress: 1D Numerical Model of UTB

Model Development





- Uniform tank temperature
- Homogeneous soil properties and uniform initial temperature




Modeling phase change process with moving boundaries and heat accumulation method

Validation with 3D model




Progress: Long-Term Performance


- A UTB with two tanks (20 ft long with 2.5 ft dia.) has similar performance to a 200 ft deep VBGHE during a year-long operation of a residential GSHP system in a mild climate



UTB provides favorable fluid temperature for more efficient operation of a GSHP





Cooler temperature in summer



More stable temperature in fall

Progress: Long-Term Performance (Continued)



- Parametric study of key design parameters
 - Two building load profiles: high (OKC) and moderate (KNX)
 - Three ground thermal conductivities



UTB works better with lower cooling load and higher ground thermal conductivity


Progress: Long-Term Performance (Continued)

- Parametric study of key design parameters
 - Configuration of UTB: one tank or two tanks
 - Integration with (pre-existing) lawn irrigation system



Impact

- Reduce GHE cost and enable wider adoption of GSHPs → **More energy savings and emission reduction**
- Enable flexible loads through built-in thermal energy storage → **Improved stability and resilience of electric grids**




Overcome mismatch between intermittent renewable power supply and fluctuating thermal demands of buildings

Technical Potential of GSHPs


	Annual Primary Energy Savings	Annual Carbon Emission Reductions	Annual Energy Cost Savings
	Quad Btu	Million Mt	Billion \$
Residential	4.3	271.1	38.2
Commercial	1.3	85.2	11.6
Total	5.6	356.3	49.8

(Source: Liu et al. 2017)



Stakeholder Engagement (Early-Stage)

- Introduce UTB to industry through publications (e.g., an article in the IEA HPT magazine)
- Develop a proposal to demonstrate UTB at a facility of US Department of Defense
- Engage with industry partners to improve UTB cost effectiveness
 - Hybridize with radiative cooling
 - Apply new low-cost PCMs



UTB integrated with a novel radiative cooling



(a) Bio-based PCM



(b) Bio-based composite PCM

Low-cost bio-based PCM

(Source: Jeong et al., *Int. Journal of Heat and Mass Transfer*, 2014)

Remaining Project Work

- **Improve 1D model (FY19)**
 - Account for seasonal variation of soil temperature in the shallow subsurface
- **Conduct lab tests to characterize performance of small-scale UTB (FY19)**
 - Characterize UTB performance in heating application
 - Evaluate impacts of improved integration of PCM
- **Perform cost analysis and improve UTB design to reduce cost (FY19)**
- **Publish results (FY19)**
 - Three papers submitted to various journals
 - A 3D Numerical Investigation of a Novel Shallow Bore Ground Heat Exchanger Integrated with Phase Change Material
 - A Numerical Investigation of the Long-term Performance of a Novel Shallow Bore Ground Heat Exchanger for Residential Ground Source Heat Pump Applications
 - Development of an Underground Thermal Battery for Enabling Ground Source Heat Pump Applications and Shaping Electric Demand of Buildings
 - Final ORNL report
- **Develop a full-scale UTB and procedures for installation (planned for FY20)**
- **Field test the full-scale UTB (planned for FY20)**

Thank You

Oak Ridge National Laboratory
Xiaobing Liu, PhD
liux2@ornl.gov

REFERENCE SLIDES

Project Budget

Project Budget: DOE \$302K in FY18; DOE \$208K in FY19

Variances: None

Cost to Date: Spent \$346K (68% of project budget) by March 2019

Additional Funding: None

Budget History

Oct. 1 – FY 2018 (past)		FY 2019 (current)		FY 2020 – (planned)	
DOE	Cost-share	DOE	Cost-share	DOE	Cost-share
\$302K	0	\$208K	0	0	0

Project Plan and Schedule

Project Schedule

Project Start: 10/1/2017	Completed Work											
Projected End: 9/30/2019	Active Task (in progress work)											
	◆ Milestone/Deliverable (Originally Planned)											
	◆ Milestone/Deliverable (Actual)											
	FY2018				FY2019				FY2020			
Task	Q1 (Oct-Dec)	Q2 (Jan-Mar)	Q3 (Apr-Jun)	Q4 (Jul-Sep)	Q1 (Oct-Dec)	Q2 (Jan-Mar)	Q3 (Apr-Jun)	Q4 (Jul-Sep)	Q1 (Oct-Dec)	Q2 (Jan-Mar)	Q3 (Apr-Jun)	Q4 (Jul-Sep)
Past Work												
FY18 Q1 Milestone: Concept design of UTB		◆										
FY18 Q2 Milestone: CFD model of UTB			◆									
FY18 Q3 Milestone: Short-term performance evaluation through CFD simulations and lab-tests				◆								
FY18 Q4 Milestone: Design of a full-scale prototype					◆							
FY19 Q1 Milestone: Characterization of new PCMs						◆						
FY19 Q2 Milestone: Long-term performance of UTB							◆					
Current/Future Work												
FY19 Q3 Milestone: Performance of a lab-scale prototype UTB integrated with improved PCMs								◆				
FY19 Q4 Milestone: Final report									◆			