Transforming ENERGY

BETO 2021 Peer Review

Biochemical Pilot Scale Support and Process Integrations WBS#: 3.4.2.201

March 24, 2021 Systems Development and Integration

Dan Schell NREL

This presentation does not contain any proprietary, confidential, or otherwise restricted information

Biochemical Pilot Plant at the IBRF

~27,000 ft² of open floor and mezzanines





North High Bay (NHB, 1994)

- Integrated 1 t/d process train
- Feed handling through product separation
- Utilities and emission control systems



South High Bay (SHB, 2010)

- Integrated 0.5–1.0 t/d process trains
- Feed handling through high-solids enzymatic hydrolysis
- Some separations equipment
- Room for expansion



Project Overview

Biochemical Pilot Plant (35-year-old facility)

- Biomass conversion to biofuels/biochemicals
- Multiple expansions have occurred



1985: First pilot plant, cellulose hydrolysis



1994: First integrated pretreatment/SSF fermentation process and added labs



2010: Multiple integrated process trains, high-solids enzymatic hydrolysis

Project Overview

Biochemical Pilot Plant (35-year-old facility)

- Biomass conversion to biofuels/biochemicals
- Multiple expansions have occurred over the years

High Level Goal: Provide a **well-maintained and process-relevant, engineering-scale pilot plant** for process development and technology verification.

- What: Maintain pilot plant meeting data quality needs and generate process-relevant material for bench-scale R&D
- **How:** Effectively use available resources to maintain functionality and safety
- Why: Facility for pilot-scale process development and scale up for BETO and industry
- **Risk:** Inopportune failures/low work efficiency due to poor communications and planning



1985: First pilot plant, cellulose hydrolysis



1994: First integrated pretreatment/SSF fermentation process and added labs



2010: Multiple integrated process trains, high-solids enzymatic hydrolysis

Market Trends



Anticipated decrease in gasoline/ethanol demand; diesel demand steady

- Increasing demand for aviation and marine fuel
- Demand for higher-performance products
- Increasing demand for renewable/recyclable materials
- Sustained low oil prices
- Decreasing cost of renewable electricity
- Sustainable waste management
- Expanding availability of green H₂

£

- Closing the carbon cycle
- Risk of greenfield investments
- Challenges and costs of biorefinery start-up
- Availability of depreciated and underutilized capital equipment
- Carbon intensity reduction
- Access to clean air and water

Environmental equity

NREL's Bioenergy Program Is Enabling a Sustainable Energy Future by Responding to Key Market Needs

Value Proposition

 Readily available pilot plant supported by DOE and made available to all users.

Key Differentiators (U.S.)

- Unique one-of-its-kind U.S based facility for flexible and integrated biomass processing
- Up to 1 ton/d pilot-scale continuous pretreatment reactor systems
- Multiple large bioreactors ranging from 160-L to 9,000-L

Capital

1. Management

Current Project Structure (FY19- FY21):



- Pilot Plant Operations Task: Maintain a functional and safe facility (Routine operations: maintenance, repair, upkeep, documentation, safety, etc.)
- New Capabilities: Acquisition managed by milestones and Go/No-Go decisions

1.0 Management

Work Management/Risk Mitigation Elements

- Outlook project scheduling/tracking system (8 years of data)
- Weekly/Bi-weekly operations staff and PI coordination meeting
- Plan-of-the-day meetings
- SharePoint-based system for task assignment/tracking
- SharePoint-based system for routine/non-routine maintenance tracking
- Out of Service program

		Outl	ook Calendar Sche	duling/Tracking		
4 March 2020 SU NO TU WE TH FR	 March 2 - 6, 2020 	Golden, Colorado + 🌁 Today 76*#748*#	💑 Tomorraw 🍚 Friday G47 F / 477 F 🚔 G47 F / 477 F			
23 24 25 26 27 28	MONDAY	TUESDAY	WEDNESDAY	THURSDAY	FRIDAY	
1 2 3 4 5 6	2	3	4	5	6	
8 9 10 11 12 13	E.		PSI: EH (1900-L PR)		PSI: SP (Evaporator)	
15 16 17 18 19 20		PSE V	4458 (load cell install)	PSI: SP (Cross flow filter)		
22 23 24 25 26 27		FCICS3: FP (Sitting)		CPR: PT (Zipperdawe)		
29 30 31			FOKS	3: FP (Column reactor testing)		
April 2020						
SU MO TU WE TH FR	7.44					

1.0 Management

Work Management/Risk Mitigation Elements

- Outlook project scheduling/tracking system (8 years of data)
- Weekly/Bi-weekly operations staff and PI coordination meeting
- Plan-of-the-day meetings
- SharePoint-based system for task assignment/tracking
- SharePoint-based system for routine/non-routine maintenance tracking
- Out of Service program

What this project doesn't do:

- Research
- Business development
- Direct collaborations

		Outlook Calend	lar Scheduling/Ti	racking		
March 2020 SU MO TU WE TH FR.		- 🏕 Taday 76°1/48°1 🏕 Tomorrow 🚔 Friday	r			
23 24 25 26 27 28	MONDAY	TUESDAY	WEDNESDAY	THURSDAY	FRIDAY	
1 2 3 4 5 6	2	3	4	5	6	
8 9 10 11 12 13 15 16 17 18 19 20		PSt I	EH (1900-L PR)		PSI: SP (Evaporator)	
		PSE V-4458 (load cell install)		PSI: SP (Cross flow filter)		
22 23 24 25 26 27	FOC	S3: FP (Sifting)		CPR: PT (Zipperclave)		
29 30 31			FCIC53: FP (Column reactor testing	e)		
April 2020						
SU MO TU WE TH FR	9.88					

Linkages/Users By Project/Program Areas (FY19/20)



2. Approach

Task 1: Pilot Plant Operations



*Supervisory Control and Data Acquisition System

2. Approach

Task 2: New Capabilities

Objective: Acquire new state-of-art capabilities to support BETO's and industry needs.

Approach:

- Identify new needs:
 - Annual consultation with BETO and bioenergy research community
 - $_{\rm \circ}$ Interaction with industry partners
- Define/implement milestones/key decision points (Go/No-Go) based on available resources
- Update plan yearly in response to changing priorities

Challenges:

- Enough resources to acquire new equipment
- Long vendor lead times
- Safety upgrades have priority

Recent focus areas:

- Separations
- Alternative pretreatment option (DMR)



3. Impact

The pilot plant supports DOE/BETO's mission to scale up and commercialize biofuel/bioproduct production technology.

- Test technical feasibility of single or multiple unit operations
- Produce integrated, engineering-scale data
- Generate process relevant materials and bioproducts

Pilot Plant Used by Many Projects

	BETO (AOP and FOA)	Partnerships
# of Projects (FY13-FY20)	18	30
Estimate Worth to NREL	~\$2 to \$3MM annually*	Several \$10,000s to several \$MM/project

*Excludes this project

New FY21 work:

- Three to four new FOA projects
- Continuing work for two industry clients
- One new SBIR project

Addresses SDI strategic goals (MYP):

- Decrease commercialization risk
- Identity and solve scale-up issues
- Create added-value co-products
- Demonstrate innovative deconstruction approaches
- Enable high performance separations technology
- Develop technologies for utilizing waste streams
- Evaluate technology options

Partner Survey Quotes

"There are no other access to demo-scale bioreactors available with the flexibility that was available at NREL."

"The team at NREL worked with us extensively to modify the process and equipment to make it work."

"We have several projects at NREL. The first was the most important in successfully scaling our process at the IBRF."

3. Impact - Pilot Plant Use Tracking (2013-2020)



"Contact Day" – On a given day, a BETO (AOP or Lab Call) or industry (any industry partner work including FOAs) project used at least one piece of equipment or unit operation in the pilot plant. (Does not include routine repair and maintenance activities performed by this project. The scale and cost of the work is not represented.)

4. Progress and Outcomes



4. Progress and Outcomes



Work in the 2.2.3.100 Low Temperature Advanced Deconstruction Project (WBS 2.2.3.100, Biochemical Conversion Platform) NEL 1 15

Work Plans – Task 1



Pilot Plant Support - Calibrations

BEAMEX CMX CALIBRATION MANAGEMENT SOFTWARE



	IBRF Biochemical Pilot Plant Specific Procedure		
Procedure Title	Effective Date	Supersedes	
Instrument Calibration Management Program	12/28/2017	07/01/1997	

1.0 Introduction

The biochemical pilot plant located in the North and South High Bays of the Integrated Biorefinery

Research Facility (IBRF) is used to perform research and testing o fuel and chemical production processes. The plant <u>contains</u> conti tonne/d) as well as stand-alone equipment. Various utility systen steam; instrument and house air; and cold, chilled, and hot wate

	REL	Certificate Number 1819/12/CAL Position ID: LIT-386-1		Annue construction on the Annual Annu Annual Chill annue (11) (11) (1
Position		Gervice Sector D		
KOTA NOR DONTRUTON LINER	Brand Social Talk and Torontal	Skilla to bela hurber	LT-BS-1 19CTHE Falses CE10 AFIE	
Part	Note rights of theme likes go low	Angustily (penting fampentum	-	(persing number
Function		Calibration Event		
tone funder	Peace Toronter a SOCK (2) UNIT	California State	10420314141414	
Kanga	4.161W00.00 8.198	Environment Temperatu	-	Environment municity
Calify alion Proces	6.m	Calibrations		
Sue Sale	RECORD HAVE TO	And Address of the Ad	SCR. ADD75	Our Sale \$133018
Read / Engris	65% stigen	ingut Tubulue	Publics (#80)\$	Our Date \$180019
1000	Surfacentra Casillation	Over Colorest		Our Date:
Californian Stronge		Cupic minute		Oue Date:



1. As Found PASSED teams for CBN store				2. As Left J				PASSE	
period appe	Adust reput	North California	Alue Jugel	Parent nor (N. W. gard)	Aurona repair (result)	Adus real (series)	Name of Street	Alter Segur	Paniline Notice
0.00	6.012	0.01	43	4.29	8.30	6.812	0.00	43	-4.1
46.00	88.101	80.00	48.0	4.18	44.00	46.101	8.0	40.0	-
10.00	102.668	10.0	106.7	4.10	162.40	102 888	10.00	4.000.2	4
96.30	41.789	8.0	48.2	-6.58	01.10	41.799	10.00	40.2	- 41
4.10	441	4.04	4.4	4.18	4.00	4.00	4.00	44	41

- 96 Process and Instrumentation Diagrams (P&ID)
- ~ 400 electronic instruments
- ~ 1,100 digital control points
- 35 operator control screens

Automated multi-function field calibrator and communicator

Pilot Plant Support - Documentation

		emical Pilot Plant ng Procedure
Procedure Title	Effective Date	Supersedes
90-L Paddle Reactor	11/6/2019	1/1/2013
	Author: J. Shekiro	Reviewer: M. Fowler

Significant Hazards or Safety Considerations

Specific hazards unique to this operation <u>include</u>: chemicals, electrical, rotating parts, and high pressures and temperatures. Operation of this equipment is covered under the pilot plant's SOP (0480).

Unique hazards-None

Emergency shutdown: Turn the agitator switch to the OFF position. Close HV-1250-1 to block the low-pressure steam supply to the paddle reactor jacket.

Prerequisites

- Ensure that the area and reactor are safe for operation.
- Confirm that the reactor has not been modified from the configuration the operators have been trained on.

Operating Procedure

1. Loading the reactor

- 1.1. Ensure the paddle reactor (PR) is upright.
- 1.2. Open the reactor vent (HV-1250-3)
- 1.3. Verify that there is zero pressure in the reactor (PI-1250-2)

Equipment Specific Operating Procedures

Pilot Plant Support - Documentation

		mical Pilot Plant ng Procedure
Procedure Title	Effective Date	Supersedes
90-L Paddle Reactor	11/6/2019	1/1/2013
	Author: J. Shekiro	Reviewer: M. Fowler

Significant Hazards or S

Specific hazards unique pressures and temperat SOP (0480).

Unique hazards-None

Emergency shutdown: T the low-pressure steam

Prerequisites

- Ensure that the a
- Confirm that the have been traine

Operating Procedure

1. Loading the reactor

- 1.1. Ensure the pa
- 1.2. Open the read
- 1.3. Verify that the

		nemical Pilot Plant Tagout Procedure
Procedure Title	Effective Date	Next Review Date
LHR Plug Screw Feeder	10/7/2019	10/7/2020
	Author: C. Gunther	r -

Procedure Purpose

To securely isolate steam and electrical from the plug screw feeder (PSF-2221) prior to its removal. This procedure isolates steam from all components of the Large Horizontal Reactor (LHR) system.

Prerequisites

- The reactor system is in standard shutdown condition.
- All requirements of the NREL LO/TO Program must be followed.
- Notification of this LO/TO must be given to affected workers.
- The P&ID for this equipment has been reviewed for any <u>additional</u> energy sources not covered in this procedure. This procedure must <u>be updated</u> if necessary.
- This equipment has been inspected for any <u>additional</u> energy sources not covered in this
 procedure. This procedure must be updated if necessary.

Procedure

- Close and LO/TO the <u>high pressure</u> steam manual isolation valve (HV-2200-35) to R-2200 Verify Zero Energy: Set pressure <u>set-point</u> on Green Fisher valve to 50 <u>psig</u> or greater and verify that line pressure is equal to 0.
- 2. Position to OFF and LO/TO the following disconnects:

Equipment Specific Lockout/Tagout Procedures

Pilot Plant Support - Documentation

	IBRF Bioche Operatir	
Procedure Title	Effective Date	Supers
90-L Paddle Reactor	11/6/2019	1/1/20
	Author: J. Shekiro	Review

Significant Hazards or S

Specific hazards unique pressures and temperat SOP (0480).

Unique hazards-None

Emergency shutdown: T the low-pressure steam

Prerequisites

- Ensure that the a
- Confirm that the have been traine

Operating Procedure

1. Loading the reactor

- 1.1. Ensure the pa
- 1.2. Open the read
- 1.3. Verify that the

0	NREL	
	dure Title	
LHR P	ug Screw Feeder	

Procedure Purpose

To securely isolate steam and electrical from the plug s removal. This procedure isolates steam from all compo-(LHR) system.

Prerequisites

- The reactor system is in standard shutdown con
- All requirements of the NREL LO/TO Program meters
- Notification of this LO/TO must be given to affe
- The P&ID for this equipment has been reviewed covered in this procedure. This procedure must be updated if necessary.
- This equipment has been inspected for any <u>additional</u> energy sources not covered in this
 procedure. This procedure must <u>be updated</u> if necessary.

Procedure

 Close and LO/TO the high pressure steam manual isolation valve (HV-2200-35) to R-2200 Verify Zero Energy: Set pressure set-point on Green Fisher valve to 50 psig or greater and verify that line pressure is equal to 0.



Process and Instrumentation Drawings

Accomplishment - Control System Conversion



Original HMI System (25-years old)

- Custom-coded software for data transfer
 - Not industry standard
 - Increasingly difficult to maintain
- Long-term viability of the vendor in doubt
- Expensive license fees (~\$25,000/y)

HMI - Human Machine Interface (Control Screens and Logic)

New 1,500-L Bioreactor Control Screen

Accomplishment - Control System Conversion



Original HMI System (25-years old)

- Custom-coded software for data transfer
 - Not industry standard
 - Increasingly difficult to maintain
- Long-term viability of the vendor in doubt
- Expensive license fees (~\$25,000/y)

HMI - Human Machine Interface (Control Screens and Logic)

New HMI System

- Industry standard OPC communications
- License fees are about \$4,000/y
- Easier to learn, program, and maintain
- Modernized user interfaces to standard usage recommendations



New 1,500-L Bioreactor Control Screen

Accomplishment - Data Management System

- Uses built-in capabilities of the HMI software (Ignition, Automation Engineering) for data storage
- Final activity is to link plant runs with associated sample data generated by the NREL analytical chemistry group



PLCs

Managing Safety & Health

Guiding Document – Safe Operating Procedure

Activities

Maintenance and Repair

Equipment Installation

Equipment Checkout

Equipment Changes

Experimental Operations

Processes/Documents

- Job Briefing
- Hazard Control Docs
- Safe Work Permit
- **Readiness Verification**
- Process Hazard Analysis*
- Change Management*
- **Operating Procedures**
- Experimental Plan

Material Production

Types of process materials produced on a yearly basis include:

- Dilute-acid-pretreated corn stover
- Deacetylated and disk-refined (DDR*) stover
- Deacetylation black liquor
- Enzymatic hydrolysate from DDR stover
- Concentrated enzymatic hydrolysate from DDR stover
- Solid lignin (from enzymatic hydrolysis)



Twine used to bale stover pugged the membrane separation modules during clarification of an enzymatic hydrolysate.









Work Plans - Task 2



New Capability - Disk Refiner

- Subcontracted design of a DMR system
- 22" disk refiner delivered in Nov. 2020
- Targeting refiner installation by end of FY21
- Needed for new CRADA and FOA projects



Feeder Section and Supporting Hydraulic Unit



Andritz 22-in High/Low Consistency Disk Refiner



3-d rendering of a DMR system located in the SHB.

Summary

Management:

- Strong NREL plant operation crew
- Workflow management process

Approach:

- Structured management of resources and activities
- · Collaborative approach to identify new capabilities

Impact:

- Support BETO/industry scale up/commercialization efforts
- Facility for process development, evaluation, and verification
- De-risk technologies and identify/solve scale-up issues

Accomplishments:

- Control system upgrade/new data management system
- Acquiring new DMR capability







Acknowledgments

Team Members

- Ryan Ferguson
- Matt Fowler
- Casey Gunther
- Wes Hjelm
- Ed Jennings
- Luke Klin
- Bob Lyons



Funding

- US Department of Energy Office of Energy Efficiency and Renewable Energy Bioenergy Technologies Office
- Josh Messner BETO Technology Manager
- Jim Spaeth SDI Program Manager

Quad Chart Overview

Timeline

- Project start date: 10/1/2018
- Project end date: 9/30/2021

	FY20	Active Project
DOE Funding	\$1.5 MM	\$4.5 MM

Project Partners*

- Partner 1
- Partner 2

Barriers addressed

- ADO-A: Process Integration
- ADO-D: Technology Uncertainty of Integration and Scaling

Project Goal

Maintain a functional and safe biochemical pilot plant, add new capabilities to support BETO funded R&D or support industry projects as needed, produce process materials to enable R&D at bench/pilot scales, and link pilot plant data with associated analytical data completing the plant's data management system.

End of Project Milestones

- Complete linking of pilot plant data (sensor readings and operating conditions) with associated analytical sample data stored in a separate database
- Install 22" disk refiner and verify operation under no load conditions

Funding Mechanism BETO AOP

Summary



Anticipated decrease in gasoline/ethanol demand; diesel demand steady

Increasing demand for aviation and marine fuel

Demand for higher-performance products



Increasing demand for renewable/recyclable materials

Sustained low oil prices

Decreasing cost of renewable electricity

Sustainable waste management

Expanding availability of green H₂



£

Feedstock

Closing the carbon cycle

Risk of greenfield investments

Challenges and costs of biorefinery start-up



Availability of depreciated and underutilized capital equipment

Carbon intensity reduction

Access to clean air and water

Environmental equity

NREL's Bioenergy Program Is Enabling a Sustainable Energy Future by Responding to Key Market Needs

Value Proposition

Readily available pilot plant supported by DOE and made available to all users.

Key Accomplishments

- Plant ready to support BETO and industry needs and continually used by a variety of **BETO-supported and industry projects**
- New modernized control and data management systems

Additional Slides

Responses to Previous Reviewers' Comments

Reviewer's Comments

- Process improvements appear to be based upon internal discussion and do not include much (if any) industry guidance; the move to the DMR process, while it has potential, looks to be driven from internal research and not an external industry need. More clear industrial guidance and input should be collected.
- Suggest forming an industry advisory group to provide feedback on future needs and best use of this facility not only for BETO funded projects, but for all the entire biochemical industry.
- No support for gas fermentation, not designed to handle hazmats, not clear if it can handle flammable or combustible materials.

Response

Several reviewers noted the need for more industrial input particularly with respect to new pilot scale capacities. While there is no formal mechanism in this project to address these comments, NREL recently initiated an effort to revitalized the pilot plants starting with gathering input from industry (Fall 2020) on new capacities needed to support lowcarbon intensities technologies. We hope to upgrade the facilities soon with these new capabilities.

• None

Process Operations Block Diagram



Pilot Plant Support Representative Work

Recent Major Repairs

- Bent shaft and broken drive gear on a feed hopper ۰
- Water leaking into baghouse blower filter housings
- Leaking agitator seals on the 1,900-L Paddle Reactor
- Failed CIP system variable frequency drive and pump motor
- Deteriorating insulation on main boiler access door
- Failed steam shutoff valves on the non-end of the process)
 Failed baghouse air control circuit board (in process)

- Multiple equipment failures led to flooded mill room
- Corroded distillation system piping (in process)





....





Pilot Plant Support Representative Work

Recent Major Upgrades

- Enclosures built to contain pretreatment vent gas discharges during biomass collection reducing operator exposure to volatile compounds.
- New exhaust gas flowmeters installed on the 1,500-L and 9,000-L bioreactors replacing 25-year-old and outdated meters
- New monitors installed in the SHB control room improve operator
 monitoring of process operations
- New steam flow meter installed on the evaporator resolves poor piping design and malfunctioning flowmeter (in process)
- New and upgraded variable frequency drives installed on the 160-L and 1,500-L bioreactors
- Load cells installed on the last remaining 160-L bioreactor without them
- Failing electrical system on the 4-L steam gun being replaced and upgraded (in process)







NREL Partnership Survey Comments (Complete List)

NREL has provided value to my organization.: Comments			The quality of NREL deliverables has been satisfactory.: Comments	The value received has been commensurate with the costs.: Comments		The timeliness of NREL deliverables has been satisfactory.: Comments	NREL communications and reporting during the performance of the project have been effective.: Comments		I would work with NREL again.: Comments	What suggestions can you provide to improve NREL's effectiveness when working with partners?
	As one vector of a comprehensive research effort to obtain value added components from biomass.									Might want to establish a communication team or process rather than rely on the individual investigators.
	alliances in the field of	The staff and facilities of NREL are definitely amongs the best available in the US.			There have been unexpected results in the CRADA program that NREL has been able to cope with and solve with trouble.	The program has been completed under schedule		of NREL, however putting	Working with NREL has been a great experience of great value to our company. It was the first time that this kind of budget was approved for a biofuel research program and it was definitely h worth executing the program with NREL I would absolutely highlight the work and commitment of Rick Elander in our program.	(1
	Provide pilot scale demonstration of our process that is not available anywhere else.	5								
	Assisted in needed advanced processing methodogoies.									
We have several projects at NREL. The first was the most important in successfully scaling our process at the IBRF.	leading to commitments for funding and further development. The process is	demo-scale bioreactors	was not despite hard work	pocket we could not have afforded it as the national	The team at NREL worked with us extensively to modify the process and equipment to make it work.	,	The NREL team work closely with us throughout the process with weekly meetings and on-site visits during the run.	,		Having more staff would like. A single scientist handling all aspects of scale-up was too much.
	As the result of collaboration with NREL, we could develop our technology and prove the advantages of our technology. It makes our business move forward.									
	Provide validation for our process at relevant scale. Development of new process.									