# Multi-Functional Smart Structures For Smart Vehicles

2021 DOE Vehicle Technologies Office Annual Merit Review

Principal Investigator: Patrick Blanchard

Ford Motor Company Dearborn, MI 48124

June 22<sup>nd</sup> 2021

Project ID# mat197

This presentation does not contain any proprietary, confidential, or otherwise restricted information



June 22<sup>nd</sup> 2021 Project ID: mat197

## Overview

### Timeline

- Project start:
- Project end:
- Percent Complete:

Oct 1<sup>st</sup>, 2020 Dec 31<sup>st</sup>, 2023 20%

\$3,864,159

### Budget

- Total project budget: \$11,365,173
  - Total recipient share:
  - Total federal share with ORNL: \$7,501,014
  - Total federal share, minus ORNL: \$5,157,264
- Authorized total spending to date (BP1)
  - \$1,704,987

## Barriers & Targets

- Barrier: Lightweight structures that satisfy both structural requirements while offering multi-functionality in a reduced design space
- Target: Enhance the performance of lightweight fiber-reinforced composite with tailored smart preforms for sensing and strength

### Partners

- Oak Ridge National Laboratory
- Purdue University
- Michigan State University
- Yanfeng Global Automotive Interiors



## Relevance

## **Overall Objectives**

Develop a new class of multi-functional composite materials and processing technologies to produce lightweight fully integrated smart structures and surfaces

### **VTO's Mission**

Support research, development (R&D), and deployment of efficient and sustainable transportation technologies that will improve energy efficiency, fuel economy, and enable America to use less petroleum.

- Polymer composites have delivered significant mass reduction when compared to metallic solutions
- However, the lower intrinsic stiffness often precludes stiffness driven applications with limited available design space as performance targets cannot be met
- This project is leveraging novel materials and processing methods to demonstrate feasibility for more weight efficient designs with closed sections and localized reinforcements
- A concept design for an instrument panel cross car beam is underway, targeting a 40% mass reduction compared to a steel counterpart at a cost premium of <\$3/lb</p>
- High volume (<3min cycle time) automated processes are being developed to enable materials handing and integration of embedded sensors and electronics
- These new materials and processing methods show promise to have application to a broad range of automotive applications thus magnifying the impact on the ability to achieve long-term improvements in fuel economy and/or battery electric vehicle range



## **Budget Period 1 Milestones and Gateway**

	Milestone (Project Month)	Lead	Description									
$\star$	0.1 Project Management	Ford	Project Management and Planning									
$\star$	1.1.1 Concept Development (M1)	Ford	Compile attribute/functional requirements for cross car beam and establish initial design concepts.									
$\star$	1.1.3 Design Sections (M9)	Ford	Transfer design sections to water assist and sensor integration teams. Complete (2) manufacturing feasibility assessment cycles.									
*	1.1.4 Performance targets (M9)	Purdue	Establish cost and performance targets. Develop framework for realistic manufacturing alternatives based on performance and cost targets for the selected application.									
*	1.2.1 Conductive composites compounding (M6)	ORNL	Identify at least four carbon-based conductive fillers (CBF) and complete their procurement, down select and compounding of three different CBF with PA6 or PA66.									
*	1.2.2.2 Conductive composites characterization (M12)	ORNL	Demonstrate two or three manufacturing techniques to prepare conductive composites (CC), Complete characterization of CC for their electrical conductivity and mechanical properties (tensile, flexural, impact).									
*	1.3.1.1 Design freeze (M8)	Ford	Complete design freeze and build of tooling to be fabricated for manufacturing feasibility studies.									
*	1.3.1.2 WAIM process tryout (M9)	Ford	Mold 30 tryout parts on Functional Demonstrator Tool to determine manufacturing feasibility of proposed hollow sections.									
*	1.4.1 Tape production (M6)	Purdue	Produce 100m of tape <25mm wide at < 1 mm thickness for the down- selected fiber and polymer system and further adapt for compatibility with M-TOW, QEE-TECH® and molding cells.									
*	1.4.2.1 Feeding adaptation (M12)	Purdue	Re-designed and adapted feeding and consolidation system of the M- TOW-line allowing direct embedment of functional ducts/system into the structural M-TOW. M-TOW targets: diameter 6-12mm, >50 v/o fiber content and at a line speed of 0.5-1.0 m/min									

*	1.5.1.1 Function identification (M6)	Ford	Identify functions in cross car beam and complete design of a 3D demonstrator (~150 x 150 x 50 mm) for integrated sensors/circuits/electronics								
*	1.5.2 Prototype tool (M12)	Ford	Fabricate prototype tooling, form/mold 30 demonstrator components and complete functional electrical testing (resistance, continuity, sensor function) of integrated sensors/circuits/electronics.								
*	1.6.1.2 Attachment concept (M9)	ORNL	Design concepts for attachment points on cross car beam $-3$ concepts with 80% load transfer to discontinuous and continuous composite with 30% weight saving compared to stamped steel hard point.								
*	1.7.1 Technology down selection (M8)	Yanfeng	Down select to 1 design concept for attachment points on cross car beam with 80% load transfer to discontinuous and continuous composite with 30% weight saving compared to stamped hard point.								
*	1.7.1.2 EOAT studies (M9)	Yanfeng	Complete EOAT studies and establish a material handling strategy for inserts and continuous fiber tows allowing 3 minute cycle time.								
	1.9.1.2 Sub-scale mold integration (M6)	ORNL	Complete design of sub-scale molds for sensor, hardware, tow placement and water assist work streams.								
$\star$	1.10.1.1 Infrastructure review (M6)	ORNL	Complete lab and Tier 1 infrastructure review to determine process sensing capability for AI model development.								
*	1.11.1.1 Recycling baseline identification (M12)	ORNL	Identify suitable short fiber reinforced thermoplastic (SF-TP) material and prepare 5-10 injection molded samples. Prepare 6 tensile testing specimens (ASTM D638) and test them for tensile strength and elastic modulus measurements.								
*	1.11.1.2 Short fiber recycled material testing (M15)	ORNL	Prepare recycled short fiber reinforced thermoplastic samples via mechanical shredding/grinding and injection molding. Prepare at least 6 tensile testing samples (ASTM D638) and document mechanical properties.								





June 22<sup>nd</sup> 2021 Project ID: mat197

## Approach: Multi-Functional Smart Materials

- While mass reduction is an important attribute, new functionalities need to be developed for polymer composites to compete effectively
- Concept instrument panel cross car beam incorporates advances in both material and processing to deliver a new customer experience to the vehicle interior.
- New functionality delivers more efficient design solutions for next generation interiors.



**Future Mobility Solutions** 

## **Project Structure**





## Task 1: Design Workstream Timing Plan

	Budget Period 1										Budget Period 2										Budget Period 3									
	Q1			(	<u>2</u> 2		Q3		Q4			Q5		Q6 Q		Q7	7 Q8		28	Q9			Q10		Q11		Q12		Q13	
Task	1	2	3	4	5 6	6 7	7 8	9	10	11	12 1	13 14	15	16 17 1	18 1	19 20	21	22 2	23 24	25	26 2	27 2	8 29	30 3	1 32	33	34 35	5 36	37	38 39
1. Component Design, Analysis & Prove-Out																														
1.1 Concept Development (Check Points 1 thru 7)			(	CP1			CP2		CP	3		C	P4	CP5			CP6		CP7 ┥								Pro	totype	;	
1.2 Integrated Computation Materials Engineering (ICME)					(	CAE1					CAE	2		CAE3		CAE4	(	CAE5	CAE	6							Te	esting		
1.3 Manufacturing Feasibility Assessment (MF1 -MF6)				Μ	IF1		M	F2 <			MF3			MF4	Μ	F5		MF6	MF	7	Тоо	I								
1.4 Techno-Economic Analysis								I <													Desig	jn	Тос	)						
1.5 Molding Tool Development								l													Freez	ze	Deliv	ery						Ford
1.5.1 Tool Design, Build & Commisioning								1																						AR
1.5.2 Tooling Changes and Part Molding Trials																					0.0								Ģ	ateway
1.6 Prototype Builds & Design Verification Testing													307	140-00				C	107	<u>40-</u>	-00								$\overline{\langle}$	
Ford/DOE Stage Gate Reviews																								(	Go/	No-	Go			

### Design & Development Process (Budget Period 1)

- The Design workstream is the lead activity with all other working groups acting as dependents
- Periodic check points (CPx) are built into the design process to incorporate results from supporting work streams
- Structural and manufacturing simulation analysis will be performed to ensure target functional requirements are achieved
- A manufacturing feasibility assessment of proposed design features and sensing technologies will be conducted to build confidence before formal inclusion on the final concept design
- A techno economic analysis will be conducted to allow evaluation of candidate designs



## Task 1 Accomplishments: Cross Car Beam Requirements / Initial Concept



- Energy Management Pathways (For Tow/WAIM) 1)
- 2) Vehicle Sensing / Health Monitoring
- **Thermal Management** 3)
- Capacitive/Force Switching and Embedded Sensing 4)
- **Class A Surface Integration** 5)
- **AM Attachment Locations** 6)
- **Bulk Material Properties** 7)



Completed Tasks:

- CAD model to meshing for CAE
- 1st check point for business case
- 2D Sketch (4th round)
- 3D Surface (1st round)



#### June 22<sup>nd</sup> 2021 Project ID: mat197

## Task 2 Accomplishments: Materials Workstream

- Team identified 4 carbon-based conductive nanofillers:
  - Carbon nanotube (CNT)
  - Carbon nanofiber (CNF)
  - Graphene-oxide (GO)
  - MXene (MX)
- Team identified 5 reinforcement materials:
  - 50% short GF
  - 50% long GF
  - 40% CF
  - 25% CF/15% BF
  - 20% CF/10% BF
- Candidate nanofillers and reinforcements have been sourced and compounding completed using a base PA66 polymer.
- Thermal, conductivity and mechanical testing due to commence in May 2021.



## Task 3 Accomplishments: Water Assist Injection Molding (WAIM)

### Design

- Initial "closed section" channels incorporated into the cross car beam design
- Demonstrator tooling design complete for manufacturing feasibility studies
- Tool build completed and received on May 12<sup>th</sup>, 2021



Technology Demonstrator Injection Mold

### Processing

- Water assist injection equipment installed and commissioned on site, March 25, 2021
- Commissioning trials completed on March 30, 2021
- Representative molding materials (per Task 2) received for Q2 processing trials.



Injection molding cell

Component cross section



## Task 4 Accomplishments: Tow/Tape Placement of Continuous Fibers

### **Budget Period 1 Accomplishments**

#### Composite Tape Production:

a) The laboratory's TAPE LINE has been redesigned and adjusted to fabricate continuous carbon and glass fiber Polyamide (PA) pre-pregs at industrial rates.
b) Production trials with surrogate fibers has been conducted in support of milestone 1.4.1





#### **Functional Preform Production**

The M-TOW LINE has been designed enabling preform fabrication with embedded functional systems for sensing, conducting and fluid transfer.



June 22<sup>nd</sup> 2021 Project ID: mat197



## Task 5 Accomplishments: Sensor Integration

Substrate materials and conductive inks have been examined for testing

- Conductive inks: silver (nanoparticle, particle-free), copper, carbon
- Film substrates: PET, PCI, PI, PA66

Location for sensing functions on the class A surface of the cross car beam have been identified

- Interactive functionality/switching for customer input
- Representative 3D geometry for prototype tooling and testing
- Preliminary injection molding trials conducted using printed circuits to understand survivability with higher temperature PAGF15 engineering polymers.
- Initial trials have utilized a flat panel injection molding tool (125 x 125 mm).

Trial Conclusions:

- Single layer capacitive touch circuitry appears to be compatible
- Force sensing resistor technology is not directly compatible with mold-behind IM processes
- Polyamide 6 could potentially be used directly as a mold-behind material
- Formulation of specific inks and films will be required to ensure compatibility with the back molding material
- Tooling for representative 3D geometry is now being designed in support of design feasibility assessments



Vehicle Research & Technology

June 22<sup>nd</sup> 2021 Project ID: mat197



## Task 6 & 7 Accomplishments: AM Attachment & Manufacturing Feasibility

### **Task 6: AM Hardware Attachment Points**

- ORNL team working with Purdue and Yanfeng to determine an attachment strategy for integration of tow materials
- Task 1 Design workstream to complete initial concept of geometry at A Pillar body attachments
- Current candidate AM processes include DED EBM – SLM – Binder Jet
- A final decision will be based on the attachment material, surface roughness, attachment size, etc

### Task 7: High Vol. Manuf. Concept Feasibility

- Completed an initial evaluation of methods to locate tow(s) in injection molding tooling
- Developed multiple concepts to hold the tow in place in various geometric situations
- Conducted Pugh analysis to determine the most effective methods
- Created designs to reflect how those methods
   would package in a surrogate tool design





#### June 22<sup>nd</sup> 2021 Project ID: mat197

## Task 9 & 10 Accomplishments: AM Segmented Tooling / AI-ML Process Optimization

Task 9: Additively Manufactured Segmented Tooling

- The ORNL team has been working with Task 3 and Task 5 workstreams to identify tooling needs for planned manufacturing studies.
- A selection of existing master unit die (MUD) bases has been secured to reduce the size of potential AM tooling inserts.
- Currently evaluating the possibilities for printing inserts to the water assist demonstrator tool to allow variants in the channel cross section to be evaluated.
- ORNL is working with Ford and Yanfeng to develop tooling in support of the embedded sensor over-molding studies
- A proposed turnaround time of 6-7 weeks has been established for powder bed fusion (PBF) and Direct Energy Deposition (DED) processes
- A final decision on an initial set of AM tooling in support of the project experimental program will be made in June 2021.

### Task 10: AI/ML Process Optimization

- Per milestone 1.10.1.1, a review of data collection and process monitoring methods has been completed for operations at Yanfeng
- The current data infrastructure captures and tracks the information associated with the injection molding machine
- Data analytics algorithms and tools are in place to extract information that can help qualify and optimize the process and the resulted molded parts.





Master Unit Die base



June 22<sup>nd</sup> 2021 Project ID: mat197

## **Collaboration and Coordination**

T	Yanfeng Global Automotive Interiors	Founded	Ford					Y	OAK RIDGE National Laboratory								
	(Sub)	(Sub)	(Prime)		(St	(dl			(Sub)								
	RASIC Chart: Multi- R: Responsible: The A: Approve: The co	Functional Smart Structures F e Institute/Company Respons	For Smart Vehicles ible for this task roval			de Ur	IN <sup>ersity</sup>	ailon?	Lon Rond								
	S: Supporting: The	Company/Institute giving supp	port for the competion of the task	55° JAN KE KOLO													
	I: Informed: The Co	mpaby/Institute to inform abo	ut this task		nigo	due/	4 A A	2M	Nell'S								
	C:Consulted: The co	C:Consulted: The company/institute that can act as expert in regard to the task															
	Task 0. Program Man	agement					R										
	Task 1. Component D	esign, Analysis & Prove-Out		1	S	S	R, A	S									
	Task 2. Formulation/C	compounding of novel materia	als	1	Ι	R	S, A	R									
	Task 3. Water-Assist	Injection Molding (WAIM) Pro	cess Development	S	Ι	S	R	S									
	Task 4. Tow/Tape Pla	cement of Continuous Fiber		1	R	S	S	S									
	Task 5. Sensor Integra	ation		1	S	S	R	S									
	Task 6. Additve Manu	factured Hardware Attachme	nt Points	S	S	R	S	S									
	Task 7. High Volume	Manufacturing Concept Feas	ibility Demonstration (sub-scale)	S	S	S	S	R									
	Task 8. Process Scal	e Up & Demonstration		S	S	S	S, A	R									
	Task 9. Additive Man	ufacturing of Segmented Tool	ing	1	S	R	S	Ι									
	Task 10. Artificial Inte	lligence/Machine Learning Fo	or Process Optimization		Ι	R	I	S									
	Task 11. Closed Loop	Recycling			Ι	R	S	S									

All partners are represented within active working groups. Weekly alignment meetings are held to ensure effective coordination across all facets of the cross car beam design and development process



June 22<sup>nd</sup> 2021 Project ID: mat197

## **Remaining Challenges and Barriers**

- Only early stage design work has been completed, leaving a significant amount of development required in order to meet mass savings and other functional objectives. The team is working towards validation of a formalized concept by the end of 2021. This will be featured as part of the Budget Period 1 gateway review. However, further refinements would still be required before a final prototype design freeze occurs in 2022.
- Determination of thermal and electrical conductivity is still outstanding as it relates to grounding requirements of electronics and the proposed elimination of supplementary wiring harnesses.
- Studies utilizing water assist injection molding have demonstrated feasibility of creating hollow sections. However, processing the size and complexity of the channels in the cross car beam presents new challenges. This is further compounded by the high thermal conductivity and rheological behavior of these highly filled fiber reinforced polymers.
- A proof of concept has been demonstrated for integration of sensing and conductive pathways in continuous tows/tapes. Further work is required to assess robustness of these "Smart Preforms" when incorporated into a high volume injection molding process.
- The relatively high processing temperatures of polyamide 66 creates survivability concerns during over-molding of sensors and embedded electronics. Further work is required to develop strategies for managing thermal exposure.
- Final validation requires full scale production demonstration featuring automated unit cell operations to manage material handling strategies for all over-molded features (e.g. sensors, smart preforms, AM attachment points).



## **Proposed Future Research**

### Budget Period 1 (Oct '20 – Dec '21): Concept Design & Development

- Design themes and CAD surface models will be subject to multiple iterations before converging upon a final concept at the end of Budget Period 1.
- Throughout this phase of work, technology and manufacturing feasibility assessments will be needed before incorporating results from parallel workstreams into the design. Furthermore, development of unit cell operations are required to manage material handling and over-molding sequences for a high volume production process.
- A Go/No-Go gateway review at the end of Budget Period 1 will also be supported by a techno-economic analysis to measure commercial viability of the concept design before scale up of operations in Budget Period 2.

### Budget Period 2 (Jan '22 – Dec '22): Materials & Process Optimization

 The team will further refine the cross car beam design based on manufacturing feasibility trials and material and process optimization. Unit cell operations for integration of all over-molded structural inserts and sensors will be demonstrated. A completed CAD design for the cross-car beam will be prepared to enable fabrication of full scale prototype tooling and molding cell automation.

### Budget Period 3 (Jan '23 – Dec '23): Prototype Validation & Testing

• The team will build prototype tooling to manufacture cross car beams for testing and validation. Materials and processing optimization will continue. Full scale injection molding will be demonstrated. The ability to fixture inserts and continuous fiber into the injection mold and retain them through the injection process will be demonstrated.

### Any proposed future work is subject to change based on funding levels



## Summary

### Highlights:

- The team has developed a vehicle interior theme that integrates a multi-functional structure within an instrument panel cross car beam
- The design volume has been established and requirements set allowing design concepts to evolve and work within dependent work streams to progress
- To date, surface CAD has been generated leading to generation of CAE models for structural analysis
- Down selection, procurement and compounding studies have been completed for candidate fibers and conductive fillers
- In parallel to design activities, facility commissioning has been completed for both water assist injection molding and production of continuous tow/tape reinforcements
- Design of a sub scale demonstrator part for water assist injection molding studies has been completed in addition to subsequent fabrication of corresponding tooling
- Methods for material handling and tooling retention are underway to support integration of all over-molded features

### Outlook

 Design of the multi-functional cross car beam structure is progressing as planned. This is supported by each of the dependent workstreams that are now fully operational. Early on in the program some delays were experienced due to COVID restrictions and limited availability of design resources. However, these issues have been resolved and overall project timing remains on track.