

# Multi-Tower Systems with Centrifugal Particle Receiver



Particle Receiver Panel, August 25, 2021

Dr. Reiner Buck



Knowledge for Tomorrow

## Introduction Centrifugal Particle Receiver „CentRec®“




- Particle residence time / receiver outlet temperature controlled by adjusting rotational speed
- Thin, optical dense layer for all load conditions



## CentRec500 – Test Campaign

- Jülich Test Campaign 2017 – 2018:
- first on-sun test of CentRec® receiver
- validation only possible on < 500 kW input from solar field (Hence, the receiver titled CentRec500)
- $T_{out} = 965^{\circ}\text{C}$  (at < 10 % part load) achieved
- only one suitable steady-state point acquired at  $T_{out} = 702^{\circ}\text{C}$  permitting validation of simulation models





## Recent Testing of 300kW Centrifugal Receiver

- Part of EU project “PEGASUS”: use of particle technology for solar-driven sulfur cycle
- Receiver aperture diameter: 60cm
- Tests in DLR sun simulator “Synlight” in Jülich



# PEGASUS Test Setup in Synlight Sun Simulator



Operation with fixed particle mass flow  
(changable orifice plates)

- 2 containers à 1 t particles
- Batch mode operation
- Particles cooled down at night with air





# Test 05.05.2021 – Typical test run

Operation time per test limited by infrastructure (batch mode, particle transport capacity)

Test 1: fast heating to provide hot particles to consecutive sulfur cycle

Test 2: pre-heating without particle flow to achieve steady-state test conditions for evaluation asap





- TE\_R\_INL\_11
- TE\_R\_INL\_12
- TE\_R\_INL\_13
- TE\_R\_INL\_14
- TE\_R\_INL\_15
- TE\_R\_INL\_16
- TE\_R\_INL\_21
- TE\_R\_INL\_22
- TE\_R\_INL\_23
- TE\_R\_INL\_24
- TE\_R\_INL\_25
- TE\_R\_INL\_26
- TE\_R\_INL\_31
- TE\_R\_INL\_32
- TE\_R\_INL\_33
- TE\_R\_INL\_34
- TE\_R\_INL\_35
- TE\_R\_INL\_36
- TE\_R\_INL\_41
- TE\_R\_INL\_42
- TE\_R\_INL\_43
- TE\_R\_INL\_44
- TE\_R\_INL\_45
- TE\_R\_INL\_46



## PEGASUS Test Results

- 22 test days with „solar“ operation, 25 h regular test time at various temperature levels
- Inhomogeneous mass flow distribution over circumference  
⇒ Hot spots limit the maximum achievable temperature
- Max. measured outlet temperature: 720°C
- Errors in measured outlet temperature
  - Measured particle outlet temperature < particle temperature in storage (by about 50K)
- Currently analysis of reason for hot spots: particle distributor, cylinder tolerances, grid structure, ...




## Results of Improved System Analysis (in cooperation with Jeremy Sment, SNL)

- Main assumptions according to Gen3 specifications
- Multi-tower system, 12 modules, each with  $42\text{MW}_{\text{th}}$  centrifugal receiver and 14h tower-integrated storage
- Particle transport between modules and central power block: insulated containers, autonomous trucks
- $\text{sCO}_2$  power cycle  $565^\circ\text{C} / 700^\circ\text{C}$ ,  $\eta = 48\%$
- Lower/upper boundary cost correlation for tower (1<sup>st</sup> marker “l” or “u”)
- Lower/upper boundary cost correlation for primary HX (2<sup>nd</sup> marker “l” or “u”)




### Parametric study for particle temperature selection

- Lower particle temperature:  $580 / 600 / 615^\circ\text{C}$
- Upper particle temperature:  $800 / 1000^\circ\text{C}$



# Results of Improved System Analysis (in cooperation with Jeremy Sment, SNL)

- LCOE range from 49\$/MWh to 66\$/MWh
- Strong impact of assumptions for tower and HX cost correlation
- Strong impact of upper particle temperature
- Little impact of lower particle temperature



(no price escalation for DoE Gen3 parameters and other values considered)



## Risks and Mitigation Measures

- **Particle loss**
  - Small chance for particle entrainment under high wind conditions
  - Preparation of lab tests for validation
- **Performance**
  - Too few “good” test data available yet
  - Further tests with improved sensors and longer test time required
- **Particle film characteristics**
  - Inhomogeneous particle flow creates hot spots
    - Ongoing lab tests to evaluate impact of potential sources
  - Thermal conductivity of particle film
    - Mixing effect in flowing particle film?
    - PhD work to evaluate this effect near completion
- **Cost**
  - Cost predictions need to be validated for
    - Receiver
    - (Particle ground transport)
- **Potential for further cost reduction:** hybrid CST/CPV receiver, multi-receiver tower, aim point switching, ...



## Ongoing Activities


- HIFLEX
  - EC project to install and tests a complete particle demonstration system in Italy; 2.5MW<sub>th</sub> receiver, ~ 10MWh storage, 620°C steam generator
- HEHTRES
  - DLR particle test infrastructure @ Solar Tower Jülich, 1MW<sub>th</sub> receiver
- PreMa
  - EC project for manganese production, includes particle-to-air heat exchanger development
- KOSTPAR
  - BMWi project; receiver upscaling, steam generator development
- TCF / NoLimits
  - DoE/BMWi project: Full load demonstration of particle receiver @ SNL/NSTTF, 600kW<sub>th</sub> receiver

### Under preparation

- SpiCoPV (BMWi):
  - Integration of CPV into particle receiver aperture (to capture spillage)
- KOSTPAR-2 (BMWi):
  - Further receiver improvement, Steam generator demonstration



Thank you for your attention!



Contact: [reiner.buck@dlr.de](mailto:reiner.buck@dlr.de)

