

An air conditioner with composite phase change material (FY19 Technology Commercialization Fund project)

Composite phase change material:





NREL
Dr. Jason Woods, Sr. Research Engineer
720.441.9727 | jason.woods@nrel.gov

Project Summary

<u>Timeline</u>:

Start date: 2018 December

Planned end date: 2021 June

Key Milestones

- 1. Experiments complete on 5-ton system prototype; 06/30/2020
- 2. Experiments complete on next-generation thermal storage prototype; 06/30/2021

Budget:

Total Project \$ to Date:

• DOE: \$500,000

Cost Share: \$550,000

Total Project \$:

• DOE: \$500,000

Cost Share: \$550,000

Key Partners:

NETenergy

Emerson

Trane Technologies


Project Outcome:

This project will develop prototypes of a new hybrid air conditioner with embedded thermal energy storage.


It focuses on packaged air conditioners, which has limited thermal storage options despite it being the largest space cooling market in the US.

The goal is to develop an affordable and cost-effective thermal storage technology that enables load flexibility and reduced carbon emissions.


Team



Materials characterization
Thermal storage design/modeling
Laboratory characterization



Material synthesis
Thermal storage sub-system build
Commercialization




Vapor-compression components build Market analysis Manufacturing cost analysis



Support on vapor-compression build Support on market analysis


Challenge

- 77% of electricity is used at buildings
 - 50-60% of that is for thermal loads
 - Much of this is mismatched with renewable-electricity generation



US electricity generation for a 100% renewable grid compared to building thermal and non-thermal loads.

Existing ice and chilled water storage are often cost-effective for these applications




There's no available solution for split and packaged systems (>80% of US floor space).


¹ US EIA, 2012. Commercial Building Energy Consumption Survey, Table B41. Cooling equipment, floorspace.

Approach

A "hybrid" air conditioner where the thermal storage shaves the peak cooling demand, while the compressor operates at a reduced capacity.

Composite phase change material:






Impact: Creating a packaged air conditioner with TES that can succeed in the market

	Rooftop unit integrated ice system (previous state-of-the-art)	Proposed hybrid air conditioner integrated with c-PCM heat exchanger					
Initial Cost	5x higher cost than standard RTU 50% higher cost than standard l						
Weight	2,700 kg in separate box	350 kg added to RTU					
Performance relative to baseline	e non-TES air conditioner						
Electric demand (kW)	90% lower	35%–45% lower					
Electricity use (kWh)	10% higher	10% lower					

Previous approaches are way too heavy and expensive for packaged systems, which condition >80% of US floor space.

Significant potential energy, CO₂, and monetary savings.




Progress

Modeling, design, and experiments:


- TES sub-system: 1st generation, 1 tonh, glycol-glycol
- Air conditioning system: 1st generation TES, 6-tonh, refrigerant-glycol
- TES sub-system: 2nd generation, 1/10th tonh, glycol-glycol


1st generation TES




2nd generation TES

Progress: 1st generation, 1 tonh prototype








Finite-volume numerical model used to estimate contact resistance. Estimated at >50% of the overall resistance.

Progress: 1st generation, full-system


Charge subsystem – Condensing unit from Trane, modified by Emerson



Discharge subsystem - Built by Emerson




Progress: 1st generation, full-system



Progress: 1st generation, full-system

Key findings:


- Controls were effective at modulating charge/discharge and keeping superheat at TES outlet near 0 °C (suction-line HX ensures adequate superheat into compressor).
- PCM leak observed due to expansion on solid-liquid phase change.
- Contact resistance a critical problem with serpentine design.
- Need to eliminate refrigerant migration at end of charge cycle, which leads to self-discharge of TES.




Progress: 2nd generation, 1/10th tonh

Material	Cycling performance – mass loss
Aluminum foil	0.7% decrease after 1 cycle
Mylar film	4.3% decrease after 2 cycles
Sealed Mylar bag	0% decrease after ~60 cycles





Progress: 2nd generation, 1/10th tonh



Net charging

Avg error = 0.34 °C Max error = 1.16 °C

Net discharging

Avg error = 0.22 °C Max error = 0.67 °C

Woods, J., A. Mahvi, A. Goyal, E. Kozubal, A. Odukomaiya, R. Jackson. Rate capability and Ragone plots for phase change thermal energy storage. Nature Energy. 6(3) (2021) 295-302.


Progress: 2nd generation, 1/10th tonh

1st generation - Copper tube

Experimental data from Goyal et al. (2021)


2nd generation - Microchannel


Results using current microchannel model



Goyal, A., E. Kozubal, J. Woods, M. Nofal, S. Al-Hallaj. Design and performance evaluation of a dual-circuit thermal energy storage module for air conditioners. Applied Energy. 292 (2021) 116843

Progress: Energy and demand savings point to manufacturing cost targets





			kW	reduction	kWh reduction						
						Fixed-					
Climate	TES design		Fixed-speed	TES hybrid	kW %	speed	TES hybrid	kWh %			
Cilliate		PCM T _t	peak power	peak power	change	energy	energy	change			
		°C	kW	kW	%	kWh	kWh	%			
Los	Serpentine	4.5		2.9	-48%		33.1	-5%			
Los	Microchannel	l 4.5	5.59	2.4	-57%	34.8	28	-20%			
Angeles	Microchannel	10.0		2.4	-57%		26.4	-24%			
	Serpentine	4.5		3.1	-36%		40	4%			
Baltimore	Microchannel	4.5	4.87	2.5	-49%	38.4	33	-14%			
	Microchannel	10.0		2.4	-51%		29.9	-22%			

cost target to achieve 3-yr payback with existing utility rates

^{*} This considers only the building owner's costs; it does not include utility incentives or other benefits to the utility.

Stakeholder Engagement & next steps

- Trane and Emerson: Customer discovery workshop
 - Focus on installers, building managers make sure this technology looks familiar
 - Approach companies with large national accounts (i.e., that own a lot of buildings)
- Exelon corporation (electric utility)
 - NETenergy working with Exelon electric utilities for future demonstration in their territory

Next steps

- Scale-up of 2nd generation thermal storage design
- Integration of scaled-up 2nd generation design with vapor compression air conditioner for laboratory experiments and eventual field demonstration
- Development of technology that uses the c-PCM for cooling and heating

Thank You

National Renewable Energy Laboratory
Dr. Jason Woods | Sr. Research Engineer
720.441.9727 | jason.woods@nrel.gov

REFERENCE SLIDES

Project Budget

Project Budget: NREL received \$500,000 from DOE Office of Technology Transitions in December 2018. NETenergy provided \$175,000 in cost share (funds to NREL) and NETenergy, Emerson, and Trane provided \$425,000 of in-kind cost share.

Variances: The project was completed as planned.


Cost to Date: All funds have been spent

Budget History										
Start date: Dec. 2018 FY 2019 (past)			020 ast)	End date: June 2021 FY 2021 (current)						
DOE	Cost-share	DOE	Cost-share	DOE	Cost-share					
\$500,000	\$165,000	\$0	\$245,000	\$0	\$140,000					

Project Plan and Schedule

Project start: December 2018

Project end: June 2021



			FY19			FY20				FY21			
		Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
Complete	ed milestones												
FY19Q1	Composite PCM experimental results												
FY19Q2	Experimental results on composite PCM heat exchanger												
FY19Q3	Progress update on HVAC system design												
FY19Q4	System built and integrated with system-scale composite PCM HX												
FY20Q1	System installed and commissioning of 5-ton prototype												
FY20Q2	Progress update on 5-ton system experiments												
FY20Q3	Report on system experiments												
FY20Q4	Experimental data on next-generation HX prototype												
FY21Q1	Draft article on next-gen TES prototype, experiments and modeling												
FY21Q2	Building model and analysis for updated system design												
FY21Q3	Final Report for Project TCF-18-15537												