

# EE0008951 – CalWave Design for PacWave



Marcus Lehmann, PhD

CalWave Power Technologies Inc.

[marcus@calwave.energy](mailto:marcus@calwave.energy)

7/20/2022

*Disclaimer: this device was not manufactured and deployed under this award.*

# Project Overview

| Project Summary   | Project Information  |
|---|--|
| <ul style="list-style-type: none"><li>• The objective of this project is to evolve the xWave detailed design to island/remote markets scale.</li><li>• Ensure device design is suitable for deploying at the PacWave South test site.</li><li>• A smaller scale xWave system was developed with DOE support under FOA- 1663 and has completed 10-months of open ocean testing in San Diego; This project scales up the xWave architecture to a size relevant for remote and island communities.</li></ul>   | Principal Investigator(s)  |
|   | <ul style="list-style-type: none"><li>• Marcus Lehmann, PhD</li><li>• Thomas Boerner, PhD</li></ul>  |
|   | Project Partners/Subs  |
|   | <ul style="list-style-type: none"><li>• Sandia National Lab</li><li>• NREL</li><li>• Czero</li><li>• Glosten</li><li>• Evergreen Innovations</li></ul> |
|   | Project Status   |
| <ul style="list-style-type: none"><li>• Complete xWave design for 2-year operation at PacWave South</li><li>• Complete anchor, mooring, and interconnection design for PacWave South</li><li>• Integration of relevant design standards (IEC, IEEE)</li><li>• Updated device metrics using validated tools and methodologies, including simulations informed by scaled tank tests and Power Take-Off (PTO) bench tests (conducted under CalWave FOA-1837 / EE0008632 efforts)</li><li>• Validation of CalWave’s <i>Holistic Control</i> framework via load management and power generation profile optimization similar to wind turbines.</li><li>• Installation, operation, and maintenance (IO&amp;M) processes and risk mitigation strategies required for a deployment at PacWave South for 2 years.</li><li>• Confirmation of manufacturing methods and third-party feasibility studies.</li></ul> | Ongoing  |
|   | Project Duration   |
|   | <ul style="list-style-type: none"><li>• March 2020</li><li>• December 2022</li></ul>   |
|   | Total Costed (FY19–FY21)   |
|   | \$341k   |

# Project Objectives: Relevance and Approach

## MARINE ENERGY PROGRAM MISSION

Conduct research, development, demonstration, and commercial activities that advances the development of reliable, cost-competitive marine energy technologies and reduces barriers to technology deployment.

### FOUNDATIONAL R&D

Drive early-stage R&D on components, controls, manufacturing, and materials; develop and validate numerical modeling tools; improve resource assessments and characterizations; develop quantitative metrics to evaluate devices' potential.

### TECHNOLOGY-SPECIFIC SYSTEM DESIGN AND VALIDATION

Validate performance and reliability of marine energy systems through prototype testing, including in-water testing, for grid-scale, power at sea, and resilient coastal community markets.

### REDUCING BARRIERS TO TESTING

Enable access to open-water, grid-connected, and non-grid connected testing facilities; support environmental monitoring technologies, tools, and data collection to understand potential environmental risks and reduce costs.

### DATA ACCESS, ANALYTICS, AND WORKFORCE DEVELOPMENT

Improve access to and use of data, tools, and science, technology, engineering, and (STEM) resources to increase awareness of marine energy technology advances and lessons learned; reduce cost, time, and uncertainty for marine energy permitting; and develop a skilled marine energy workforce.

Direct relevance to Program Goals:

Primarily focuses on Technology-Specific System Design and Validation



# Project Objectives: Relevance and Approach

## Relevant Standards



## Manufacturing Lessons Learned (partially from previous projects)

1. Importance and methods for pressure testing
2. Alignment of steel hull structural welding standards (vessels/offshore structures)
3. Criticality of pre-deployment testing

### 042.3 Reference Standards

1. *Guide for Steel Hull Welding*, AWS, ANSI/AWS D3.5-93R, 1992.
2. *Structural Welding Code – Steel*, AWS, AWS D1.1/D1.1M:2015, 2015.
3. *Fabrication and testing of offshore structures*, DNV GL, DNVGL-OS-C401, 2018.
4. *Non-destructive testing*, DNV GL, DNVGL-CG-0051, 2015.
5. *Paints and varnishes -- Evaluation of degradation of coatings — Designation of quantity and size of defects, and of intensity of uniform changes in appearance — Part 3: Assessment of degree of rusting*, ISO, ISO 4628-3:2016.

# Project Objectives: Relevance and Approach



**WecOptTool**  
Controls Development



**CFD modeling <-> Controls**  
**Orcaflex modeling**



*\*image from FOA 1663 deployment*

## Approach:

1. Design optimization specifically for PacWave & target island commercial sites
2. IEC alignment supporting path towards certification
3. Detailed design/selection of anchoring system
4. Evolve numerical models and tools related to fluid-absorber-PTO interaction, utilizing resource assessments specific to PacWave & target islands; including extreme events
5. Catalog of metrics and improvements leading to long-term cost reductions

*Disclaimer: this device was not manufactured and deployed under this award.*



# Video



*Disclaimer: this device was not manufactured and deployed under this award.*


# Project Objectives: Relevance and Approach



**WecOptTool**  
Controls Development




CFD modeling <-> Controls  
Orcaflex modeling



*\*image from FOA 1663 deployment*

## Approach:

1. Design optimization specifically for PacWave & target island commercial sites
2. IEC alignment supporting path towards certification
3. Detailed design/selection of anchoring system
4. Evolve numerical models and tools related to fluid-absorber-PTO interaction, utilizing resource assessments specific to PacWave & target islands; including extreme events
5. Catalog of metrics and improvements leading to long-term cost reductions




*Disclaimer: this device was not manufactured and deployed under this award.*




# Project Objectives: Relevance and Approach

Open water demonstration results and lessons learned




Iteration on updated absorber geometry and controller



Validation in irregular waves

Scaled up PTO & test bench to PacWave Scale under FOA-1837



Hardware in the Loop (HIL)


## Approach:

1. IOM&D planning for PacWave; Risk evaluation & mitigation;
2. Certification planning and third-party verification of design to appropriate IEC Standards
3. Engagement with commercial & insurance industry to understand requirements for fully insurable and project financeable commercial deployments



# Project Objectives: Relevance and Approach

- First cohort deployment at PacWave
- Anchoring and mooring design
- Interconnection example
- Shore side interconnection buildout
- Permitting path



## Approach:

1. Develop Installation, Operations, Maintenance & Decommissioning (IOM&D) Plan including specifying vessels, partners and logistical resources local to PacWave test area
2. Grid integration planning
3. Geotechnical analysis to support anchor selection/design
4. Commercial plan



# Project Objectives: Expected Outputs and Intended Outcomes

## Outputs: xWave Design Basis



- Updated & Optimized Absorber size, geometry, structure
- Robust and proven standard controller
- Robust and proven advanced controller
- Additional advanced controller

## Outputs: Anchoring & mooring system for PacWave South



- Updated & Optimized anchoring and mooring layout
- Proper mooring type and size

*Disclaimer: this device was not manufactured and deployed under this award.*

## Outcomes:

- Detailed risk evaluation and mitigation early on
- Installation considering interconnection, mooring, device
- Operational planning including design load cases (IEC)
- Decommissioning and site remediation fundamental plan


**Outputs:** Detailed Risk Register; IOM&D plan

[illegible]

## Outcomes:

- DOE SAM evaluation
- DOE & OES subsystem metrics

**Outputs:** Updated metrics (macro level and detailed system level)





# Project Timeline

## FY 2020

- Derivation of Requirements
- Incorporation of standards
- Preliminary hull design & PTO Integration
- Preliminary electrical/SCADA/ *Holistic Control* design

## FY 2021

- IO&M Plan
- Preliminary mooring & anchor design
- Commercialization plan
- Preliminary design report & review meeting

# Project Budget

| Total Project Budget – Award Information |            |          |
|--|------------|----------|
| DOE                                      | Cost-share | Total    |
| \$1,800K                                 | \$450K     | \$2,250K |

| FY19   | FY20   | FY21   | Total Actual Costs<br>FY19–FY21 |
|--------|--------|--------|---------------------------------|
| Costed | Costed | Costed | Total Costed                    |
| \$0K   | \$31K  | \$310K | \$341K                          |

- Expenditures less than expected in FY21 due to delays in engaging external contractors due to pending internal design decisions.
- It is anticipated that these costs will catch up as external contractors are more actively engaged


# End-User Engagement and Dissemination

- Preliminary and Detailed design reports on MHK-DR
- Commercialization planning as designated task of the award
  - Conversations with end users: Islands, Off-Grid Markets, Navy, other remote locations
  - Conversations with community members
- Engagement with PacWave team
  - Resource assessment
  - Geotechnical data & Analysis
  - Grid integration planning
- MIT Clean Energy Prize Success Stories – Alumni Spotlight
- Highlighted in “Accelerating Energy Innovations for the Blue Economy” by the World Ocean Initiative
- Attended 9-hour course on Diversity, Equity, and Inclusion strategies for small companies



# Performance: Accomplishments and Progress

- Completed Preliminary Design & Report in 2021



- Completed Preliminary Commercialization Plan
- Successful completion of Preliminary Design Review
- Advancement of Detailed Design with further knowledge about PacWave site specifications

Participation in the following:

- Greentown Labs: ClimateTech Action Summit
- Rice Technology Venture Forum
- EnVest.Earth Presentation
- Solar Impulse Label Awarded

# Future Work

- Final hull design & manufacturing plan
  - Hull design approached from manufacturing standpoint / design for manufacturing
  - Coupled with supplier selection and tow plan
- Electrical system alignment with relevant standards / Validation of design according to standards
- Final mooring & anchor detailed design
- Final SCADA design & holistic control integration
- Final design report including estimates for project metrics
- Final design report & design review meeting
- Final commercialization plan
  
- Target Date of Final Design Review: September 2022

□ Building the fundamental basis for testing of the xWave at PacWave under FOA-2415 starting 2024

# Q&A