

DOE Office of Electricity TRAC Peer Review



PROJECT SUMMARY

DEMONSTRATION OF A 5 MVA MODULAR CONTROLLABLE TRANSFORMER (MCT) FOR A RESILIENT AND CONTROLLABLE GRID

The project team will design, build, and test a 5 MVA 24 kV/12 kV modular controllable transformer (MCT) and demonstrate its functionality, which includes modularity, interoperability through variable impedance and connection of multiple voltage levels, power flow control, and fail-normal design.























PRINCIPAL INVESTIGATOR Dr. Deepak Divan, Professor, Georgia Institute of Technology



WEBSITE https://cde.gatech.edu/





The Numbers

DOE PROGRAM OFFICE: **OE** – Transformer Resilience and **Advanced Components (TRAC)**

FUNDING OPPORTUNITY: **DE-FOA-0001876**

LOCATION: Atlanta, GA

PROJECT TERM: 06/01/2019 to 05/30/2022

PROJECT STATUS: Current Awardee

AWARD AMOUNT (DOE CONTRIBUTION): \$1,798,315

AWARDEE CONTRIBUTION (COST SHARE): \$495,032



Introduction: Grid Resiliency

• Key concerns of modern day grid:

- Grid Resiliency
- Cyber-Physical Security
- Rapid restoration following extreme events
- Dynamic Balancing of Load and Generation volatility.
- What is Grid Resiliency?
 - The ability of a system to return to an optimal/sub-optimal state following disturbances.
- The current infrastructure is not equipped to handle High Intensity Low Probability (HILP) events:
 - Weather-related emergencies (Hurricanes, Lightning Strikes)
 - Physical damage through terrorist attacks
 - Cyber-physical attacks
 - EMP bursts
- Critical Infrastructure sustaining damage:
 - Generators,
 - Transmission Line Network,
 - Substations and
 - Large Power Transformers (LPTs)





a measure for resiliency

Resiliency Metric

ould serve as esiliency

Large Power Transformers — Problems

- Large Power Transformers (LPTs) are critical pieces of lacksquaretoday's electricity infrastructure.
- Failure of a single LPT can disrupt electrical services to 30ullet100,000 customers.
- Following problems make LPTs extremely vulnerable and ۲ very difficult to replace upon failure
 - Unique designs
 - Aging assets,
 - limited flexibility embedded in the grid,
 - long turn-around times,
 - transportation delays and
 - foreign manufacturing infrastructure make.
- Case simulated on IEEE 30 bus system.
 - T6-10 fails and overloads T4-12
- What is the most resilient approach to handling loss of LPT contingency?



Scenario	LPT T4-12 (MVA)	LPT T6-10 (MVA)	Overload (MVA)
Base	95.2	68.8	0
LPT Outage	136.4	Outage	36.4

5 MVA Modular Controllable Transformer



✓ Fail normal design ✓ Manufacturability ✓ Transportability ✓ OEM requirements ✓ Overload capability

20000 per 20 cycles

Dual primary voltages 24 kV and 12 kV

+/- 0.9 pu

+/- 3%

5 MVA Modular Controllable Transformer



Daily Voltage Variation



Primary Innovation

- Modular controllable transformers (MCTs) consist of fractionally rated power converters integrated with standard HV transformers rated at 10-200 MVA
- MCTs provide unprecedented resiliency for high-impact low-frequency events through flexibility in configuration, easier transportability, and faster restoration time
- The MCT provides dynamic control to mitigate congestion issues and to integrate higher levels of variable renewable energy on the grid
- MCTs can enable multi-terminal AC systems (MTACs) at a fraction of the cost of multi-port DC systems (MTDCs)



Technology Status

2013-2016/ ARPA-E/G-CDPAR

- 1 MVA Xmr w/ 3% voltage injection capability
- 13 kV/1 MW Field Demonstration on a two feeder system

13 kV 1 MW Power Router Field Demo





2017/ARPA-E/G-CNT

- 13 kV 1 MVA Xmr + 5% control 3-level BTB converter
- Demonstrated in lab environment



12.47 kV/1 MW Back-to-back converter

2017 - 2018 / DOE/ MCT Phase -1

- Replace 200 MVA LPT with multiple small rated Modular Controllable Transformers (MCT) to improve grid resiliency and operational control (P/Q/V/I/Z).
- 139 kV/ 39 kV 56 MVA transformer w/8% voltage control.
- Delta Star designed 56 MVA LPT to
 - integrate fail-normal switch
 - minimize transportation and commissioning time
 - Shipped with bushings and oil filled

2019 - 2022 / DOE/ MCT Phase -2

Design, build and test a 5 MVA 24 kV/12 kV MCT and demonstrate the functionality, which includes modularity, power flow control, interoperability through variable impedance and connection of multiple voltage levels, storage integration, and fail-normal design









Project Objectives

- Design, build and test a 5 MVA 24 kV/12 kV MCT and demonstrate the functionality, which includes modularity, power flow control, interoperability through variable impedance and connection of multiple voltage levels, storage integration, and failnormal design
- Assess the impact and penetration level of the proposed MCT and evaluate cost-effectiveness compared to traditional LPTs



Build and Testing — Fail-Normal-Switch



TABLE 1 Summary of the protection mechanisms of proposed FNS under any possible abnormal conditions

Protection Mechanism

Suitable MOVs are selected for spikes and surges SCRs are designed to sustain 10-cycle 20kA short circuit current

FNS is informed by an active low fault signal from the converter, then SCRs and contactors are immediately closed

SCR gate drivers operate immediately by the active low trigger pulse. As their power is supplied by SPB, drivers continue operating without interruption until NC contactors close.

Contactor coils are fed by 110V AC. Contactors immediately close in case of 110V AC power loss since they are normally closed.

APB is designed to monitor induced overvoltage across FNS and operates both SCRs and contactors in case of an overvoltage.

FNS is proposed to immediately act in case of any cable cuts via active low/high control logic.

Any undetectable open circuits together with an APB malfunction and/or gate driver faults can be cleared by the proposed overvoltage self-triggering circuit for SCRs.

Build and Testing — 400kVA Converter





Build and Testing — Testing Plan

Test fail-normal switch at 20 kA for 20 cycles at NEETRAC, GT facility





Test 1.0 kV 400 kVA converter at CDE, GT lab



Test at 24 kV Grid Simulator facility, **Clemson University**





23.9 kV

CTRLBUS3

REDBOARD_TS3B T-body deadbreak 35kV elbows CB1 EXP EXP TR3) EXP TR2) EXP TR1) RDN EXP 1 min 4.5 MW Q12 1.5 MVar Controlled Base flows flows - 4.5 MW

Impact/Commercialization

- The MCT creates a building block for the future grid by integrating a modest level of dynamic control with a smaller rated modular transformer
- It provides flexibility in locating devices, increases system capacity through power routing, increases renewable energy integration through volt-VAR control, and improves overall grid resiliency and reliability
- It also addresses the logistical and economic barriers, by allowing the build of smaller rated standardized transformers that can be built and inventoried.

IP STATUS Basic IP is issued. Additional IP, if any, will be filed during the project duration.

Innovation Update — Enabling Multi-Terminal AC Systems with MCT

Multi-Terminal Systems (MTS) Advantages:

- MTS can provide additional **controlled** paths to transport or integrate large amount of power
- What more can MTS do?
 - ✓ Re-enforce transmission/distribution system
 - ✓ Improve system stability
 - ✓ Damp power oscillation between areas
 - ✓ Frequency control

DC solutions are costly and complex fault protection needed

Example of MTS implementation with HVDC-light



Advantages of MCT

- Uses standard large power transformer and widely available BTB converters
- Allows scaling to 100's of kV and 100's of MW with low-cost & small footprint
- Fail-normal approach retains basic functionality in case of converter failure.
- High impact at 10,000 bus system and Texas system (simulations)
- Multiple units can be deployed in one centralized location or in a dispersed fashion \checkmark
- Reduces cost and size for P/Q/V/I/Z control by 6X as compared with HVDC Light



MCT can provide the advantages of MTDC at a fraction of the cost and become the key enabler for future multi-terminal AC (MTAC) systems

Project schedule, deliverables, and current status

Budget: \$2,293,347 (\$1,798,315 + \$495,032)

Milestone	Completion Date	St
Project Management and Planning	6/31/2019	Com
Product Requirement Document	7/28/2019	Com
Fail-Normal Switch	11/30/2019	Com
5 MVA Transformer Design and Build	12/30/2021	Delayed (Lockdow
400 KVA Converter tested	12/30/2021	In-Progres
Test Site Preparation	1/30/2022	
Integration and Testing	5/30/2022	Delayed (Lockdow
System Analysis	5/30/2022	

atus

pleted

pleted

pleted

n & NCE execution)

ss (Delayed)

/n & NCE execution)

THANK YOU



U.S. DEPARTMENT OF OFFICE OF ELECTRICITY

Georgia Center for Tech Energy