

DOE Office of Electricity TRAC

Peer Review



PROJECT SUMMARY

Design, Deployment, and Characterization of the World's First Flexible Large Power

The project objective is to design, build, and deploy the world's first flexible large power transformer (LPT). The prototype is a 165kV, 60/80/100MVA autotransformer with three LV ratings including 57.5kV, 69kV and 80.5kV and a leakage impedance adjustable online from 4.3% to 9.3%. A flexible transformer protection system is also developed. Anticipated results include an >99.5% efficiency; a size and weight within 120% of comparable conventional LPT; compliance with IEEE standards C57.12.00 and C57.12.90; 6 months of field-testing data demonstrating comparable performance with conventional LPT.

PRINCIPAL INVESTIGATORS

Dr. Ibrahima Ndiaye, Technology Manager, GE Research Mr. Enrique Betancourt, Applied R&D Manager, Prolec GE

WEBSITE

https://www.ge.com/research/#

The Numbers

DOE PROGRAM OFFICE:

OE – Transformer Resilience and Advanced Components (TRAC)

FUNDING OPPORTUNITY:

DE-FOA-0001876

LOCATION:

Niskayuna, New York

PROJECT TERM:

10/01/2019 to 05/31/2022

PROJECT STATUS:

Incomplete

AWARD AMOUNT (DOE CONTRIBUTION):

\$2,375,922


AWARDEE CONTRIBUTION (COST SHARE):

\$593,981

Primary Innovation

A flexible autotransformer that has:

- 3 <u>configurable transmission</u> class voltage ratings at the secondary (e.g 161kV/138kV/115kV)
- a leakage impedance that is <u>adjustable</u> both online and offline in a wide range
- a leakage <u>impedance selection independent</u> from voltage configuration
- Used only existing and proven material



Impact/Commercialization

- Can serve a universal spare to increase the grid resiliency, reduce LPT spare inventory, and reduce US dependency on foreign suppliers
- Increase the grid flexibility in power flow and voltage regulation and make its operation more adaptable to higher penetrations of renewable generation.
- Increase the grid reliability for severe events with control of short-circuit levels.
- NPI plans are in process at Prolec GE

IP STATUS

- US 11,087,913 Transformer system issued
- US 2021/0151235 A1 Flexible transformer system published.
- A 3rd patent disclosure on protection is *pending*

Innovation Update

- Completed the design and manufacturing of a 165kV, 60MVA prototype of a flexible LPT with configurable secondary at 57.5kV, 69kV and 80.5kV and a variable impedance from 4.3% to 9.3% (at 60MVA).
- Deployed and energize on 9/3/2021 with Cooperative Energy at Columbia, MS the prototype which became the world's 1st flexible LPT in operation.
- Deployed together with the prototype a flexible protection system that can automatically update protection settings online upon impedance change
- Prototype is undergoing 6 months of field validation with 4 months continuous operation already accrued.

Prototype specifications

Autotransformer 60/80/100 MVA (12/16/20 MVA External Tertiary)

			<u>Connection</u>	<u>BIL</u>
VH	161 kV		Υ	650
VX	57.5/ 69 /80.5 kV		auto	350/150
VY	13.8 kV		D	110
3Ph	ONAN/ONAF/ONAF	60 Hz	65 °C	

On-line Impedance Variation range ZH-X = 4.2 to 9.3% @ 60 MVA

Voltage regulation (in LV line) +/- 10% of rated voltage in 16 taps Tested impedance values for 165kV/69kV configuration

IMPEDANCE @ 85°C												
kV BASE												
165.025 / 80.5 / 13.8				165.025 / 57.5 / 13.8								
kVA BASE												
69 000			60 000									
%Z H-X	%Z H-Y	%Z X-Y	%Z H-X	%Z H-Y	%Z X-Y	%Z H-X	%Z H-Y	%Z X-Y				
			9.34	4.495	3.060							
			8.714	4.611	3.125							
			8.125	4.734	3.216							
			7.568	4.861	3.324							
			7.045	4.992	3.45							
			6.549	5.124	3.597							
			6.090	5.254	3.762							
			5.666	5.395	3.943							
			5.267	5.535	4.144							
			4.918	5.679	4.37							
,			4.599	5.829	4.617							
			4.309	5.981	4.885							
		kVA BASE 69 000	165.025 / 80.5 / 13.8 kVA BASE 69 000	165.025 / 80.5 / 13.8 165 KVA BASE 69 000 %Z H-X	RV BASE	RV BASE	No No No No No No No No	Note				

Designed and tested according to

• IEEE C57.12.00 IEEE Std for General Requirements of Liquid-Immersed Transformers

Connoction

DΠ

IEEE C57.12.90 IEEE Std Test Code for General Requirements of Liquid-Immersed Transformers

Design and commissioning of the prototype

On Load Voltage Tap Changer

HV, LV and TV bushings

PROLEC %

Flexible voltage Connection Board

Impedance variation automatic tap changer.

MS3000


(remote monitoring)

Auxiliary windings multiple leads.

Proprietary information

Internal layout of the designed flexible LPT prototype

Ztap position (MS3000)





Transformer cabinet

(CTs, RTDs terminals)




Impedance Tap changer

(Controller)




Impedance Tap changer


Field validation site



Commissioning of the augmented protection relay




Development and commissioning of an augmented protection relay for the flexible LPT



IEEE Std C57.109-2018 IEEE Guide for Liquid Immersed Through Fault Current Duration

Protection and monitoring system





World 1st Flexible LPT ready for operation




Prototype as installed at Cooperative Energy's 161kV substation in Columbia MS

Energization of the prototype






Highest inrush current was 437A (1.22 of full load current); Significantly lower level as compared to conventional transformers.




14MVA throughput power after closing of LV breaker

Remote monitoring system



Remote monitoring system reporting all the operating conditions and health status for the 6 months validation period and beyond

Remote monitoring system



Prototype loading since energization (9/3/2021). Peak load of 41MVA has been observed

The team!



The development and commissioning team, September 3rd, 2021, Columbia MS

Acronyms

CT: Current transformer

GE: General Electric

HV: High voltage

IEEE: Institute of Electrical and Electronic Engineers

LV: Low voltage

LPT: Large power transformer

MVA: Mega volt ampere (transformer power rating unit)

NPI: New Product Introduction. A GE process for new products

commercialization

PT: Potential transformer

SCADA: Supervisory control and data acquisition

Ztap: Position of the flexible impedance tap changer

THANK YOU

