# 

# DOE Office of Electricity TRAC Peer Review



## **SSPS Controller: Hardware in Loop** Validation

## PRINCIPAL INVESTIGATOR

Dr. Radha Sree Krishna Moorthy, R&D Associate Staff, ORNL

## **PROJECT SUMMARY**

**Project** aims at validating the hierarchy (controls, communication & optimization) associated with SSPS in a controller hardware in the loop (CHIL) environment

**Develop the SSPS controller and the associated framework** 

**Development of device controls for SSPS nodes/hubs** 

□ Validation of the SSPS framework through use case

**Develop the required CHIL test benches to validate the framework** 





# The Numbers

## DOE PROGRAM OFFICE: **OE** – Transformer Resilience and **Advanced Components (TRAC)**

FUNDING OPPORTUNITY: AOP

LOCATION: **Knoxville**, **Tennessee** 

**PROJECT TERM:** 09/01/2021 to 08/30/2023

**PROJECT STATUS:** Ongoing

AWARD AMOUNT (DOE CONTRIBUTION): \$500,000

AWARDEE CONTRIBUTION (COST SHARE): **\$0** 

**PARTNERS**: N/A

# Team - ORNL



Radha Sree Krishna Moorthy Principal Investigator & System Integration



Madhu Chinthavali SSPS Architecture Michael Starke Controls,

Communication &

Optimization




Joao Pereira Advanced Algorithms Development




### Benjamin dean Communication & Software Development

# Innovation: Futuristic Grid Architecture

## Architecture for decentralized control of grid to support futuristic assets, loads and hybrid ac/dc configurations



# Innovation: SSPS Controller Framework




### **Potential Features:**

- □ Steady-state and dynamic coordination to maximize the resource utilization & downstream system features
- Cloud based computations
- □ AI techniques to learn and tune forecasts and identify system needs
- Transactive market for nodes & hubs
- □ Shares information with the distribution management system (DMS)/ Advanced Distribution Management System(ADMS)/ other hierarchical controller




# Innovation: Generalized Framework for SSPS


Framework to effectively use the features of the downstream systems the nodes/hubs and the fundamental building blocks



## Innovation Update #1: Technical Approach



**Base Case:** Operation of inverter-based resources without coordination to prove the need for coordination & to prove the need for hierarchical control.



## Innovation Update #2: Controller Coordination Techniques

- **Problem Objective:** Coordinate the downstream nodes/hubs/other entities to regulate the voltage/balance phases/reduce distortions along the feeder under dynamic and steady-state conditions considering all uncertainties.
- □ Techniques: Mixed Integer Linear Programming (MLIP) & Advanced algorithm-based techniques

### Mixed Integer Linear Programming (MILP)

- Optimization formulation considering economics i.e., cost of P & Q
- □ Allocation for reserves for dynamic conditions/operation
- □ Considers reserves, downstream nodes/hubs architecture, available control modes etc.


**Advanced Algorithm-Based** Techniques

- □ Hybrid techniques AI & Machine learning
- Training data set generation for different operating conditions. Variables include grid parameters, hubs/node parameters etc.
- Problem formulation based on feeder losses, placement of the nodes/hubs.
- System training and testing



## Innovation Update #2: Feeder Selection

- □ Modified IEEE 34 bus system has been selected based on the following criteria: small to medium sized feeder (complexity) with capability to emulate the need for grid functions (voltage regulation, phase balancing, power factor correction and harmonic filtering).
- Placement of the hubs/nodes has been decided on the feeder sensitivity



\*\*A Distribution System Test Feeder for DER Integration Studies, Dharmawardena, H. et all - 2018

## **Milestone Update**

**Task:** Development of required models in a real-time (RT) platform

Quarters	Tasks	Sept (21) – Nov (21)	Dec (21) – Feb (22)	Mar (22) - May (22)	Jun (22) – Aug (22)
BP1 - Q1	Identification of the reference feeder model to validate the framework & architecture	Completed			
BP1 - Q2	Development of optimization formulation for the feeder		In Progress		
BP1 - Q3	Development and validation of hub and node models in RT				
BP1 - Q4	Development of futuristic grid architecture				

**Deliverable:** Model and optimization framework for hierarchical/distributed controls

## **Milestone Update**

**Task:** Development and validation of SSPS controller

Quarters	Tasks	Sept (22) – Nov (22)	Dec (22) – Feb (23)	Mar (23) - May (23)	Jun (23) – Aug (23)
BP2 – Q1	Development and validation of node & hub controllers				
BP2 – Q2	Development and validation of the SSPS controller				
BP2 – Q3	Integration of SSPS controller with the nodes & hubs in RT platform				
BP2 – Q4	Demonstrate use case scenarios to validate the futuristic grid architecture				

**Deliverable:** SSPS controller and validation of futuristic grid architecture

## **Risks**

□ No anticipated risks or delays

## **Future Work**

□ Formulate the optimization problem/objective function and constraints for the problem


Elaborate on the architectural details for SSPS 

Develop the test bed for the validation of the framework

# Impact/Commercialization

## Impact:

Provide solutions for real world grid modernization/integration problems through advanced flexible integrated open research platforms





# Impact/Commercialization

### **Invention Disclosures Filed:**

□ M. Chinthavali, M. Strake and R. S. K. Moorthy, "SSPS Controller Architecture: Coordinated Optimization and Control of Multiple Solid-state Power Substations in Electrical Distribution Network".

# **THANK YOU**



# U.S. DEPARTMENT OF OFFICE OF ELECTRICITY