



中国石化
SINOPEC

Million-Tonne CO₂ Capture, Utilization and Storage(CCUS) The Qilu-Shengli Oilfield Project



中国石油化工集团有限公司
SINOPEC GROUP

SINOPEC, CHINA

June 13, 2023

Outline

1. Introduction

2. Engineering Practice

3. Innovative Technologies

4. Summary

1. Introduction

◆ The Qilu-Shengli Oilfield Project

The largest CCUS project in China.



(1) CO₂ captured from Qilu Petrochemical Company

(2) Through **114.5 km** pipeline to Shengli Oilfield for CO₂-EOR and storage

(3) Injected into low permeability reservoirs, expected EOR by **11.6%**

1. Introduction

◆ Project timeline

Date	Events
June 9, 2013	CO ₂ high pressure miscible flooding pilot test at block G89-1&F142.
June 11, 2021	The preparation of the Qilu-Shengli Oilfield CCUS Project completed, including reservoir engineering, surface engineering, injection and production engineering, and monitoring engineering.
July 5, 2021	Sinopec began the construction of China's first Million-Tonne CCUS Project : Qilu-Shengli Oilfield CCUS Project.
April 4, 2022	Pilot operation of the Million-Tonne CCUS Project.
August 25, 2022	The CCUS demonstration project was fully completed and operated , and runs well up to now.

Outline

1. Introduction


2. Engineering Practice

3. Innovative Technologies

4. Summary

Sinopec

One of the largest integrated energy and chemical companies in the world.



Sinopec has many advantages of engaging in all stages of the CCUS process.

(1) CO₂ capture engineering

- The exhaust emissions from coal gasification are initially captured.
- The captured exhaust is further processed through a series of steps, including cooling, dehydration, liquefaction, and purification using a distillation tower.
- The liquid CO₂ purity > 99%.

Compression unit



Liquefaction purification unit



Propylene refrigeration unit

CO₂ storage unit



(2) CO₂ pipeline engineering

- The Qilu-Shengli Oilfield CO₂ pipeline, 114.5-kilometer long.
- The maximum transmission capacity of 1.7 million tonnes per year.
- The pipeline is under operation.



(3) Surface engineering

The injection, gathering, and reinjection of produced gas has been completed.

Injection system

- 15 new injection plants
- Skid-mounted equipment
- Regional information center




Oil gathering system

- 2 regional oil gathering centers East/West, Enclosed produced gas and liquid gathering, and processing system




Reinjection system

- Produced gas is pressurized and reinjected to formation



(4) CO₂ flooding and storage engineering

➤ Project site: block G89&F142 in Jiyang Basin




- 48 km² area
- Geological reserve 25.62 mts
- Depth 3000-3500m
- Thin layers, low permeability (< 5mD), strong heterogeneity
- Underground viscosity < 3cP.

(4) CO₂ flooding and storage engineering


- 73 injectors 166 producers
- Expected oil production 351,000 ts/yr

- Expected EOR by 11.6%
- Expected incremental oil production 2.97 mts

The Qilu-Shengli oilfield project well pattern



Development technical policies




(5) Monitoring engineering

- Geological safety: fault and cap sealing ability evaluation
- Well integrity: injection-production wells and cement rings evaluation
- Environmental risks: real-time monitoring of air, soil and water


Faults and caps evaluation

Safety assessment of faults



To realize dynamic tracking of pressure field and stress field based on Multi-field coupling simulation. The faults and caps stability was evaluated according to the stress Mohr circle.

Well bore integrity




Eight-sector detection

Helium gas seal detection

Quantitative evaluation of casing condition by "40 arm imaging+electromagnetic flaw detection".

Environmental monitoring



An integrated technology of all-temporal and spatial CO₂ safety monitoring and early warning was constructed.

Outline

1. Introduction

2. Engineering Practice

3. Innovative Technologies

4. Summary

(1) CO₂ capture technology

- Low temperature distillation: Propylene refrigeration, -23°C, Pressure, 2 MPa.
- Low energy consumption: waste heat utilization, energy recovery and gas separation pressure optimization, the energy consumption reduce by 10%.
- The capture cost has been reduced by 40%.

Efficient packing in extraction tower




Waste heat / residual pressure utilization technology




(2) CO₂ pipeline transportation technology

- Designed initial pressure: 10 MPa. End pressure: 9 MPa.
- Pressure control: less than 1.0MPa per 100km.
- Stability of CO₂ phase: prevent the generation of hydrate.

Phase curves with different impurities



CO₂ density curves at different pressures and temperatures



(3) CO₂ injection technology

◆ High pressure injection system

- The first set of equipment in China: storage tank, injection pump, measurement unit, and partial pressure injection.
- The injection pressure reaches more than 40 MPa.

Storage tank



- Automatic stabilized pressure
- Stable constant low temperature

Injection pump




- High-pressure gas-liquid separation device
- High-efficiency airtight injection

Measurement unit



- Improved metering accuracy
- Inject multiple wells at the same time



Injectors



(4) CO₂ flooding and storage technology

◆ CO₂ high pressure miscibility flooding

Build a high-pressure flooding system, to improve miscibility, expand sweep efficiency more than 30%, greatly increase recovery(>8%) and CO₂ storage.




(4) CO₂ flooding and storage technology

◆ Injection optimization

- Gas-water alternating technology: dynamic gas-water ratio, and solves gas channeling.
- The initial injection gas slug was 0.1PV, changed to 0.05PV after 1PV.
- Raise the sweep **efficiency** by 14% and improve the oil recovery by 11%.

Maximizing the three-phase resistance


The injection gas-water ratio for the required maximum flow resistance varies depending on the remaining oil saturation



Distribution of resistance for three-phase

Dynamic gas-water ratio

Adjusting the gas-water ratio to ensure high resistance throughout the entire process




Dynamic gas-water ratio optimization

Expand swept volume

Sweep efficiency

Recovery efficiency




Before and after implementation

Before and after implementation

(4) CO₂ flooding and storage technology

◆ Produced gas reinjection technology


- The technology consists of pretreatment, low-temperature liquefaction separation and low-temperature liquid CO₂ reinjection.
- Produced gas reinjected to formation, the CO₂ dynamic storage rate > 90%.



(5) Monitoring technology

A monitoring system based on reservoir, wellbore, surface, and atmosphere environment has been established to realize real-time dynamic warning and monitoring.

Monitoring area



Vertical:
Atmospheric
Near surface
Deep surface




Horizontal:
core area
(20km×10km)
comparison area
(5km outreach)

Monitoring items

Items	Points	Frequency
Atmosphere	Core area: 12; Comp. area: 2 in upwind direction 4 downwind direction	Core area: Online continuous monitoring; Comp. area: 1/mth
Surface-soil gas	Core area(1km)150; Comp. area(4km)40; Stable isotope of C13: 13 around injector.	Background value 1/mth, during injection 1/3mths
Near surface-soil gas, ground water	250m above the fault 1, No.1 fault 8; two fully penetrated faults 2; sampling depth 30m.	Background value 1/mth, during injection 1/mth
deep subsurface	2200m near the fault	Background value 1/mth, during injection 1/mth
Wellbore integrity monitoring	injectors 68、others 30	1 before injection; 10% of injectors during injection period annually
Vegetation (optional)	30km x 17km	Background value 1/mth, during injection 1/3mths
Ground deformation (optional)	30km x20km	Background value 1/mth, during injection 1/3mths

Fault monitoring




Possible leaking faults

Items	Fault No.	Possible leakage direction	Well	Coordinate	Unit	Installation location
1	1	Southeast	F142-8-2	N37°19'30.70" E117°95'22.65"	Dongsheng Corp. Binbo branch	Southeast corner
2	1	Southeast	F142-8-2	N37°14'17.16" E118°05'71.73"	Dongsheng Corp. Binbo branch	Southeast corner
3	2	Southeast	G89-X21	N37°76'32.11" E117°89'44.81"	Chunliang plant. Daluhu Branch	Southeast corner
4	2	Southeast	F143-4	N37°57'14.21" E117°91'53.36"	Dongsheng Corp. Binbo Branch	Southeast corner
5	3	Southeast	G891-8	N37°19'11.69" E117°32'62.63"	Chunliang plant. Zhenglizhuang Branch	Southeast corner
6	4	Southeast	G891-5	N37°18'47.82" E117°78'63.19"	Chunliang plant. Zhenglizhuang Branch	Southeast corner

Project benefits


- The daily injection is 1,200-2,000 tonnes, with 0.47 million tonnes of CO₂ injected. The daily oil production is 302 tonnes, with 26,500 tonnes of incremental oil production obtained.
- E.g Fan 142-20, the oil production rate increases from 8 t/day to 40 t/day.
- Operating cost \$35/bbl , balancing oil price \$65/bbl.

Fan 142-20



- Well pattern : parallel to the direction of main stress and bar sand
- To date, a total of 17,000 tons of CO₂ has been injected

Fan 142-20 production curve



Outline

1. Introduction


2. Engineering Practice

3. Innovative Technologies

4. Summary

Summary

- (1) China has successfully established its 1st million-tonne CCUS demonstration project and the 1st 100 kilometer CO₂ transmission pipeline.
- (2) The project design, construction and equipment development are completed by Sinopec.
- (3) The Qilu-Shengli Oilfield Project is operated well and safely.
- (4) Valuable experiences accumulated for large-scale CCUS projects, rendering support in the construction of hub and industrial clusters in China.



THANK YOU!



CCUS Project in Shengli Oilfield