

## Queued Up: Status and Drivers of Generator Interconnection Backlogs

Joseph Rand, Lawrence Berkeley National Laboratory

Transmission and Interconnection Summit June, 2023

This work was funded by the U.S. Department of Energy under Contract No. DE-AC02-05CH11231. The views and opinions of the authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof, or The Regents of the University of California.

Image source: Licensed from Shutterstock



### Outline

Current status of U.S. interconnection queues

Evidence of a problem:

- 1. Delays and bottlenecks
- 2. Increasing interconnection costs

Looking ahead: Reforms and solutions

NOTE: Focus on transmission interconnection, not distribution/DER interconnection

Thanks to DOE, and especially the i2X program, for supporting this work

## Current grid interconnection process was designed in 2003 for an electricity system with fewer, larger, centralized power plants



- Transmission grid operators
  require new projects looking to
  connect to the grid to undergo a
  series of impact studies
- These studies determine the grid upgrades necessary to allow projects to connect safely and reliably, and allocate the cost of those upgrades
- Withdrawals can result in multiple re-studies: a vicious cycle of delays, backlogs & higher costs

Source: Derived from image courtesy of Lawrence Berkeley National Laboratory and used with permission. | GAO-23-105583



## There has been a substantial increase in annual interconnection requests (both in terms of number and capacity) since 2013; over 700 GW added in 2022 alone



Decrease in new requests in 2022 likely driven by "pauses" on new requests in CAISO and PJM (see slide 7).



Notes: (1) This total annual volume includes projects with a queue status of "active", "suspended", "withdrawn", or "operational". (2) All values – especially for earlier years – should be considered approximate.

### Active capacity in grid interconnection queues (~2,000 GW) exceeds the installed capacity of the entire U.S. power plant fleet (~1,250 GW)



**Entire U.S. Installed Capacity vs. Active Interconnection Queues** 

More than 95% of active capacity in interconnection queues is zero-carbon



#### Source: Berkeley Lab, "Queued Up". 2023

Notes: (a) Hybrid storage in gueues is estimated for some projects. (b) Total installed capacity from EIA-860, December 2022.

### Especially strong developer interest in solar (~947 GW) and storage (~680 GW); Hybrid plants represent a large fraction of proposed solar and storage



#### See <u>https://emp.lbl.gov/queues</u> to access an interactive data visualization tool.



Notes: (1) \*Hybrid storage capacity is estimated for some projects using storage:generator ratios from projects that provide separate capacity data, and that value is only included starting in 2020. Storage duration is not provided in interconnection queue data. (2) Wind capacity includes onshore and offshore for all years, but offshore is only broken out starting in 2020. (3) Hybrid generation capacity is included in all applicable generator categories. (4) Not all of this capacity will be built.

## Active queue capacity highest in the non-ISO West (598 GW), followed by MISO (339 GW) and PJM (298 GW). Solar and storage requests are booming in most regions.





Notes: (1) \*Hybrid storage capacity is estimated for some projects using storage:generator ratios from projects that provide separate capacity data, and that value is only included starting in 2020. Storage duration is not provided in interconnection queue data. (2) Wind capacity includes onshore and offshore for all years, but offshore is only broken out starting in 2020. (3) Hybrid generation capacity is included in all applicable generator categories. (4) Not all of this capacity will be built.

7

Only 21% of projects that applied for interconnection prior to 2018 have been built – 72% have been withdrawn (7% are still actively trying!)



One consequence of high withdrawal rates is the need to restudy the projects that remain in the queue, increasing uncertainty in cost outcomes and further elongating the process



### **Evidence of a Problem #1: Increasing timelines**



Source: Derived from image courtesy of Lawrence Berkeley National Laboratory and used with permission. | GAO-23-105583

### The mean duration prior to withdrawing has edged higher in recent years; later-stage withdrawals are becoming more common

Withdrawn Date



 Some recentlywithdrawn projects are waiting longer in the queues before making the determination to withdraw

Commercial Operations (COD)

 Later stage withdrawals can be costly for developers and can disrupt assumptions built into other projects' interconnection studies, necessitating re-studies in some cases and increasing study durations



Duration Analyzed:

Interconnection Request (IR)

## Study duration exceeds 3 years in most grid operating regions; ERCOT and Southeast are faster. Battery projects tend to be processed more quickly than other types





Notes: (1) Data are only shown where sample size is >2 for each region and year. (2) Not all data used in this analysis are publicly available. (3) "West" includes PacifiCorp, Public Service Co. of New Mexico, Idaho Power; "Southeast" includes Southern Company, Seminole Electric Cooperative.

### Some delays are also evident *outside* of the interconnection process: procurement / offtake, local permitting, construction, etc.





Notes: (1) Data were only available for 737 projects across 5 ISO/RTOs and one utility (Southern Company), out of 3,846 total "operational" projects in the full dataset. (2) Not all data used in this analysis are publicly available.

12

## The median duration from interconnection request to commercial operations date continues to rise, reaching ~5 years for projects completed in 2022; Longest in CAISO





Notes: (1) In-service date was only available for 6 ISOs (CAISO, ERCOT, ISO-NE, NYISO, PJM, SPP) and 5 utilities (Duke, LADWP, PSCo, SOCO, WAPA) representing 58% of all operational projects. (2) Duration is calculated as the number of months from the queue entry date to the in-service date.



### **Evidence of a Problem #2: Increasing cost to connect**



## Interconnection costs have grown over time in all studied regions, driven primarily by broader network upgrades (not local interconnection costs)



Region	"Earlier" period	"Recent" period
MISO	(2000-) 2018	2019-2021
SPP	2010-2019	2020-2022
PJM	2000/2017 - 2019	2020-2022
NYISO	2006-2016	2017-2021
ISO-NE	2010-2017	2018-2021

- Average interconnection costs have grown across regions and request types:
  - Often doubling for projects that have completed all studies
  - increasing even more for active projects currently moving through the queues.
  - Projects that withdraw have the highest interconnection costs



### Renewables and storage often face higher interconnection costs than natural gas



Offshore Wind costs exclude transmission investments offshore

- Solar costs are fairly consistent across regions:
  Completed: 5-10% of total project Capex
  Withdrawn: 20-40%
- Wind costs have greater variation:
  Completed: 3%-16% of total project Capex
  Withdrawn: 10%-40%
- Storage expensive despite (or because of?) its locational flexibility

#### *Hypothesis:*

Renewables are often located in more rural areas where the existing transmission system is weaker, requiring costlier network upgrades.



### A "wicked" problem: multifaceted drivers of interconnection backlogs

**General sentiment:** we are asking the serial queue process designed in 2003 to do too much. Reforms are needed, but also perhaps a fundamental re-thinking is required given clean energy transformation demanded.

Transmission expansion has been *limited over the last decade, focused primarily on local reliability upgrades* 

Developers use queue requests for data collection given low information *transparency, low entry cost, high network upgrade costs,* and *uncertain costs* given serial nature and re-studies

Lack of *standardization, inaccurate study data* & assumptions, low consideration of *grid-enhancing technologies*, generator technology changes, *network cost assignment*, and late *withdrawals* 

Bulk grid not developing rapidly, leading to *inadequate transmission* and to high *network upgrade costs assigned* to generators in queue

Enormous *increase in number and capacity* of projects in queues, creating *workflow and workforce challenges* when relying on existing tools and administrative processes

Multi-year *queue delays* leading to re-studies, *reliability concerns, high generator-pays upgrade costs*, and frustrated stakeholders (developers and transmission operators alike)



A vicious cycle: the increasing number of requests increase delays and uncertainty, which further incentivizes developers to submit more requests

## Proposed reforms are underway at FERC and among most RTOs, but more opportunities remain

### FERC NOPR: Queue Reform

- Cluster studies; first ready, first served; higher fees & readiness criteria
- *Timeline, process, data, and reporting* requirements for transmission providers
- Improved and more coordinated process for *affected system studies*
- Revisions to study data & assumptions to better match real system/conditions and ensure reliability
- Consideration of *grid-enhancing technologies*

### Possibilities Beyond FERC's Interconnection NOPR

- Proactive transmission planning and enhanced coordination between transmission planning and interconnection
- Enhanced *data transparency* on transmission availability and possible interconnection costs to pre-screen interconnection requests
- Increasing the *automation* of the interconnection study processes
- More interconnection resources and staff to speed the process; ability for developers to hire third-parties
- Revisiting the *impact threshold criteria* that result in network upgrade cost assignment, and review energy-only interconnection process
- *Revisions to interconnection cost allocation:* reform of participant funding for network upgrades



Contact: Joseph Rand (jrand@lbl.gov)

#### More Information:

- Visit <u>https://www.energy.gov/eere/i2x</u> to learn about and participate in the DOE's i2X program
- Visit <u>https://emp.lbl.gov/queues</u> interconnection queue analysis and data
- Visit <a href="https://emp.lbl.gov/interconnection\_costs">https://emp.lbl.gov/interconnection\_costs</a> for research on generator interconnection costs

#### Acknowledgements:

This work was funded by the U.S. Department of Energy's Office of Energy Efficiency and Renewable Energy, in particular the Solar Energy Technologies Office and the Wind Energy Technologies, in part via the Interconnection Innovation eXchange (i2X). We thank Ammar Qusaibaty, Michele Boyd, Juan Botero, Cynthia Bothwell, Jian Fu, Patrick Gilman, Gage Reber, and Paul Spitsen for supporting this project.

#### Disclaimer

This document was prepared as an account of work sponsored by the United States Government. While this document is believed to contain correct information, neither the United States Government nor any agency thereof, nor The Regents of the University of California, nor any of their employees, makes any warranty, express or implied, or assumes any legal responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by its trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof, or The Regents of the University of California. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof, or The Regents of the University of California.

Ernest Orlando Lawrence Berkeley National Laboratory is an equal opportunity employer.

#### **Copyright Notice**

This manuscript has been authored by an author at Lawrence Berkeley National Laboratory under Contract No. DE-AC02-05CH11231 with the U.S. Department of Energy. The U.S. Government retains, and the publisher, by accepting the article for publication, acknowledges, that the U.S. Government retains a non-exclusive, paid-up, irrevocable, worldwide license to publish or reproduce the published form of this manuscript, or allow others to do so, for U.S. Government purposes





### Appendix



### **Methods and Data Sources**

- Data collected from interconnection queues for 7 ISOs / RTOs and 35 utilities, which collectively represent >85% of U.S. electricity load
  - Projects that connect to the bulk power system, not behindthe-meter
  - Includes projects in queues through the end of 2022
  - The full sample includes:
    - 3,846 "operational" projects
    - 10,262 "active" projects
    - 374 "suspended" projects
    - 15,672 "withdrawn" projects
- Hybrid / co-located projects were identified and categorized
  - Storage capacity in hybrids (separate from generator capacity) was estimated based on available data for some projects
- Note that being in an interconnection queue *does not guarantee* ultimate construction



Coverage area of entities for which data was collected Data source: Homeland Infrastructure Foundation-Level Data (HIFLD) A full list of included balancing areas can be found in the Appendix Note that service areas can overlap No data collected for Hawaii or Alaska



### **High-Level Findings**

#### Developer interest in solar, storage, and wind is strong

- Over 10,000 projects representing 1,350 gigawatts (GW) of generator capacity and 680 GW of storage actively seeking interconnection
- Most (~1260 GW) proposed generation is zero-carbon
- Hybrids comprise a large share of proposed projects



#### Completion rates are generally low; wait times are increasing

 Only ~21% of projects (14% of capacity) requesting interconnection from 2000-2017 reached commercial operations by the end of 2022



- Completion rates are even lower for wind (20%) and solar (14%)
- The average time projects spent in queues before being built has increased markedly. The typical project built in 2022 took 5 years from the interconnection request to commercial operations<sup>1</sup>, compared to 3 years in 2015 and <2 years in 2008.

#### Proposed capacity is widely distributed across the U.S.

- Substantial proposed solar capacity exists in most regions of the U.S.; 947 GW of solar active in queues
- Wind capacity is highest in NYISO, the non-ISO West, PJM, and SPP, with increasing share of offshore projects
- Storage is primarily in the West and CAISO, but also strong in ERCOT, MISO, and PJM; much in hybrid configurations
- Only 82 GW of gas capacity active in the queues, less than 10% of active solar capacity





### Active capacity in queues (>2,000 GW) exceeds installed capacity of entire U.S. power plant fleet (~1,250 GW), as well as peak load and installed capacity in most ISO/RTOs



Comparisons of queue capacity to installed capacity or peak load should also consider generators' contributions to adequacy, for resource example their "effective load carrying capability" (ELCC). As variable resources, solar and wind contribute a smaller percentage of their nameplate capacity to resource adequacy compared to dispatchable generation like natural gas.

Decarbonizing the electric sector therefore requires higher levels of *installed* solar and wind capacity to achieve the same resource adequacy contributions. High levels of storage can offset this need to some degree. Electrification of buildings and transport will also result in load growth.



Notes: (a) Hybrid storage in queues is estimated for some projects. (b) Total installed capacity from EIA-860, December 2022. (c) RTO installed capacity from FERC Annual State of the Markets Report (https://www.ferc.gov/media/report-2021-state-markets). Peak load data from RTO websites.

Active interconnection requests are growing in all regions; highest for solar (~950 GW), storage (~680 GW), and wind (~300 GW, including 113 GW offshore)



Solar and storage requests are booming in most regions; after being overwhelmed in 2021, CAISO and PJM "paused" new requests in 2022



# Interest in hybrid plants has increased over time: Hybrids comprise 52% of active storage capacity (358 GW), 48% of solar (457 GW), and 8% of wind (24 GW)



<sup>\*</sup>Hybrid storage capacity is estimated using storage:generator ratios from projects that provide separate capacity data

**Gas Hybrids** include: Gas+Solar+Storage (13 GW), Gas+Storage (0.4 GW), Gas+Solar (0.3 GW) [not shown above]



Notes: (1) Some hybrids shown may represent storage capacity added to existing generation; only the net increase in capacity is shown; (2) Hybrid plants involving multiple generator types (e.g., Wind+Solar+Storage) show up in all generator categories, presuming the capacity is known for each type.

Capacity-weighted completion rates are even lower: Only 14% of all capacity requesting interconnection from 2000-2017 is online; 16% of wind capacity, 10% of solar capacity



Percentage of capacity online by region:

Percentage of capacity online by generator type:





Notes: (1) Completion rate shown here is capacity-weighted, calculated as the capacity that is online by end of 2022 divided by the total capacity requesting interconnection each year. (2) Includes data from 7 ISO/RTOs and 26 utilities.

## The median duration from request to withdrawn date ticked up in 2022; wind projects typically spend more time in queues than gas or solar prior to withdrawing





Notes: (1) Withdrawn date was available for 6,323 projects from 5 ISOs and 6 utilities. (2) Duration is calculated as the number of months from the queue entry date to the date the project was withdrawn from queues.

## After falling from a 2012 peak, the typical duration from interconnection request (IR) to interconnection agreement (IA) increased sharply since 2015, reaching 35 months in 2022





Notes: (1) Sample includes 3,348 projects from 6 ISO/RTOs and 5 non-ISO utilities with executed interconnection agreements since 2005. (2) Not all data used in this analysis are publicly available.

## There is a clear step change in IR to IA duration between "small" (<20 MW) and "large" (>20 MW) generator interconnection procedures



Notes: (1) Box-plot includes projects executing interconnection agreements from 2010-2022. (2) Duration is calculated as the number of months from the queue entry date to the interconnection agreement date.

## IR to COD timelines are longest in CAISO, NYISO, and SPP; solar and wind projects typically take longer than other types, with standalone battery projects moving fastest to completion





Notes: (1) In-service date was only available for 6 ISOs and 5 utilities representing 58% of all operational projects; . (2) Duration is calculated as the number of months from the queue entry date to the in-service date.

## Larger projects have longer development timelines: Typical IR to COD duration increases monotonically by project size (MW)



 For the smallest projects in our sample (<5 MW), the median project came online less than 2 years (20 months) after the interconnection request

Commercial Operations (COD)

- The median 5-20 MW project, meanwhile, takes nearly 3 years (33 months) from IR to COD
- Larger projects spend even more time in the interconnection and development process, with the median 100-200 MW project taking >4 years and the median 200+ MW project taking over 4.5 years (55 months) from IR to COD



Notes: (1) Box-plot includes projects reaching commercial operations from 2010-2022. (2) Includes data from 6 ISOs and 5 utilities. (2) Duration is calculated as the number of months from the queue entry date to the in-service date.

## Broader network upgrades triggered by new interconnection requests mostly behind recent cost increases (not local interconnection costs)



### **Interconnection Cost Components**

Point of Interconnection (POI) or Interconnection / Attachment Facilities Costs:

- Interconnection station and transmission line extensions
- Often excludes other infrastructure (step-up transformer, spur lines...)

#### **Network Costs:**

•

- Broader transmission network upgrades triggered by reliability or stability violations caused by a new generator.
- May require modest upgrades (breakers) or reconstruction of several high-voltage transmission lines.
  - Costs may be shared by multiple generators that contribute to the upgrade and are usually paid for by project developers in the ISOs that we studied.

Region	"Earlier" period	"Recent" period		
MISO	2018	2019-2021		
SPP	2010-2019	2020-2022		
РЈМ	2017-2019	2020-2022		
NYISO	2006-2016	2017-2021		



ISO/RTOs	Other (non-ISO) Transmission Operators						
PJM	Southern Company	Associated Electric Coop.	LG&E & KU Energy	Portland General Electric	Public Service Co. of NM		
MISO	Tennessee Valley Authority	PSCO	Salt River Projects	Idaho Power	Avista		
ERCOT	Duke/Progress	Santee Cooper	NV Energy	Florida Municipal Power Pool	El Paso Electric		
SPP	WAPA	Georgia Transmission Corp.	Navajo-Crystal	Tri-State G&T	Imperial Irrigation District		
NYISO	Florida Power & Light	Arizona Public Service	Dominion	Jacksonville Electric Authority	Platte River Power Authority		
CAISO	Bonneville Power Admin.	LADWP	Puget Sound Energy	Tucson Electric Power	Black Hills Colorado		
ISO-NE	PacifiCorp	Seminole Electric Coop.	Tampa Electric Co.	NorthWestern	Cheyenne Light Fuel & Power		

