

VOLUME 30
TANSAO 30 1-814 (1978)
ISSN: 0003-018X

1978 WINTER MEETING


WASHINGTON D.C.

NOVEMBER 12-16, 1978

RECEIVED
NOV 16 1978

AMERICAN NUCLEAR SOCIETY

ETEC LIBRARY



TRANSACTIONS

14-08576-8613

TRANSACTIONS

OF THE
AMERICAN NUCLEAR SOCIETY

1978 WINTER MEETING

November 12-16, 1978
Sheraton Park Hotel
Washington, DC

Volume 30
TANSAO 30 1-814 (1978)
ISSN: 0003-018X

Technical Program Chairman
Clyde Jupiter (U.S. NRC)

Assistant Technical Program Chairman
Gail H. Marcus (Analytic Serv)

National Program Committee Chairman
James L. Scott (ORNL)

Editor
Ruth Farmakes (ANS)

Assistant to the Editor
Mary Jane Keenan (ANS)

DIVISION REPRESENTATIVES

C. K. Anderson (C-E) - *Nuclear Fuel Cycle*
S. R. Bierman (BNWL) - *Nuclear Criticality Safety*
G. Coulbourn (BOECON) - *Power*
Richard K. Disney (Westinghouse) - *Radiation Protection & Shielding*
Donald R. Ferguson (ANL) - *Mathematics & Computation*
Charles A. Flanagan (Westinghouse) - *Controlled Nuclear Fusion*
Brian K. Grimes (NRC) - *Power*
Robert D. Leggett (Westinghouse Hanford) - *Materials Science & Technology*
W. S. Lyon (ORNL) - *Isotopes & Radiation*
Denis E. O'Brien (Comm Ed) - *Reactor Operations*
Helen Pfuderer (ORNL) - *Environmental Sciences*
Roy G. Post (U of Ariz) - *Education*
Robert R. Stiger (EG&G Idaho) - *Nuclear Reactor Safety*
John Toman (LLL) - *Alternative Energy Technologies & Systems*
Walter D. Tucker (BNL) - *Remote Systems Technology*
Charles R. Weisbin (ORNL) - *Reactor Physics*

TECHNICAL SESSIONS

MONDAY, 9:00 AM, NOVEMBER 13, 1978

- *Nuclear Energy: The Washington Viewpoint. 1
(Plenary Session)

MONDAY, 2:00 PM, NOVEMBER 13, 1978

- *INFCE - A Status Report from the U.S. Viewpoint 269
POSTER SESSION: Fundamental Materials Studies,
Component Performance, and Fusion Reactor
Materials† 149
*Global CO₂, Climate, and Nuclear Power 84
Methods in Heat Transfer and Fluid Flow 204
*Twenty-Five Years of Remote Technology - The
Beginnings 749
*Inservice Inspection Programs 626
Plant Economics and Public Acceptance 485
*Qualification and Proof Testing of Nuclear Com-
ponents 491
*Risk Tree Analysis in Criticality Control 255
Advances in Radiation Transport Methods and Data
for Shielding. 582
TRS-1: Reliability and Probabilistic Risk Assess-
ment 354
Physics of Thermal Reactors 687
Inertial Confinement Fusion 20
FRS-1: Design and Accident Initiators 412
TRS-2: Vapor Explosions. 364
TRS-3: Containment Analysis and Experiments† 369
*Transuramics in the Environment 125
Safeguards and Accountability 270

†Starts 2:30 PM.

‡Starts 3:30 PM.

TUESDAY, 9:00 AM, NOVEMBER 14, 1978

- *Optimization of Fuel Design and Management for
the Once-Through Fuel Cycle 274
POSTER SESSION: Instrumentation and Control† 497
*Monitoring Nuclear Power Plants. 86
*Determination of Mechanical Properties Using Re-
mote Handling Techniques. 752
*Remote Handling in Large Hostile Environments. 758
Plasma Engineering and Magnetic Confinement
Concepts 30
Research Test and Training Reactor Experience. 634
*Impact of Fuel Damage Limits on Reactor Opera-
tion. 516
Waste Management - I. 282
Shielding, Radiation Transport, and Dosimetry
Applications. 594
*Qualification of Computer Codes for Nuclear Re-
actor Analysis - I. 217
Fast Reactor Integral Experiment and Analysis 698
*In-Situ Recovery - Oil Shale and Coal - I. 2
FRS-2: Safety-Related Mechanical Analysis 422
TRS-4: ECCS Analysis 375
*Chemical Behavior of Radioisotopes 132

†Starts 10:00 AM.

*Special Session

FRS = Fast Reactor Safety

TRS = Thermal Reactor Safety

TUESDAY, 2:00 PM, NOVEMBER 14, 1978

- *Technical Approaches to Diversion Resistance 295
POSTER SESSION: Heat Transfer and Fluid Flow†. 524
Environmental Impacts of Low-Level Waste. 90
*Decommissioning 551
*Hot Cell Examination and Maintenance Equip-
ment - I. 766
Power Reactor Startup Experience - I 640
*Technology for Advanced Systems 39
*Nuclear Plant Backfits and Modifications. 655
*Performance of Materials for LWR Steam Gen-
erators 166
*Radiation Protection Problems in Decommissioning
Nuclear Installations 605
*Qualification of Computer Codes for Nuclear Re-
actor Analysis - II 225
*Reactivity Coefficients: Measurement, Evaluation
and Application in Light-Water Reactors. 710
*In-Situ Recovery: Oil Shale and Coal - II. 6
FRS-3: Safety Experiments - I. 436
TRS-5: ECCS Analysis and Experiments. 387
*Nuclear Materials Safeguards and Management
Technology. 136
Plutonium Recycle. 300

†Starts 3:00 PM.

WEDNESDAY, 9:00 AM, NOVEMBER 15, 1978

- *Remote Fabrication of Nuclear Fuels 309
POSTER SESSION: Fuels and Materials Perfor-
mance† 170
*The Impact of the Regulatory Process on Safety-
Related Design of Nuclear Power Plants 479
*Radiation Streaming in Power Reactors - I. 233
*Hot Cell Examination and Maintenance Equip-
ment - II. 775
Training and Qualifications of Nonlicensed Nuclear
Plant Personnel 661
*Fusion Hybrid Concepts 49
*Solid Radioactive Wastes from Reactors 557
Waste Management - II 289
*The Impact of Fire on Nuclear Power Plant Safety 668
*Soluble Neutron Absorbers and Experimental Data
for Criticality Control 256
Physics of Thorium Reactor Systems 716
*Environmental Aspects of In Situ Solution Mining of
Uranium Ore 98
FRS-4: Material Behavior in Disrupted Cores. 448
*Utilization of Low-Enriched Uranium Fuel in Re-
search Reactors 725
Isotope and Radiation Applications 140

†Starts 10:00 AM.

WEDNESDAY, 2:00 PM, NOVEMBER 15, 1978

- Analyses of Fuel Cycle Processes 318
POSTER SESSION: Reactor Physics Methods†. 240

†Starts 2:30 PM.

Technical Sessions

vii

Reprocessing and Spent-Fuel Storage	326
*Radiation Streaming in Power Reactors - II	610
*Remote Maintenance at the New Waste Calcining Facility	784
Power Reactor Startup Experience - II	646
Blanket Engineering and Fusion Technology	64
*Nuclear Power Plant Remote Handling and Viewing Equipment	793
*Impingement and Entrainment Reduction Devices - Alternative Intake Structure Design	103
Power Plant Radioactive Waste Management	675
*Use of Soluble Neutron Absorbers for Criticality Safety	263
*Nuclear Data	732
Alternative Energy Technologies and Systems - General	9
FRS-5: Safety Experiments - II	460
TRS-6: Safety-Related Phenomenology	397
*The NRC, The Universities, and Nuclear Safety Research	75
Environmental Sciences - General	111

THURSDAY, 9:00 AM, NOVEMBER 16, 1978

Improvement of Reactor Core Design and Fuel Cycles	336
*Technical Support to IAEA Safeguards	347
*Remote Maintenance in Fusion Programs	799
*Remote Handling Operations, Maintenance and Equipment in Reprocessing, Refabrication, and Waste Handling	806
*Operating Quality Assurance	680
Plant Engineering	564
Siting Methodology Criteria and Regulation	119
Core Design	571
*Mechanical Properties of Irradiated Cladding Material	194
Parameter Identification in Power Reactors	743
Fusion Reactor Neutronics and Shielding	618
FRS-6: Post-HCDA Phenomenology	470
TRS-7: Fuel Analysis and Experiments	403
*Nuclear Engineering Education in Waste Management	76

TABLE II
Source of Decommissioning Funds

Cash and Commitments as of December 1, 1972 (Decommissioning Reserve Fund)	\$ 4,113,826
Member Company Contributions - 1974 and 1975	2,809,402
Contribution from APDA	42,270
Revenue from Salvage Sales	564,580
Anticipated NELIA Refunds	350,000
	<u>\$ 7,880,078</u>
Use charges, and other operating costs paid after December 1, 1972, from the above funds.	<u>\$ -365,090</u>
Funds Available and Used for Decommissioning	<u>\$ 7,514,988</u>

equipment so it can be sent to burial, how certain areas can be entombed, and many other aspects of how the plant is built could be of significant help in final decommissioning. How to dispose of contaminated and activated sodium coolant from a breeder reactor should be studied as part of building the plant. Engineers should anticipate that decommissioning will be an eventuality and should design to some extent to accommodate performing that task.

1. *Fermi I: New Age for Nuclear Power—A History of the First Large Breeder Reactor Electric Power Plant and Its Contributions to the Development of a Long-Range Source of Energy*, to be published by ANS in late 1978.
2. "Retirement of the Enrico Fermi Atomic Power Plant," NP-20047 and NP-20047 (Suppl. 1) by Power Reactor Development Company (Mar. 1974 and Oct. 1975).

LR-08603

4. Progress Report on Decommissioning of the Sodium Reactor Experiment, G. W. Meyers, W. D. Kittinger (AI)

The disposition mode selected for the last stage of the decommissioning of the sodium reactor experiment (SRE) at the Energy Systems Group's Engineering Field Laboratory near Los Angeles, California, was complete dismantlement. The primary objective is to remove all significant reactor-originated radioactive materials from the site. This final phase of the project began in 1975 with development work for accomplishing remote, underwater cutting of reactor vessels and components.¹ The project will be concluded in GFY 1979. This project is the major effort in a DOE-funded program of decommissioning eight nuclear facilities at the Field Laboratory.

Further objectives in the decommissioning of the SRE were to enable release of facility and site to unrestricted further use without surveillance requirements, to preserve the building structure to the extent of economic justification, and to perform the work within acceptable radiation exposure and safety guidelines for the workers, the public, and the environment. These objectives have all been met to date. The activities were designed and

accomplished to meet radiation levels as low as practicable as well as to meet radioactivity concentration guidelines that were derived by AI and given concurrence by the DOE, NRC, and the State of California Health Department.

The SRE was a 20 MW(th), sodium-cooled, graphite-moderated thermal reactor which used enriched uranium fuel. Initial operation began in 1957. The last nuclear operation was in 1964 although the sodium systems were operated until 1967. The fuel elements and control rods were removed; the primary sodium was drained into the fill tank, and secondary system sodium was drained into drums. The reactor and support systems were placed in protective storage status, using nitrogen as a cover gas. A surveillance and maintenance program was initiated. The reactor operated for about 27,000 h and generated over 37 million kWh(e).

The planning, engineering, and development activities for the dismantling were initiated in 1974. Peripheral system removal began shortly thereafter. Interior system dismantling efforts began in 1976. The major tasks that have been accomplished are:

1. Safe removal of radioactively contaminated sodium; cleaning of sodium residues from the reactor vessel, piping, and components; and the reaction of bulk sodium and residues to status permissible for disposal. Techniques employed for melting and alcohol flushing or spraying were effective as removal schemes. Reaction with alcohol produced a product for safe disposal. Approximately 2500 lb of sodium were removed from components and treated.

2. Safe and controlled removal of very large and heavy, activated or interior contaminated equipment. The reactor loading face shield plug, reactor ring shield, fuel and moderator handling machines, and liquid and gas holding tanks were removed intact and shipped to a licensed commercial nuclear waste burial site. This disposal approach minimized radiation exposures and release risks, minimized costs, and yet did not add significantly to the waste volume commitment.

3. Removal of reactor vessel internals such as cooling piping, clamps, bellows, and grid plate in a radiologically safe manner. The complex configurations of piping were cut away remotely and underwater by shaped-charge

explosives and a plasma torch. Plasma torch techniques were adapted to cut other reactor components.

4. Removal of the five concentric activated and contaminated structures of the reactor vessel. Radiation levels required water shielding and remote operation. A rotating mast manipulator equipped with plasma torch and video system was utilized to dissect the $\frac{1}{4}$ -in. stainless-steel thermal liner, $1\frac{1}{2}$ -in. stainless-steel core tank, and the $\frac{1}{4}$ -in. outer tank. The concrete-embedded $\frac{1}{4}$ -in. steel cavity liner was removed along with the concrete. Plasma torch cutting also sectioned the grid plate and tank bottoms by use of a specially designed manipulator arm. The $5\frac{1}{2}$ -in.-thick steel thermal rings were removed from the vessel for remote-controlled and -contained oxy-acetylene torch cutting.

5. Removal of the 4-ft-thick biological shielding, storage, and wash cells, hot fuel examination cell, other ground vaults. Removal required excavations to 40 ft below grade, selective separation of contaminated and activated surfaces or volumes, and special care for personnel safety and avoidance of contamination spread. It was found most cost and radiation control effective to preserve the building structure during the entire dismantling phase.

Activities that remain are those to accomplish final structure decontamination, removal of air cleaning and other support facilities, site repairs, final radiation surveys, and completion of the final report. The total project is estimated to cost about \$10 million. A portion of the total cost funded the necessary tooling, technique, and operating parameter development work.

1. A. W. GRAVES, G. P. STREECHON, and D. A. PHILLIPS, *Trans. Am. Nucl. Soc.*, 27, 760 (1978).

5. Financial Evaluation of Nuclear Plant Decommissioning Costs, B. J. Ewers, Jr. (NSP)

The financial evaluation of decommissioning a nuclear generating plant has four considerations. These include the method and associated cost of decommissioning, the economic methodology to evaluate these costs, selection and evaluation of methods to recover these costs, and subjective nonfinancial considerations. A structure which quantifies all but the latter is presented leaving the nonfinancial considerations such as political and regulatory feasibility for subjective evaluation.

Method and Cost of Decommissioning

The study prepared for the Atomic Industrial Forum Inc. serves as a base to evaluate the method and associated cost of decommissioning.¹ Three basic methods and associated costs extrapolated to 1978 dollars were Mothballing (\$5 to 7 million), Entombment (\$16 to 27 million) and Complete Removal (\$53 to 63 million). These costs compare to an estimated 1978 inservice date construction costs for an 1100-MW nuclear plant of \$500 million.

A negative net salvage cost equal to 10% of plant cost and an average service life of 30 years is typically used by utilities for plant depreciation purposes. This negative 10% net salvage would recover the estimated cost of decommissioning for most methods disregarding inflation. Figure 1 illustrates the inadequacy of the negative 10% net salvage for many combinations of inflation and decommissioning method.

Methodology to Evaluate Costs

To evaluate the financial impact on a utility, accounting and rate-making principles were considered. One




Fig. 1. Effect of inflation on decommissioning costs.

basic goal, to match the timing of revenues and expenses, is accomplished for capital expenditures when the noncash expense called depreciation when generated from the capital asset will be received over the assets life. When this goal is considered for an asset of net negative salvage where capital is invested at the end of the period, negative net salvage should like be expensed through depreciation over the earning life of the asset.

Maintenance costs incurred after the facility has been decommissioned were considered a net cost at decommissioning equal to the capitalized cost of the annual expense. Since one cannot charge as a depreciation expense items for which capital outlay has not been made, the tax deductible expense in the decommissioning was normalized or matched with the value of the asset.

Economic tools that evaluate the effective cost associated with capital budget decisions require application of the time value of money methodology. Utility companies traditionally used some variation of a method called the present value of future revenue requirements. The comparative costs presented in Fig. 2 represent the present value of revenue requirements considering: (a) utility capital structure which results in a discount rate of 10%; (b) an initial plant cost of \$500 million (in 1978 dollars); and (c) an estimated 1978 decommissioning cost of \$50 million. These assumptions are used for demonstration purposes only.




Fig. 2. Cost of decommissioning for various accounting methods and inflation rates.