

# 2024 PROJECT PEER REVIEW


U.S. DEPARTMENT OF ENERGY  
BUILDING TECHNOLOGIES OFFICE

## BTO Peer Review: OCCTOPI

Optimized Commercial Control  
Technology Of Plug-loads &  
Lighting



# Optimized Commercial Control Technology Of Plug-loads & Lighting (OCCTOPI)



University of California, San Diego (UCSD)

National Renewable Energy Laboratory (NREL)

PI Jan Kleissl, Professor, Department of Mechanical & Aerospace Engineering

[jkleissl@ucsd.edu](mailto:jkleissl@ucsd.edu)

Keaton Chia, R&D Engineer and Project Manager

[kwchia@ucsd.edu](mailto:kwchia@ucsd.edu)

DE-EE0010921

# Project Summary

## OBJECTIVE, OUTCOME, & IMPACT

The project will reduce the electrical base load of commercial buildings using flexible lighting and plug loads. Open-source software will be produced to facilitate system integration and intelligent controls. With more than 80% of small to medium U.S. commercial buildings lacking building automation, OCCTOPI provides an affordable solution to implement energy management strategies.

## TEAM & PARTNERS

- University of California, San Diego (UCSD)
- National Renewable Energy Laboratory (NREL)
- Nabu Casa
- Best Energy Reduction Technologies (BERT)
- Acuity Brands



## STATS

Performance Period: 04/01/2024 to 9/30/2024

DOE Budget: \$600k, Cost Share: \$150k

Completed Milestones:

Milestone 1: Baseline Studies

Milestone 2: Start Prototyping Activities

Milestone 3: Baseline Model



# Problem

**Plug loads are increasing in buildings and are very difficult to control. Existing solutions are expensive and siloed. There is a need for an affordable solution for small to medium commercial buildings so that the U.S. can achieve energy efficiency, demand reduction, and decarbonization goals.**

- Plug loads are plug-in electric loads in a building and account for over 50% of whole-building energy consumption in high-efficiency buildings (*Lobato et al. 2011*).
- More than 80% of small to medium U.S. commercial buildings lack a building automation system (*Trenbath et al. 2022*).
- Lack of system interoperability, such as with lighting occupancy data, limits the effectiveness of plug load control (PLC).
- Building electrification measures are constrained by a site's electrical capacity and may require costly infrastructure upgrades.

C. Lobato, S. Pless, M. Sheppy, and P. Torcellini. 2011. "Reducing plug and process loads for a large scale, low energy office building: NREL's research support facility." Nevada: ASHRAE.

K. Trenbath, R. Meyer, K. Woldekidan, K. Maisha, and M. Harris. 2022. Commercial Building Sensors and Controls Systems - Barriers, Drivers, and Costs. <https://doi.org/10.2172/1880546>



# Alignment and Impact

**OCCTOPI provides a low-cost solution for small to medium commercial building operators to effectively manage their plug-load energy consumption by leveraging:**

- (1) An open-source automation platform
  - (2) Integrations with off-the-shelf consumer products
  - (3) System interoperability for intelligent energy management, specifically lighting and plug-load control.
- Empowers underserved communities with an affordable option to manage their energy consumption and realize cost savings.
  - Improve building efficiency by eliminating wasted plug-load electricity consumption.
  - Pathway to grid-interactive efficient buildings



# Alignment and Impact

## Current State-of-the-Art

- Commercial systems are expensive, closed ecosystems, and face interoperability challenges.
- Commercial building systems lack support for modern IoT communication standards which limits accessibility to affordable consumer hardware.
- Most plug load control (PLC) systems are stand alone. Typical Building Automation System do not have adequate PLC features.
- Automatic receptacles have been integrated with lighting, but are often limited to scheduling and occupancy driven controls which may not be the appropriate strategy for certain plug loads.

## OCCTOPI

- Built on top of Home Assistant (HA), an **open-source automation platform** used by over 300,000 users world-wide.
- Large user community for support.
- Founding company continues to develop the open-source software in addition to providing cloud services.
- Robust system in place for the deployment of official and community software Add-Ons.
- BACnet and OPC connectors will be added to compliment **HA's existing 1,000+ consumer product integrations** including the Matter standard.
- Implement **advanced PLC by leveraging device interoperability.**




# Approach

## OCCTOPI Deliverables

- BACnet connector
- Software for energy & system management
- Advanced PLC control strategies using PLC + lighting integration
- Target of 25% reduction in lighting and PL energy consumption w/ a payback period of less than 3 years.

## System Architecture



New Features to Home Assistant



# Approach

1. UCSD lab prototype
2. Lab evaluation at NREL's Energy Systems Integration Facility
3. Two field demonstrations:
  1. Large UCSD Campus building
  2. Small site in Alaska




Diagram of OCCTOPI applications and field validation details.



# Approach



RISK MANAGEMENT LOG				
ID	Risk	Likelihood Impact	Potential Impact	Mitigation Strategy
R1	Unforeseen technical challenges with BACnet connector development can delay the project.	Likelihood: High Impact: High	Demonstration of a working lab prototype may be delayed which impacts Budget Period 1 Go/No-Go Decision Point	The project team has three current BACnet connectors that can be used as references for the Home Assistant version.
R2	Changes to the Matter standard may require updates to Matter software connectors developed by Nabu Casa.	Likelihood: Medium Impact: Medium	Task 4 integrations may have to be updated which would impact the project schedule.	Devices selected will have both Matter integration as well as an OEM integration to provide an alternative. Nabu Casa actively updates their Matter connector and is an active member of the Connective Standards Alliance that oversees the Matter Standard.
R3	Project may run into unexpected networking issues and cybersecurity constraints.	Likelihood: Medium Impact: Medium	Task 7 may face schedule delays if these issues are encountered during field deployment.	Project team will engage early on with IT departments at both field validation sites to capture requirements.



# Approach

## Commercialization Path

- All software features (“Add-Ons”) will be published onto the Home Assistant Add-Ons page for free use
- Source code available on GitHub
- Affordable hardware already available from Nabu Casa for ease of setup (HA Yellow & Green)
- Adoption through UC Sustainability Programs such as the Green Office Certification. UC market consists of 5,847 buildings (142M SF).





# Progress and Future Work

*\*New Project: Progress since project start (April 1, 2024)*


## Task 2 – Energy Monitoring and Control

- Metering data processed & Submeters installed (M1 & M3 complete)
- Plug loads and lighting audit complete
- V1 Load profiler algorithm done
- Load disaggregation estimate done
- Energy efficiency proof of concept done


## Future Work:

- Compare load disaggregation to submeter data
- Version 2 load profiler and efficiency


## Center Hall Stats



Base Load Distribution



Active Load Distribution



Avg. Baseload Energy (unoccupied)	Avg. Baseload Power (unoccupied)	Avg. Working Day Energy Load (active + baseload)	Avg. Non-working Day Energy Load (active + baseload)	Avg. Active Load Duration (working days)
329 kWh	36 kW	1,203 kWh	611 kWh	14.7 hours




# Progress and Future Work

## Identify Savings Opportunities

- Load profiler identifies time periods for building activity
- Efficiency = 'useful consumption'/total electricity consumption
- Occupancy used as a proxy for useful consumption

```
Entity: sensor.p11_edge_1181920_electric_consumption_w_2
Total Power Consumed: 131040.20000000027
Power Consumed During State Change = 1: 4312.999999999999
Efficiency: 3.2913563929236904 %
```





# Progress and Future Work


## Task 3 – Prototyping Testbed Setup

- Home Assistant (HA) and Z-wave devices setup in lab (M2 complete)
- Dashboard iterations in progress
- New graphs created for energy monitoring
- Completed initial range tests for long-range Z-wave


## Future Work:

- Add BACnet devices for lab offices
- Integrate load profiler and efficiency score algorithms to HA

Total Energy Consumption



Individual Device Energy Consumption





# Progress and Future Work

## Task 4 – Systems Integration

- BACnet connector discovers devices and points; converts to MQTT; displays devices in HA
- Functional for both BERT plug load controllers & Acuity connected LED lighting system
- Testing a variety of IoT brands

## Future Work:

- Assign BACnet devices to spaces.
- Development control via BACnet
- Use Modbus for metering data

HOME BERT ACUITY

LED Device at

	0966_RELAY_DimInLevel_00000879	0.0 percent
	0966_RELAY_DimLevelP1_00000879	0.0 percent
	0966_RELAY_LightLevel_00000879	0.0 footCandles
	0966_RELAY_OccupiedP1_00000879	Unknown
	0966_RELAY_Online_00000879	Unknown
	0966_RELAY_PCellInhibitP1_00000879	Unknown
	097F_RELAY_DimInLevel_0000087E	0.0 percent
	097F_RELAY_DimLevelP1_0000087E	0.0 percent
	097F_RELAY_LightLevel_0000087E	0.0 footCandles
	097F_RELAY_OccupiedP1_0000087E	Unknown
	097F_RELAY_Online_0000087E	Unknown
	097F_RELAY_PCellInhibitP1_0000087E	Unknown
	0D6B_RELAY_DimInLevel_00000892	0.0 percent
	0D6B_RELAY_DimLevelP1_00000892	0.0 percent

HOME BERT ACUITY

BERT Device at

	AI1 BERT Temperature	0.0 degreesFahrenheit
	AI3 BERT Power Measurement	35,400.0 milliwatts
	AI4 BERT Voltage Measurement	118.0 volts
	AI5 BERT Current Measurement	300.0 milliamperes
	AI7 BERT Average Power Last Ho...	34,937.0 milliwatts
	AV1 BERT Calibration Temper...	0.0 degreesFahrenheit
	AV2 BERT Power Threshold	0.0 watts
	AV3 BERT High Temperature...	90.0 degreesFahrenheit
	AV4 BERT Low Temperature T...	0.0 degreesFahrenheit
	AV5 BERT Customer ID	11,222.0 noUnits
	BI1 BERT Temperature Measurement Enab...	Unknown




# Progress and Future Work

## Task 5 – Systems Management

- Example dashboards created for operators
- Proof of concept for change of plug load appliance alert

## Future Work:

- User engagement for UI/UX design
- Device and zone management
- Task 6: Lab evaluation at NREL's Energy Systems Integration Facility
- Task 7: Two field validations



# Thank you

University of California, San Diego  
(UCSD)

National Renewable Energy Laboratory  
(NREL)

Keaton Chia, R&D Engineer, PM

[kwchia@ucsd.edu](mailto:kwchia@ucsd.edu)

DE-EE0010921



**2024 PROJECT  
PEER REVIEW**

U.S. DEPARTMENT OF ENERGY  
BUILDING TECHNOLOGIES OFFICE



# Reference Slides





# Project Execution

## Budget Period 1 Milestones

- M1 Baseline Studies – complete
- M2 Prototyping – complete
- M3 Baseline Model – complete
- M4 BACnet Connector – in progress
- M5 Energy & Control – in progress
- M6 User Design – in progress
- M7 Management Features – in progress
- M8 ESIF Evaluation – not started

## PROJECT SCHEDULE

**WBS 1\_ Administration:** spans entire project (4/1/2024-3/31/2026)  
•Q8 Milestone\_Project Completion

### **Budget Period 1**

- WBS 2\_ Baseline & Energy Control Features** (4/10/2024 - 2/13/2025)
  - Q2 Milestone\_Baseline Model. NREL responsible for FNHS activities.
  - Q4 Milestone\_Energy Monitoring & Control v1 Features
- WBS 3\_ Prototype Setup** (4/10/2024 - 7/11/2024)
  - Go/No Go\_Prototyping Activities can Begin
- WBS 4\_ System Integration** (7/1/2024 - 5/30/2025)
  - Q3 Milestone\_BACnet connector operational
- WBS 5\_ System Management Features** (6/18/2024 - 2/12/2025)
  - Q4 Milestone\_Management Features v1 Complete
  - DEIP Milestone\_User-informed Design

### **Budget Period 2**

- WBS 6\_ Deployment Preparation** (12/30/2024 - 6/10/2025)
  - Go/No Go\_V1 System Ready for Evaluation
  - Go/No Go\_System ready for Field Deployment
  - Q6 Milestone\_System Ready to Ship to Field Sites
- WBS 7\_ Field Validations** (5/7/2025 - 1/16/2026)
  - Go/NoGo for FNHS Deployment
  - Q7 Milestone\_All Occupants Trained
  - Q7 Milestone\_Field Tests Complete



# Team

## Project Team

UC San Diego

PI Jan Kleissl, PhD

Adil Khurram, PhD

Keaton Chia, PM

Jesse Wolf



Kim Trenbath, PhD

Amy LeBar

Omkar Ghatpande

Vanessa Stevens

## Project Partners



N A B U  
C A S A



**AcuityBrands**