



The New

Affordable
Zero

Homes

PhilaU Powered to Zero



OUR TEAM:



Jessica Livezey



Tyler Scire



Megan Ullery

CERTIFICATIONS:



INDUSTRY PARTNERS:



Celentano
Energy
Services



PROJECT SUMMARY

OVERVIEW:



- Attached Duplex Housing
- Alternate option to non-profit home building organizations

KEY FACTS:

| | Unit 1 | Unit 2 |
|--|--------|--------|
| Square Footage: | 1,414 | 1,060 |
| Bedrooms: | 3 | 3 |
| Bathrooms: | 2.5 | 2 |
| HERS w/o PV: | 36 | 39 |
| HERS with PV: | -2 | -2 |
| Monthly Net Zero Ready Utility Costs: | \$56 | \$46 |
| Monthly Utility Costs with Renewables: | \$5 | \$5 |


SITE LOCATION:

- Brewerytown, Philadelphia, Pennsylvania
- Climate Zone: 4a, mixed-humid







DESIGN GOALS:

- Exceed Baseline Standards
- High Performance
- Natural Daylight Analysis




Illuminance values of Lighting Analysis


| | Brewerytown Rowhouse | Habitat for Humanity | New Affordable Zero Homes |
|----------------------------------|----------------------|---|--|
| Dwelling | | | Unit 1: 1,414 Unit 2: 1,060 |
| Sq. Ft.: | 1,252 | 1,070 | |
| # Bed/Bath: | 2/1.5 | 3/1.5 | Unit 1: 3/2.5 Unit 2: 3/2 |
| Cost: | \$252,750 | \$160,000 | Unit 1: \$168,763 Unit 2: \$175,321 |
| Monthly Utilities: | \$150-\$200 | | Unit 1: \$56 Unit 2: \$46 |
| R-Roof: | 38 | 38 | 40 |
| R-Wall: | 13 | 30 | 30 |
| Standards & Programs: | None | Minimum LEED Silver, Energy Star, Advanced Framing, IAQ | Energy Ready, LEED Platinum, Energy Star, EPA, Water Sense |




COMPARISON TO PHILADELPHIA HOMES:



Typical Philadelphia Rowhome



Typical Philadelphia Duplex





Typical Habitat Duplex



New Affordable Zero Duplex

FIRE WALL / ROOF CONDITIONS:




WEST ELEVATION:



Rear Yard

TRANSFORMATION FROM TYPICAL DUPLEX TO NEW AFFORDABLE ZERO HOMES:



Typical Duplex Form

New Affordable Zero Duplex Form

SOUTH ELEVATION:



View Towards W. Girard Avenue




PROGRAM KEY:


- 1. Living Room
- 2. Dining Room
- 3. Kitchen
- 4. Bedroom
- 5. Bathroom
- 6. Walk-in Closet
- 7. Roof Deck




Unit 1 Dining Room



NATURAL VENTILATION:




CIRCULATION:



L1


- Aging in place
- ADA accessibility




L2



Unit 2 Living Room




Unit 2 Kitchen



L3


| | IECC 2009 | DOE NZRH R.5 | New Affordable Zero Homes |
|--------------------------------|-----------|-----------------------------|---------------------------|
| Ceiling R-Value | 38 | 49 | 50 |
| Wall R-Value | 13 | 20 | 35.7 |
| Floor R-Value | 19 | 19 | 21 |
| Basement Wall R-Value | | | |
| | 10 / 13 | 10 / 13 | 23.6 |
| Window SHGC | NR | 0.25 | 0.25 |
| Window U-Value | 0.35 | 0.3 | 0.2 |
| AFUE | | 90% | 90% |
| SEER | | 15 | 17 |
| HSPF | | 9 | 9.8 |
| ASHRAE 62.2 Ventilation System | | 1.4 cfm/W; no heat exchange | 1.4 cfm/W |
| Infiltration (ACH50) | | 2.5 | 1 |
| Water Heater Energy Factor | | Electric: EF = 2.0 | EF = 2.75 |



ENERGY ANALYSIS STRATEGIES:

SEFAIRA UNIT 1:


Unit 1 Annual Energy Use (kBTU)



| | |
|------------|--------|
| Appliances | 19118 |
| Heating | 149189 |
| Cooling | 14821 |

SEFAIRA UNIT 2:

Unit 2 Annual Energy Use (kBTU)




| | |
|------------|--------|
| Appliances | 19118 |
| Heating | 139494 |
| Cooling | 14185 |

ENERGY ANALYSIS STRATEGIES:


REM/RATE UNIT 1 w/o PV: 36

REM/RATE UNIT 2 w/o PV: 39

Annual Consumption




Annual Consumption




PV SYSTEM:

| | Unit 1 | Unit 2 |
|-----------------------|--------------|--------------|
| Roof Area | 530 SF | 1022 SF |
| Roof Slope | 37.5 degrees | 37.5 degrees |
| Annual Electrical Use | 8662 kWh | 7087 kWh |
| DC System Size | 6.93 kW | 5.67 kW |
| # 315W Panels | 22 | 18 |
| Panel Coverage Area | 388.3 SF | 317.7 SF |
| HERS Score with PV | -2 | -2 |


REM/RATE UNIT 1 WITH PV:



REM/RATE UNIT 2 WITH PV:




PV DOUBLE SIDED CELL:



LG NeON™ 2


Double Sided Cell. Digital image. LG NeON 2 Module. LG, 2015. Web. <<http://www.lg.com/us/commercial/solar-panels/lg-LG315N1C-G4>>.

PV LIGHT ABSORPTION:



LG NeON™ 2

Light Absorption Cell. Digital image. LG NeON 2 Module. LG, 2015. Web. <<http://www.lg.com/us/commercial/solar-panels/lg-LG315N1C-G4>>.




STRUCTURAL INSULATED PANEL SYSTEM:


- Self contained system
- Insulation and structure are pre-assembled
- Panels are stacked and joined to form a complete sealed envelope with minimal labor and can be assembled quickly

INSULATED CONCRETE FORMS SYSTEM:


- Pre-insulated formwork for foundations
- More efficient and quicker to assemble than traditional wood formwork.



Typical Stud Framing



Advanced Stud Framing




SIPs Construction

"Energy-Efficient Framing, A.k.a. Advanced Framing." Green Building Advisor. N.p., n.d. Web. 8 Apr. 2016; Gibson, Scott. "High-Performance Walls." Home Power. N.p., n.d. Web. 8 Apr. 2016.

“ITS LIKE BUILDING WITH LEGOS
AND ANY UNSKILLED
VOLUNTEER CAN PUT TOGETHER
THE FORMWORK”


~Habitat Philadelphia on
ICF construction



Concrete Forms. Digital image. Insulated Concrete Forms. Advanced NRG, 2012. Web. <<http://www.advanceng.com/concreteforms.html>>.


SEALING THE ENVELOPE:

THERMAL BARRIER:




The thermal barrier exists within both the SIP and ICF system due to the fact that insulation is within these pre assembled systems.

VAPOR BARRIER:



Sheeting is applied directly to the exterior face of these systems underneath the exterior finishes.


MOISTURE BARRIER:



The moisture barrier exists at the ground, roof and foundation while the exterior walls just repel the water to the ground.


UNIT 1:

Unit 1 Developer Rate




UNIT 2:


Unit 2 Developer Rate



Unit 1 Habitat for Humanity



Unit 2 Habitat for Humanity



Habitat for Humanity is able to reduce our costs due to the fact that they receive selection of building materials and appliances by donation as well as a portion of labor is done by volunteers.

HABITAT FOR HUMANITY VOLUNTEER WORK:

- Site Work Labor
- Framing Labor
- Envelope Sealant

HABITAT FOR HUMANITY REDUCTIONS:

- HVAC
- Plumbing
- Electrical

HABITAT FOR HUMANITY TYPICAL DONATIONS:

- Windows
- Doors
- Paint
- Washer
- Dryer
- Refrigerator
- Range/Oven
- Lighting
- Casework


| Financial Chart | Unit 1 |
|-------------------|------------------|
| Site Work | \$13,303 |
| Foundations | \$20,983 |
| Framing | \$40,596 |
| Exterior Finishes | \$21,499 |
| Major Systems | \$34,000 |
| Interior Finishes | \$59,755 |
| Final Steps | \$9,708 |
| Total | \$199,844 |

| Financial Chart | Unit 2 |
|-------------------|------------------|
| Site Work | \$11,876 |
| Foundations | \$22,612 |
| Framing | \$42,709 |
| Exterior Finishes | \$22,966 |
| Major Systems | \$30,358 |
| Interior Finishes | \$49,358 |
| Final Steps | \$9,104 |
| Total | \$188,983 |



| Financial Chart | Unit 1 HfH |
|----------------------|------------------|
| Site Work | \$13,303 |
| Foundations | \$20,983 |
| Framing | \$40,596 |
| Exterior Finishes | \$15,399 |
| Major Systems | \$9,500 |
| Interior Finishes | \$35,650 |
| Final Steps | \$5,460 |
| Volunteer / Donation | \$81,578 |
| Total | \$140,891 |



| Financial Chart | Unit 2 HfH |
|----------------------|------------------|
| Site Work | \$11,876 |
| Foundations | \$22,612 |
| Framing | \$42,709 |
| Exterior Finishes | \$13,043 |
| Major Systems | \$9,000 |
| Interior Finishes | \$36,822 |
| Final Steps | \$5,368 |
| Volunteer / Donation | \$71,013 |
| Total | \$141,430 |

PLUMBING SYSTEM:




RAINWATER HARVESTING + GREYWATER SYSTEM:






Flashing behind to add an additional layer of protection from water infiltration




Extend flashing 1 inch onto the course below

Installation of HardiPlank Siding.
HardiPlank, 2013. Print.

WALL / FLOOR DETAIL:




FOUNDATION WALL / FLOOR DETAIL:




PV RACKING ASSEMBLY:

1. EF-44R-SS-NDD
2. XHD: #15 Self Drilling Fastener
3. EFL-44RNDD-1214-BLK Flashing
4. EPDM Sealing Washer
5. L-102-3 Compression Bracket
6. 3/8" Bonded Washer
7. 3/8" Flange Nut




ECO-44R-NDD Product Guide.
EcoFasten Solar, 2014. Print.

DOOR DETAIL:






WINDOW DETAIL:




ROOF DETAILS:

- The party wall is an integral structural, thermal and fire resistant element
- The air gap within the party wall aids in the reduction of noise and the spread of fire between the units




SYSTEMS:

- ReCoupAerator 200DX ERV System
- Mitsubishi Ductless System



ERV. Digital image. Ultimate Air: Energy Efficient Ventilation. Web. <www.ultimateair.com>.



Second Floor Mechanical Plan

APPLIANCES:



- Frigidaire Top Mounted Refrigerator



- LG Studio Series Dishwasher




- Frigidaire Induction Electric Range with Self-Cleaning Convection Oven



- Glacier Bay 2-piece Single Flush Round Toilet

MATERIALS SOURCE MAPPING:



COMPARISON OF DESIGN PARAMETERS:

| | Brewerytown Rowhouse | Make it Right Foundation | Phila. Habitat for Humanity | Unit 1 Developer Rate | Unit 2 Developer Rate | Unit 1 Habitat Rate | Unit 2 Habitat Rate |
|---|----------------------|---|---|--|--|--|--|
| Dwelling Sq. Ft.: | 1252 | 1400 | 1070 | 1414 | 1060 | 1414 | 1060 |
| Bed/Bath: | 2 Bed/1.5 Bath | 3 Bed/2 Bath | 3 Bed/ 1.5 Bath | 3 Bed/2.5 Bath | 3 Bed/2 Bath | 3 Bed/2.5 Bath | 3 Bed/2 Bath |
| Construction Price: | \$209,055 | \$140,000 | \$112,000 | \$199,844 | \$189,039 | \$140,891 | \$141,430 |
| Sale Price: | \$298,650 | \$200,000 | \$160,000 | \$281,947 | \$277,251 | \$187,027 | \$195,617 |
| Price after Incentives: | \$298,650 | \$200,000 | \$160,000 | \$250,341 | \$246,334 | \$168,763 | \$175,321 |
| Monthly Mortgage Price w/ Utilities & PV: | \$1,154 | \$773 | \$618 | \$970 | \$952 | \$654 | \$678 |
| Standards + Programs: | None | LEED, Earthcraft, Energy Star, Advanced Framing | Minimum LEED Silver, Energy Star, Advanced Framing, IAQ | Energy Ready, LEED Platinum, Energy Star, EPA, Water Sense | Energy Ready, LEED Platinum, Energy Star, EPA, Water Sense | Energy Ready, LEED Platinum, Energy Star, EPA, Water Sense | Energy Ready, LEED Platinum, Energy Star, EPA, Water Sense |



- Meet or Exceed Baseline Standards of DOE NZRH, IECC 2009, and Philadelphia Habitat for Humanity Criteria
- High Performance Exterior Envelope
- Achieved Direct Natural Daylight Values of 70% at 9am and 60% at 3pm Versus a Typical Philadelphia Rowhome with an Average of 30%
- HERS Score w/o PV: Unit 1 = 36 and Unit 2 = 39, HERS Score w/ PV: Unit 1 = -2 and Unit 2 = -2
- Total Cost Built at a Habitat for Humanity Rate is 36% Less Than Our Home Built at a Developer Rate