


# Materials and Designs for High-Efficacy LED Light Engines

2017 Building Technologies Office Peer Review



*NBD: Narrow-Band Downconverter*

# Project Summary

## Timeline:

Start date: 7/1/15

Planned end date: 6/30/17

## Key Milestones:

1. Month 9: measure red-emitting narrow-band downconverter (NBD) thermal efficiency “droop” of < 10% from room temperature to 85°C.
2. Month 15: confirm <10% LED luminous flux degradation and <0.004 du’v’ color shift at >1,000 hrs. of accelerated testing (high-T, high current).

## Budget:

### **Total Project \$ to Date:**

- DOE: \$1.12M
- Cost Share: \$281K

### **Total Project \$:**

- DOE: \$1.5M
- Cost Share: \$375K (20% of total)

## Project Outcome:

New red emitting narrow-band down-converter (NBD) materials will enable white solid-state lighting with **10-20% or higher efficacy** compared to conventional phosphors.

Cree is overcoming challenges in NBD **efficiency** and **reliability** (robustness) in typical LED operating conditions to accelerate these materials toward real applications.

# Purpose and Objectives

**Problem Statement:** simultaneous achievement of red-emitting NBDs with high **down-conversion efficiency**, high **spectral efficiency**, and high **robustness** in application conditions

**Target Market and Audience:** LEDs integrated into nearly all solid-state lamps and luminaires, particularly warm white (2700-3500K CCT).

## Impact of Project:

- Output:* stable and efficient red-emitting NBD materials as drop-in replacements for conventional red phosphors in white LEDs.
- Primary contribution:* increase warm-white LED efficacy in a timeframe that meets or exceeds DOE SSL roadmap goals
  - Near term: >160 lm/W\* in low- to medium-power LED packages
  - Intermediate term: >170 lm/W\* in low- to medium power LED packages
  - Long term: proliferation into high-power LED packages


\*At DOE SSL baseline LED drive current of 35 A/cm<sup>2</sup> (~1 W/mm<sup>2</sup>). LED efficacy at lower currents will be significantly higher (>180 lm/W).





# Approach

**Approach:** Synergistically combine advances in materials synthesis, light engine configuration & processing, and reliability (robustness).

Factors contributing to **Efficacy**:



Factors contributing to **Reliability**:





**Key Issues:** primary challenge is achieving high red NBD **reliability** in accelerated testing conditions (high light flux, T, & RH) while maintaining high **down-conversion efficiency** (*i.e.* turning blue photons into red photons).

**Distinctive Characteristics:** a multi-thrust approach with continuous application-centric reliability testing is quickly transitioning NBDs toward commercialization.

# Progress and Accomplishments – NBD Synthesis

- NBD synthesis and post-synthesis treatment are being systematically varied and evaluated based on characterization and reliability testing





- Lessons learned: NBD composition, purity, morphology, and post-synthesis treatment are all factors in optimizing QY. Optimization of some of these parameters may not result in high NBD reliability!

# Progress and Accomplishments – Light Engine

- White NBD-containing LEDs fabricated and tested under steady-state conditions at various temperatures.


XHG2 - 3500K - 55°C - 65mA				
	LF	LF gain	CRI R <sub>a</sub>	CRI R <sub>9</sub>
All Phosphor	23.8	-	92.5	60
NBD	26.2	+10%	93.0	70



- Lessons learned: NBD thermal droop must be factored into “real world” white LED performance. Further white LED luminous flux (LF) gains expected as red NBD QY and thermal droop improve

# Progress and Accomplishments - Reliability

- LED accelerated testing in high-current, high-T, high-RH ambients acts as synthesis feedback and helps define the application space.
- Progressively higher stress currents (and therefore blue flux) are being applied.



- Lesson learned: NBD-containing LEDs often exhibit luminous flux **rise** early in testing; color point change (namely  $du'$ ) is a better indicator of NBD stability and lifetime prediction.

# Project Integration and Collaboration

**Project Integration:** project R&D staff continually communicate with **Cree LED product development groups** to ensure timeliness and relevance of project goals and achievements.

*Synthesis:* how reproducible is NBD synthesis? How scalable? \$/lumen?

*Light Engine:* are NBDs compatible with existing LED fabrication processes and package configurations?

*Reliability:* how does evolving NBD reliability map onto projected lifetime (>50,000 hrs.) in various luminaire application conditions?

**Partners, Subcontractors, and Collaborators:** no external partners.

**Communications:** project results presented at annual DOE SSL R&D Workshops.



# Next Steps and Future Plans

## Next Steps and Future Plans:

- *By end of project*: package-level evaluation and multiple-condition REL studies to help elucidate NBD failure mechanisms and ways to overcome them. Luminaire-level demonstration for comparison w/ all-phosphor.
- *After project*: continue intensive synthesis/package/REL cycle in the drive to create robust red-emitting NBDs
- *Future*: establish “technical” vs. “fundamental” NBD limitations, and compare to other nascent red down-converter materials systems. Apply “lessons learned” in synthesis and robustness improvements from current project to new materials systems, if applicable.

---

# REFERENCE SLIDES

# Project Budget

**Project Budget:** \$1.5M Federal Share / \$375K Cree Cost Share

**Variiances:** currently at +\$98K (6.7% of combined of Federal + Cost Share budget)  
No modifications to project plan.

**Cost to Date (as of 2/18/17):** \$1.25M Federal / \$251K Cost Share (83.6% of total)

**Additional Funding:** none.

## Budget History

7/1/15 – 9/30/16 (project start to end of FY16)		10/1/16 – 6/30/17 (FY17)		FY 2018 – N/A N/A	
DOE	Cost-share	DOE	Cost-share	DOE	Cost-share
\$929,459	\$185,892	\$323,748	\$64,750	N/A	N/A

# Project Plan and Schedule – Past Work

- All Milestones except 3.2 met early or on time.
- Milestone 3.2 deferred (with DOE PM approval) to later in program due to task re-prioritization.

Project Schedule												
Project Start: 7/1/15	Completed Work											
Projected End: 6/30/17	Active Task (in progress work)											
	◆ Milestone/Deliverable (Originally Planned)											
	◆ Milestone/Deliverable (Actual)											
	FY2015				FY2016				FY2017			
Task	Q1 (Oct-Dec)	Q2 (Jan-Mar)	Q3 (Apr-Jun)	Q4 (Jul-Sep)	Q1 (Oct-Dec)	Q2 (Jan-Mar)	Q3 (Apr-Jun)	Q4 (Jul-Sep)	Q1 (Oct-Dec)	Q2 (Jan-Mar)	Q3 (Apr-Jun)	Q4 (Jul-Sep)
<b>Past Work (Year 1)</b>												
1.1 RT QY of > 90% @600-630nm and <40nm FWHM				■	■	◆						
2.1 < 10% QY, < 5nm change @ >1,000 hrs of REL testing				■	■	◆						
3.1 <5% QY change in cured polymer matrix					◆							
3.2 NBD LED color point: 75%/65% single/5-run yield				■	■	■	◆	■	■	◆		
4.1 Spectra w/ LER >350 lm/W @ CRI > 90 & 3000-3500K				◆								
4.2 NBD LED w/ 145 lm/W @ > 80 CRI (RT, 35 A/cm <sup>2</sup> )				■	■	■	◆					

See next slide for Current/Future work

# Project Plan and Schedule – Current/Future Work

Project Schedule												
Project Start: 7/1/15	Completed Work											
Projected End: 6/30/17	Active Task (in progress work)											
	◆ Milestone/Deliverable (Originally Planned)											
	◆ Milestone/Deliverable (Actual)											
	FY2015				FY2016				FY2017			
Task	Q1 (Oct-Dec)	Q2 (Jan-Mar)	Q3 (Apr-Jun)	Q4 (Jul-Sep)	Q1 (Oct-Dec)	Q2 (Jan-Mar)	Q3 (Apr-Jun)	Q4 (Jul-Sep)	Q1 (Oct-Dec)	Q2 (Jan-Mar)	Q3 (Apr-Jun)	Q4 (Jul-Sep)
<b>Current/Future Work (Year 2)</b>												
1.2 QY thermal droop of < 10% from RT to 85°C								◆				
1.3 <10% LF & <2nm peak WL variation for 5 LED runs												◆
2.2 REL testing acceleration factors determined										◆		
3.3 NBD-LED FF CAU within 0.004 du'v' of all-phosphor										◆		
3.4 < 10% NBD-LED LF drop, instant on to steady state											◆	
4.3 NBD-LED w/ >160 lm/W at >80 CRI, RT, 35 A/cm <sup>2</sup>												◆
4.4 NBD-LED w/ >180 lm/W peak at >80 CRI, RT												◆
5.1 Down-select demonstration luminaire form factor											◆	
5.2 Demonstration Luminaire w/ >150 lm/W, 90 CRI												◆