

# Liquid Pathway to SunShot

## 1697-1544

---

Craig Turchi (PI)  
DOE Gen3 CSP Kickoff Meeting  
June 25, 2018



Crescent Dunes Solar Energy Facility, Nevada

# Outline

**Project Overview**

---

**Objectives**

---

**Project Team**

---

**Complementary Projects**

---

**Schedule and Decision Points**

---

---

---

# Liquid Pathway to SunShot

- Leverage expertise with liquid-HTF solar towers
- Use low-cost, thermally stable energy storage media
- Design for  $s\text{CO}_2$  Brayton-cycle integration

Vast Solar's Jemalong sodium-HTF pilot facility (Australia)




SolarReserve's Crescent Dunes molten-salt HTF, Nevada, USA




# Liquid-HTF Alternatives

## Cl-Salt HTF




# Liquid-HTF Alternatives

## Cl-Salt HTF



## Sodium HTF



Direct-storage Na thermocline also considered

# Liquid Pathway Advantages


- High heat-transfer rates; low-pressure HTF
- Established approaches for piping, pump, valve, and HX design (including the receiver)
- High energy and exergy efficiency of storage (direct TES)
- Flexible dispatch—solar collection and power generation are decoupled
- Recognized and accepted by industry and financiers

# Liquid Pathway Challenges

- Liquid-HTF property challenges
  - Cl salt: corrosivity & corrosion control, heat capacity, thermal conductivity, purification & melting, melting point
  - Sodium: reactivity, corrosivity & corrosion control, cost
- Containment material selection
  - Corrosion resistance, strength at temperature, durability, cost
- Receiver efficiency (90% target)
  - Flux limits, pressure drop, selective coatings, cost
- Operations
  - Startup, shutdown, power ramp rates, heat trace & freeze recovery

# Technology Key: Cl-Salt Corrosion Control

DOE-funded work has shown that control of salt chemistry dramatically reduces corrosion in Cl-salt melts




The effect of temperature on the average corrosion rate (reported via current density, note different scales) for the cases with and without cathodic protection in isothermal conditions for Haynes 230 coupons. (Mehrabadi, et al. 2017)



# Cl-Salt Formulation

Carnallite:  
 $\text{MgKCl}_3 \cdot 6 \text{H}_2\text{O}$



Phase diagram of Na/K/Mg–Chloride modeled with FactSage [Mohan et al., Energy Conversion and Management 167 (2018).

# Liquid Pathway

Project Overview

---

**Objectives**


---

# 3-Phase Project

Phase 1: Resolve critical-component issues, select materials

Phase 2: Downselect components, deliver system design & test proposal

Phase 3: Construct, test, and document system results



# Phases 1-2 Objectives

1. Validate and publish the thermo-physical properties of the ternary Mg/Na/K chloride salt
  2. Identify suitable insulating refractory materials for use in molten-chloride salts
  3. Design and estimate the cost of an internally insulated hot-salt tank to control tank-wall temperature to less than 500°C
  4. Design salt pumps, valves, and a primary HX for the 2-MW pilot facility and extrapolate design conditions to full-scale
  5. Design and estimate the thermal efficiency of liquid-HTF receivers, operating at 720°C outlet HTF temperature with a target thermal efficiency approaching 90%.
- *Down select components and integrated-system design and submit Phase 3 proposal*

# Phase 3 Objectives

(Subject to Phase 2 conclusions)

1. **Demonstrate corrosion control** in 300-series stainless steel piping (cold side) and high-Ni alloy piping (hot side) in a flowing chloride-salt loop; validate ability of chemical sensors to monitor HTF chemistry and alert operators to excursions
2. **Fabricate salt tanks** out of 300-series stainless steel with internal insulation to control tank wall temperature to less than 500°C.
3. Build and **test a liquid-HTF receiver**, operating at 720°C outlet HTF temperature with (full-scale) thermal efficiency approaching 90%.
  - Confirm heat transfer rates
  - Demonstrate operations for startup, shutdown, and power ramping
  - Evaluate and define guidelines for receiver fill and drain protocols
4. **Validate pumps**, piping, and fittings in contact with the HTF
5. **Validate primary heat exchanger performance** for heat-transfer rates and ramp rates
6. Perform component and system modeling and **simulate full-scale, SunShot-achieving performance**

# End of Project Deliverables

- **Documentation package** in the form of a national laboratory report that captures component and system drawings and specifications of the 2-MW<sub>t</sub> test system, operating protocols, and lessons learned,
- **Performance model** of annual generation of a full-scale, 100-MW<sub>e</sub> plant based on the tested technology that illustrates the ability to achieve the SunShot goal of 6 ¢/kWh,
- **Video summary** of the project objectives, accomplishments, and impact on the future of CSP, and
- **Transition plan** on how lessons learned in the 2-MW<sub>t</sub> test can be implemented in near-term and long-term commercial plants.

# Liquid Pathway

Project Overview

---

Objectives

---

**Project Team**

---


ASTRI  
Partners

Team Member	Role(s)
NREL	Project management and reporting, Salt receiver design, TES design, corrosion & alloy selection, system analysis
Sandia National Lab	Site Host, Planning and Operations Salt receiver design, project management and on-sun testing (Phase 3)
Savannah River National Lab (SRNL)	Corrosion mitigation and materials selection
Australian National University (ANU) Commonwealth Science & Industrial Research Org. (CSIRO) Queensland Technical University (QUT) University of South Australia (UniSA)	Sodium HTF and salt properties Liquid-sodium receiver, TES design, materials, salt properties, salt/sodium compatibility and heat exchange, solar field/receiver optimization
SolarReserve	CSP Developer: CSP deployment and market analysis
Bridgers & Paxton	Integrator: Facility design, engineering, procurement, and construction
Brahma Group Inc.	Tanks
JT Thorpe & Son	Refractories (tank liner)
Flowserve	Salt pumps and valves
Hexces	Primary heat exchanger
ICL Innovation	Salt supply, blending and melting
EPRI	Technical and Commercial Review panel organizer
German Aerospace Center (DLR)	Freeze recovery protocols




# Administration

Funding/Contractual connections between organizations



# Leadership


- 5-member leadership team guides project and has authority over down-select decisions
- EPRI-led Technical Review Committee supports Leadership Team



# Technology Teams

## Phase 1-2

Technology teams plan and undertake tasks related to specific subsystems and components



# Test Location



Phase 3 testing  
planned for Sandia's  
National Solar  
Thermal Test Facility

# Liquid Pathway


Project Overview

Objectives

Project Team

**Complementary Projects**

# Complementary Projects



- Complementary Topic 2A work will be tracked and reviewed during Phase 1
- At the outset of Phase 2, downselections are made to the preferred system design

Support Testing feeds information into design activities

# Liquid Pathway

Project Overview

---

Objectives

---

Project Team

---


Complementary Projects

---

**Schedule and Decision Points**

---


# Phase Schedule





# System and Component Downselection

- Leadership team has authority over downselect decisions
  - At onset of Phase 2, workshops will review options and downselect components
  - Analytic hierarchy process will be used to aid decision making
  - EPRI-led Technical Review Committee will provide guidance on market acceptance of the different system designs



# Thank you

---

[www.nrel.gov](http://www.nrel.gov)

**NREL is a national laboratory of the U.S. Department of Energy, Office of Energy Efficiency and Renewable Energy, operated by the Alliance for Sustainable Energy, LLC.**



# Supporting Slides for Q&A Period

---

# Go/No-Go Decision Points

*Budget Period 1 Go/No-Go (Q6), Proceed with Phase 3 proposal development.* NREL will present all preliminary engineering, design, cost models, sites studies, etc. to DOE and the Technical Review Committee. The component performance and cost estimates will be captured in an annual simulation model for the commercial-scale design to illustrate the path to achieving the SunShot goal of 6 ¢/kWh.

*Budget Period 2 Go/No-Go (Q8). Proceed to Phase 3 procurement and construction.* NREL will submit all preliminary engineering, design, cost models, sites studies, etc., embodied in the Phase 3 Submittal Package to DOE. The FOA states DOE's intention to down-select to a single Topic Area 1 award for continuation to Phase 3 activities.

*Budget Period 3 Go/No-Go (Q15). Proceed with system startup and testing.* NREL will provide the Safe Operating Procedures to the Technical Review Committee and DOE's designee for verification of completion and adequacy.

# Construction Expertise


- Bridgers & Paxton: system integrator for design and build; provide design package, system specifications, controls

B&P was selected by Areva for their molten-salt system test at Sandia



- Brahma Group Inc: tank design and construction in this project, but capable EPC contractor

Brahma served as a construction contractor at Crescent Dunes



Review

# A review of sodium receiver technologies for central receiver solar power plants

J. Coventry<sup>a,\*</sup>, C. Andraka<sup>b</sup>, J. Pye<sup>a</sup>, M. Blanco<sup>c</sup>, J. Fisher<sup>d</sup>

<sup>a</sup> Australian National University, Research School of Engineering, Canberra, ACT 0200, Australia

<sup>b</sup> Sandia National Laboratories, P.O. Box 5800, Albuquerque, NM 87185-1127, USA

<sup>c</sup> CSIRO Energy Flagship, 10 Murray Dwyer Cct, Mayfield West, NSW 2304, Australia

<sup>d</sup> Vast Solar, Level 10, 17-19 Bridge St, Sydney, NSW 2000, Australia



Fig. 5. 1.2 MW<sub>th</sub> tubular sodium receiver at Vast Solar's Jemalong Solar Thermal Station.




Fig. 9. Exergy balance for (a) salt and (b) sodium receivers with equal solar flux ( $C = 800$ ) and equal 300–550 °C working fluid temperature range. Also includes (c) sodium with 500–850 °C working fluid range and (d) sodium with both 500–850 °C and  $C = 1600$  (adapted from Pye et al., 2014).

# Internally Insulated Tank

