



HARMONIZATION OF STATION ACCEPTANCE PROCEDURES IN GERMANY WITH SAE AND ISO BY CLEAN ENERGY PARTNERSHIP (CEP)

International Hydrogen Infrastructure Workshop, 11.-12.09.2018, Boston
Thomas Brachmann, Honda R&D Europe (Deutschland) GmbH



ORGANIGRAM

WORKING GROUP HRS // TT FUELLING PROTOCOL / 3RD PARTY

Clean Energy Partnership / TaskTeam fuelling protocol / 3rd Party

Members



HONDA



Activities



Evaluation of HRS test reports for approval



Training 3rd Party



Harmonization of CEP & ISO tests



Standardized report template

Future activities

HRS Certification outside Germany

New refuelling protocols






Training subcontractors

New transport modes

The TaskTeam has set-up group workshops to define required HRS approval procedures


CEP HRS APPROACHES

WHERE WE ARE AND WHAT WE WANT

Main Questions	Activities	Status
Which test program should be used for testing in future?	<ul style="list-style-type: none"> Defining a test according to CEP & ISO: Workshop 1&2 <ul style="list-style-type: none"> Implementation of the tests as FAT or SAT? Additional performance tests? 	
How has the test to be evaluated?	<ul style="list-style-type: none"> Sharpening the scope for interpretation of current SAE / ISO regulations. What are minor and what are significant challenges for the acceptance? 	
How should the test be documented?	<ul style="list-style-type: none"> Creation of a reporting standard 	
Who tests and evaluates?	<ul style="list-style-type: none"> Enabling an independent 3rd party (ZSW) to evaluate the reports and test the HRS 	
When should a test be repeated?	<ul style="list-style-type: none"> When does an acceptance test (including periodic inspections) becomes necessary? 	

CEP ACCEPTANCE TEST

HISTORY & OUTLOOK



AFID: Alternative Fuel Infrastructure Directive

CEP ACCEPTANCE TEST

APPLICATIONS

- The CEP test is standardized and necessary to get an approval for public refuelling
- 25 tests allowing to validate the HRS system/components and HRS performance
 - Creation of a test report, evaluated by the car OEMs within the CEP



CEP ACCEPTANCE TEST PROCEDURE

Each CEP HRS utilizing the SAE J2601-2014 refuelling protocol

- has to successfully pass the safety function test procedure and
- should fulfil the station performance test procedure

Test procedure validates


- Safety related functions
- Customer related performance

Test no.	realized b	function	IrDa	Preparation to be performed	Perform during main refueling part	Test outcome
1	FAT or HSTA	Ambient temperature (T_{amb})	NR	Influence T_{amb} measurement to $< -40^{\circ}\text{C}$ by manipulation of transmitter signal loop	not relevant	Main refueling part is not allowed to start
2	FAT or HSTA			Influence T_{amb} measurement to $> 50^{\circ}\text{C}$ by manipulation of transmitter signal loop		
3	FAT or HSTA	Vehicle tank starting pressure	NR	Refuel with < 0.5 MPa starting pressure by manipulation of transmitter signal loop	not relevant	Main refueling part is not allowed to start
4	FAT or HSTA			Refuel with > 70 MPa starting pressure by manipulation of transmitter signal loop		
5	FAT or HSTA	Excess hydrogen flow	NR	Manipulation of transmitter signal loop. Additional hardware might be required for manipulation of signal without software change.	Influence hydrogen mass flow measurement to $> 60\text{g/s}$	Refueling must be aborted
6	HSTA	Absolute hydrogen delivery temperature	NR	not relevant	After a period of > 35 sek. influence hydrogen delivery temperature measurement under the lowest permitted temperature (e.g. $< -40^{\circ}\text{C}$ @ T40 Stations)	Hydrogen delivery temperature has to be under the upper temperature limit within 30 s and then refueling must be aborted when leaving the fuel delivery temperature corridor.
7	FAT or HSTA	Hydrogen delivery pressure monitoring	No	Manually calculate expected APRR based on observed starting conditions	Influence hydrogen delivery pressure measurement above APRR Corridor	Refueling must be aborted. Compare the manual calculated APRR with the actual (ideal) APRR (Tolerance value to be evaluated).
8	FAT or HSTA				Influence hydrogen delivery pressure measurement below APRR corridor	
9	FAT or HSTA		Yes		Influence hydrogen delivery pressure measurement above APRR corridor	
10	FAT or HSTA				Influence hydrogen delivery pressure measurement below APRR corridor	

Current CEP base document characterizing the required tests

WHICH TEST PROGRAM SHOULD BE USED FOR TESTING IN FUTURE?

CEP & ISO: ONE PROTOCOL TO TEST THEM ALL



Current CEP approval tests:

- acceptance test_SAEJ2601-2010 (8 Tests – old projects only)
- acceptance test_SAEJ2601-2014 (25 Test)

ISO 19880-1 approval tests:

- SAT* Option 1 (7 Tests)
- SAT* Option 2 (9 Tests - Japan)
- FAT* & SAT* Matrix (33 Tests)

*Site Acceptance Tests (SAT),
Factory Acceptance Tests (FAT)

DEFINING A TEST ACCORDING TO CEP & ISO

SHARPENING THE SCOPE FOR INTERPRETATION OF CURRENT SAE / ISO REGULATIONS



Tests	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33
ISO	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33
CEP				22	1	2	3	4		5	p	11			15		p					p	p	p	16	17	p	21	22		p	13	p
FAT	X	X	X	X	X	X	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
SAT	X				X	X	X	X	X		X			X	X	X	X	X	X	X				X	X	X		X		X	X	X	X

Comparison ISO 19880-1 + CEP

- Only in CEP or ISO
- Partly in CEP or ISO
- In CEP and ISO

CEP & ISO harmonization to be finished shortly

Plan: to be replaced by ISO 19880-1 FAT and SAT tables

- Annex I : Table C.2 - FAT and SAT Matrix
- Test procedure based on Chapter 12: SAT Option 1 Table
- Consistency between former tests and ISO tests to converge

Important 2 know

“CEP hydrogen fuelling validation test protocol” will be part of ISO appendix

- incl. harmonization of ISO & CEP tests

Synopsis of ISO and CEP Tests

DEFINING A TEST ACCORDING TO CEP & ISO

SHARPENING THE SCOPE FOR INTERPRETATION OF CURRENT SAE / ISO REGULATIONS



Development of a database within the CEP to comment on ISO & CEP tests



HONDA



Overview

number of Tests: 25

TEST N° Partly in ISO || CEP 20

05.07.2018

ISO Test

Partly in ISO

☒ in ISO
 ☒ in CEP
 ☒ in SAE

CEP Test No.

CEP 20

FAT No.

ISO / CEP

CEP 20 / ISO 17, 24

ISO No.

ISO 19880-1

Category

Fault: Communications Abort

SAE No.

SAE J2601

SAT/FAT

☐ FAT
 ☒ SAT

CEP Proposals

☐ FAT
 ☒ SAT

☒ Safety relevant
 ☒ Performance relevant
 ☒ Evaluation relevant

☒ should be done
 ☐ should not be done

Sort by Tests

CEP Tests

ISO Tests

CEP/ISO Tests

Sort by CEP Proposals

Safety relevant

Performance relevant

Evaluation relevant

Should be done

Should not be done

FAT

SAT

Sort by 2DOS

2 DO

number of Tests: 25

Test Info

To be monitored even with non-communications fueling (if applicable)

Function

Abort Signal Test and if applicable vehicle volume determin. Test should be splitted in volume determination and abort signal test

TestOutCome/ Acceptable Criteria

Refueling must be aborted. The determined volume must be within an accuracy of ±15%. Volume determination must happen optionally through IR or switch to the most conservative ramp
 Fueling Stop within 5 s with out-of-bounds

Preparation to be performed

starting pressure: <5 MPa (+/-1 MPa)

☐ COM
 ☐ Non COM
 ☐ Fall Back
 ☒ Top Off

Perform during main refueling part

Simulated Communications Abort Signal, e.g. by manipulating of signal loop
 HSTA should send an Abort Signal after 20-30 seconds.

☐ T Statement
 ☐ Pulse Statement
 ☒ IrDA

2Dos

☐ ToDo

Comment FAT / SAT

Abortion test. Cannot be performed in FAT

Comment after repair

New test required if communication is successful (software, IR/nozzle exchange if necessary)

Comment TaskTeam

Comment Air Liquide

Comment Linde

Each HRS report is available in CEP HRS approval data base/bank

THE PROCESS FOR HRS APPROVAL TODAY & FUTURE

Procedure	Description	Responsibility
1. declaration	The HRS supplier declares the SAE conformity of the system.	HRS-Supplier
2. testing	The HRS is tested by a qualified independent 3rd party on behalf of the HRS operator/supplier in accordance with the CEP acceptance program. The results are documented in detail in an acceptance report.	HRS-Supplier / 3rd Party
3. evaluation	The acceptance report and declaration of conformity are checked and confirmed by a qualified independent 3rd party on behalf of the plant operator/supplier. This should preferably take place within the framework of HRS testing by the ZÜS.	3rd Party / ZÜS
4. control	The acceptance report will be submitted to the OEMs. The OEMs evaluate the report and discuss the results with the HRS supplier.	OEMs
5. approval	Explicit approval of the acceptance reports by the OEMs.	OEMs

HANDOVER TESTING TO AN INDEPENDENT 3RD PARTY

	Who is conducting the test?	Who is creating the acceptance test report?	Who assess the acceptance test report?	Who gives the HRS approval?
Past	HRS-Supplier	HRS-Supplier	OEMs	OEMs
Today	HRS-Supplier + independent 3rd party	HRS-Supplier + independent 3rd party	OEMs	OEMs
Target: 2nd step	HRS-Supplier + independent 3rd party <ul style="list-style-type: none"> • Retest of selected inspection points or • Perform all site acceptance tests 	independent 3rd party <ul style="list-style-type: none"> • 3rd party has to create an acceptance test report for at least 2 stations of every manufacturer 	OEMs + independent 3rd party <ul style="list-style-type: none"> • 3rd party has to assess an acceptance test report for at least 2 stations of every manufacturer 	OEMs
Target for 2018/2019	independent 3rd party	Independent 3rd party	independent 3rd party	OEMs

DEFINE REPORT TEMPLATE FOR ACCEPTANCE TEST

Main Questions

How should the test be documented?

Activities

- Creation of a reporting standard
- Who bears the costs of the examination?
- When does an acceptance (including periodic inspections) become necessary?

Open Items

- quality of the reports has strongly improved, but reporting format is still not comparable
- report template was prepared and approved
- data quality, temporal resolution, measurement uncertainties, calibration certificates of the sensors: required for 3rd party?
- HRS data details to become accessible through technology provider

	N° Chrono Tests N° Station N° Client	012504-N1-01003_SAE-J2601 Safety and performances Wendlingen H2M	Page : 1/55
HYDROGEN REFUELLING STATION SAE J2601 Safety and Performances tests			
			
AIR LIQUIDE Advanced Technologies 2 rue de Clémenceire F - 38360 SASSENAGE ☎ +33 (0)4 76 43 62 11 or / ou +33 (0)4 76 43 62 27 - Fax : +33 (0)4 76 43 62 71			
Measurements & records Yacine BRAIK Corentin AIRIAU		Distribution (Diffusion): Date : October 11th 2017 Version : (0)	
Approbation Damien SALLAIS/Sylvain PAYARD/Christophe MICHEL Industrial Solutions Europe ☎ +33 (0)6 12 78 11 67			

Le document est la propriété de Air Liquide. Il est à usage interne et ne doit pas être communiqué à des tiers. Il est soumis aux conditions de confidentialité de Air Liquide. Toute réimpression ou utilisation non autorisée sans la permission écrite de Air Liquide est formellement interdite. Toute réimpression ou utilisation non autorisée sans la permission écrite de Air Liquide est formellement interdite. Toute réimpression ou utilisation non autorisée sans la permission écrite de Air Liquide est formellement interdite.

BUSINESS CONFIDENTIAL INFORMATION



HOW SHOULD THE TEST BE DOCUMENTED?

CREATION OF A REPORTING STANDARD



Activities

Creation of a reporting template “CEP hydrogen fuelling validation test protocol”
Template will be part of ISO appendix (incl. harmonization of ISO & CEP tests)

Status




THE LINDE GROUP

Linde

Abnahme
nach Wasserstofftankstellen
für SAE J2601-2014

Shell Tankstelle
Verdistr 96
München



[Bild: Shell Tankstelle Verdistr 96 München]

Abnahmeprüfung SAE J2601
Benennung: Verdistr 96

1.25

11.07.2018

 AirLiquide Air Credo T'ou N° Client	01 30 60 411 - 010103 - 0101 20071 Safety and performances Weedingen HCM	Page : 1/55	
<div style="text-align: center;"> HYDROGEN REFUELLING STATION SAE J2601 Safety and Performances test </div>			
			
AIR LIQUIDE Advanced Technologies 2 rue de Cécilemence F - 38180 SAINTEVAL ☎ + 33 (0)1 76 43 62 11 or / ou ☎ +33 (0)1 76 43 62 27 - Fax : + 33 (0)1 76 43 62 71			Distribution (Diffusion): Date : October 11th 2017 Version : (0)
Measurements & records Victor BILAU Caroleen AIRLIQ Approbation Damien SALLAIS/Sylvain PAYARD/Christophe MICHEL Industrial Solutions Europe ☎ + 33 (0)6 12 28 11 87			

17020001-7	Author: JB	Version: 001
Date: 02-12-2016	Enddate:	Confidentiality: 2
File Name: qualification	Document reference:	CONFIDENTIAL

Confidential for CAR OEMs within the CEP only

H2STATION® TECHNICAL SPECIFICATION

For CEP SAEJ2601-1 and performance validation test

H2station HS001 200kg/day


CONFIDENTIAL

For CAR OEMs within the CEP only

Document revision Fig. 0

Revision no.	Author	Issue date	Comments
001	JB	02-12-2016	First Edition

© 2016 H2i, H2station | www.h2i-hydrogen.com Page 1 of 7

	Test No:	ZSW-FTSM00001, Version 1.2	HRS: Moardeicher Landstr. 85-86 D-28116 Sautr	Page:	1 of 24
	Customer:	H2M			
	Technology:	NEL			

HYDROGEN REFUELLING STATION

SAE J2601-2016 Safety and Performance tests

Zentrum für Sonnenenergie und Wasserstoff-Forschung Baden-Württemberg
 Heintzelstr. 8, 70509 Ulm
 Fon: + 49 (0) 731 9530-421 or + 49 (0) 731 9530-434, Fax: + 49 (0) 731 9530-666
markus.jenne@zsw.de, guenther.schlumberger@zsw.de

Measurements & Records

Done by	Date
Markus Jenne	18. 8.11
Günter Schlumberger	July 2018

Evaluation & Report


Version	Done by	Date	Remarks
1.0 & 1.1	Günter Schlumberger	25.07.2018	
1.2	Günter Schlumberger	31.07.2018	

Approval & Distribution

Version	Approved by	Date	Recipients	Date
1.1	Markus Jenne	25.07.2018	Cemil Cömert, H2M Mike Huttmacher, H2M	27.07.2018
1.2	Markus Jenne	25.07.2018	Cemil Cömert, H2M Mike Huttmacher, H2M Dr. Alexander Kabis, ZSW	31.07.2018

BUSINESS CONFIDENTIAL INFORMATION

ACTIVITIES & CHALLENGES




Activities

- Definition of a test according to CEP & ISO
– Discussion with ISO
- Training an independent 3rd party (ZSW) to perform the tests and create and evaluate the test reports
- Creation of a reporting standard for a 3rd party and manufacturer

Status



 **50 HRS approved (9/2018)**


 **44 HRS in realization**



For the timely opening of announced HRSs, the assessment time needed for OEMs averages to minimum 3 weeks including various iteration rounds in which OEMs demand safety & performance related clarifications from HRS technology providers

TRIAL PERIOD FOR 3RD PARTY QUALIFICATION

TIME FOR APPROVAL PROCESS & DISCUSSION




CHALLENGES AHEAD

REDUCTION OF OVERALL APPROVAL TIME & PROCESS SPREAD IN EU

- Adoption of harmonized test reports standards for a 3rd party and technology provider
- Reach a consistent HRS opening schedule with min. 3 weeks lead time for car OEM review of test reports
- Enhance quality of test reports to reduce iterations with OEMs for final approval
- Negotiation with EU countries to adopt the established HRS approval process

Car OEMs are committed to provide expertise to the approval process for best future test report quality

FUTURE ACTIVITIES



HRS certification in Europe



New refuelling protocols



**Training
subcontractors**

MOVE IT WITH HYDROGEN

Thomas Brachmann
Chief Project Engineer
Honda R&D Europe
+49 698 9011 506

Thomas_Brachmann@de.hrdeu.com

