



Oregon State
University

High Flux Microchannel Receiver Development

Brian M. Fronk

Award # DE-EE0007108

Presented at SETO CSP Program Summit

March 19th, 2019

COLLEGE OF
ENGINEERING

School of Mechanical, Industrial, and
Manufacturing Engineering

sCO₂ High Flux Receiver Development



Project Goals

- Receiver efficiency > 90%
- sCO₂ from 550°C to 720°C
- $P = 250$ bar
- < \$150/kW_{th}
- > 10,000 cycle life



Oregon State
University

UCDAVIS




Micro-Pin Receiver Concept

Advantages


- $D_H \downarrow h \uparrow$
- Thin walls
- Reduced material
- Modularity

Challenges

- Thermal hydraulic
- Materials
- Manufacturing
- Reliability




~ 300 μm




~ 350 MW
thermal



Approach: Numbering-Up Concept






Technology Development TRL 3→5



Prototype Development



Impact – Design, Materials and Fabrication



- Joining high temperature nickel alloy
- Qualifying vendors (machining, etching, etc.)
- Ongoing work to mitigate identified failure modes

Impact – On Sun Demonstration




UCDAVIS

- Phase 1 prototype
- Direct heating of $s\text{CO}_2$
- 8 cm x 8 cm

Impact – Performance Goals



- Based on experimentally validated thermal models **OSU predicts receiver efficiencies that exceed Sunshot Goals for both supercritical CO₂ (91% to 93%) and molten salt (90% to 93%)**
- Based on an experimentally validated mechanical model **OSU predicts pin array life times that exceed 12,000 thermal/pressure cycles** meeting Sunshot Goals for supercritical CO₂. Due to low pressure, this is not expected to be an issue with molten salt
- Based on experimentally validated thermal models **OSU has shown that the MSR applied to molten salt can have a 30 year life with corrosion rates of 15 microns per year** and meet Sunshot receiver efficiency goals

Impact – Cost Targets



Receiver Elements	Costs
Solar Receiver Capacity	350,000 kW _t
Valves	\$4,525,000
Receiver Piping (inlet)	\$32,098
Receiver Piping (Outlet)	\$411,790
Inlet Piping #1	\$54,915
Outlet Piping #1	\$704,220
Inlet Piping #2	\$8,827
Outlet Piping #2	\$100,826
Inlet Connectors	\$8,781
Outlet Connector	\$56,284
Structural Members	\$62,693
Losses (2%)	\$28,809
Welding	\$711,542
Transportation	\$6,600
Crane	\$108,852
Modules	\$6,194,500
Total Direct Costs	\$13,015,737
Contingency (10%)	\$1,301,574
Total Cost	\$14,317,311
Cost/kW_t	\$40.90



Impact – Gen3CSP Pathways



- Designs developed for lower pressure sCO₂, He, molten salt with >90% efficiency
- Cost advantage increase at lower pressure

Looking Forward

- Pathway to megawatt scale demonstrated
- Modular concept advantageous
 - Tailored receiver design
 - Manufacturability
- Detailed investigation of joining processes
- **On-sun testing to 720 °C**
- Larger format prototypes with at-scale fabrication techniques



Acknowledgments

Oregon State University

- Kevin Drost
- Brian Paul
- Sourabh Apte
- Rajiv Malhotra

SNL

- Kevin Albrecht
- Clifford Ho
- Matt Carlson

UC-Davis

- Vinod Narayanan
- Erfan Rasouli

NETL

- Omer Dogan
- Kyle Rozman
- Matt Carl

PNNL

- Mark Weimer



**SOLAR ENERGY
TECHNOLOGIES OFFICE**
U.S. Department Of Energy