




DUF6 Facility Design Lessons Learned

2019 Department of Energy
Project Management Workshop
"Technology Implications"

Reinhard Knerr
Federal Project Director
Department of Energy





Depleted Uranium Hexafluoride (DUF₆) Project

DUF₆ Mission

Operate conversion facilities to safely convert DUF₆ into a more stable chemical form (oxide) for beneficial reuse or disposal thus reducing immediate and future risk to workers and surrounding community.

Conversion generates two products:

- Uranium Oxide
- Aqueous Hydrofluoric Acid





DUF₆ Project




- DUF₆ resulted from the uranium enrichment process at DOE's three Gaseous Diffusion Plants.
- 67,000 14-ton DUF₆ Cylinders in storage at the beginning of the Project.
- Two DUF₆ Conversion Facilities constructed to convert DUF₆ into stable uranium oxide.
- Construction started in 2004. Operations began in 2010 (Portsmouth) and in 2011 (Paducah).



DUF₆ Project

DUF₆ Physical Process





Post Construction Plant Reconfiguration and Retrofit

PAD Line Monthly Run Time FY19

FY19 Largest Lost Production


PORTS Line Monthly Run Time FY19

➤ **Safety**
➤ **Maintainability**
➤ **Reliability**





Safety





Safety

Removed Filters in KOH Recovery Building





Safety

There is a future project to install double blocks and bleeds around equipment in the HF storage section of the plant.




Photo of single block around HF pumps



Safety

LOTO


10. TAG NO.	11. ENERGY ISOLATING DEVICE	12. DEVICE STATUS	13. LOCKABLE (Yes/No)	19. ALIGNED/ LOCKED/ TAGGED BY	37. CONCURRENT VERIFICATION BY	20. INDEPENDENT VERIFICATION BY
45	X-2-HFR-VA-5032	Process Offgas	NO	KR	<i>[Signature]</i>	RK
46	X-0-IAS-VA-049D	CLOSED	YES	KR	<i>[Signature]</i>	RK
47	X-2-HFR-VA-5102	CLOSED	NO	KR	<i>[Signature]</i>	RK
48	X-0-IAS-VA-049J1	CLOSED	YES	KR	<i>[Signature]</i>	RK
49	X-3-HFR-VA-5022	Process Offgas	NO	KR	<i>[Signature]</i>	RK
50	X-0-IAS-VA-049E	CLOSED	YES	KR	<i>[Signature]</i>	RK
51	X-3-HFR-VA-5032	Process Offgas	NO	KR	<i>[Signature]</i>	RK
52	X-0-IAS-VA-049F	CLOSED	YES	KR	<i>[Signature]</i>	RK
53	X-3-HFR-VA-5102	CLOSED	NO	KR	<i>[Signature]</i>	RK
54	X-0-IAS-VA-049K1	CLOSED	YES	KR	<i>[Signature]</i>	RK
55	X-1-HFR-VA-5234	CLOSED	YES	KR	<i>[Signature]</i>	RK
56	X-1-POS-VA-6090	CLOSED	YES	KR	<i>[Signature]</i>	RK
57	X-1-POS-VA-6012	CLOSED	YES	KR	<i>[Signature]</i>	RK
58	X-1-POS-VA-601D1	CLOSED	YES	KR	<i>[Signature]</i>	RK
59	X-1-HFR-VA-5232	CLOSED	YES	KR	<i>[Signature]</i>	RK
60	X-1-HFR-VA-5211	CLOSED	YES	KR	<i>[Signature]</i>	RK
61	X-1-HFR-VA-5210	CLOSED	YES	KR	<i>[Signature]</i>	RK
62	X-1-HFR-VA-5212	CLOSED	YES	KR	<i>[Signature]</i>	RK
63	X-1-HFR-VA-5213	CLOSED	YES	KR	<i>[Signature]</i>	RK
64	X-1-HFR-VA-5205	Aligned to TK-520	YES	KR	<i>[Signature]</i>	RK



Maintainability

Insufficient Isolation Capability

Individual Hydrogen Fluoride Tanks cannot be taken out of service.



April 2019




2019 DOE Project Management Workshop


10



Maintainability




Inadequate accessibility to components/equipment during maintenance.






Maintainability



Recovery H2O
Scrubber

Liquid HF
Receiver Tank

Transfer
Systems



Valves


HF Pump

HF Pump



Maintainability


HF Recovery and Off-Gas Scrubber Systems





Maintainability


Permanent scaffolding replaced temporary scaffolding.



Hydrogen Fluoride Recovery System.



Reliability




Cylinder Evacuation Room (CER)- Design didn't work




Reliability

➤ No Bypass / Common Header






Reliability



Original Condenser



Prototype Condenser





Reliability



Outdoor Cranes-Before



Outdoor Cranes-After



Reliability



HF detection system for HF transfer line.



Only one crane in the VAP area.

Single Point Failures




Reliability



Single Blower



Redundant Blowers



KOH Piping Valves

Backup Scrubber

Redundant Pump Pair

- Secondary scrubber was designed with one scrubber recirculation pump and one blower.
- Added a redundant scrubber recirculation pump and a redundant blower.



Reliability



Original H2 Gen

- Obsolete when DUF6 Plant Started
- Capacity Degraded
- Design Issues.




New Prism Unit



Reliability



Single Point Failure



Tube-Truck/Tank
Backup Supply System



Conclusion

The Project is spending tens of millions of dollars in retrofits to improve safety, maintainability and reliability.



These retrofits if factored in on the front end of the design would have reduced the Projects operations and maintenance costs.