

# TESTING OF A 1 MWe SUPERCRITICAL CO<sub>2</sub> TEST LOOP

Jeff Moore, Ph.D.

Southwest Research Institute (SwRI)

[energy.gov/sunshot](http://energy.gov/sunshot)



EPR | ELECTRIC POWER  
RESEARCH INSTITUTE



# Sunshot Team



# Project Objectives

- To develop a novel, high-efficiency supercritical CO<sub>2</sub> (sCO<sub>2</sub>) hot-gas turbo-expander optimized for the highly transient solar power plant duty cycle profile
  - This sCO<sub>2</sub> turbo-expander design advances the state-of-the-art from a current Technology Readiness Level (TRL) 3 to TRL 6
- To optimize novel recuperator technology for sCO<sub>2</sub> applications to reduce their manufacturing costs
- The sCO<sub>2</sub> turbo-expander and heat exchanger will be tested in a 1-MWe sCO<sub>2</sub> test loop, fabricated to demonstrate the performance of components along with the overall optimized sCO<sub>2</sub> Brayton cycle
- The scalable sCO<sub>2</sub> turbo-expander and improved heat exchanger address and close two critical technology gaps required for an optimized concentrating solar power (CSP) sCO<sub>2</sub> plant and provide a major stepping stone on the pathway to achieving CSP at \$0.06/kW-hr levelized cost of electricity, increasing energy conversion efficiency to greater than 50%, and reducing total power block cost to below \$1200/kW installed

Team: SwRI, GE, KAPL, Thar Energy, Navy Nuclear Laboratory, Aramco, EPRI, US DOE

Project: 5-year, \$10 million program to develop & test an expander & recuperator for sCO<sub>2</sub> power generation from CSP


Schedule: Expander, recuperator, and test loop design complete

System targets:


- 10 MWe net module size
- 50% net thermal efficiency

Expander targets:

- ~14 MW shaft power
- >700°C inlet temp
- >85% aero efficiency
- Multi-stage axial




# Simple sCO<sub>2</sub> Recuperated Cycle for Test Loop





# Loop Operating Conditions

Component	T out, °C (°F)	P out, bar (psi)	Flow, kg/s (lb/s)
Pump	29.22 (84.60)	255.0 (3698)	9.910 (21.85)
Recuperator-Heat	470.0 (878.0)	252.3 (3659)	8.410 (18.54)
Heater	715.0 (1319)	250.9 (3639)	
Expander	685.7 (1266)	86 (1247)	
Recuperator-Cool	79.58 (175.2)	84 (1218)	9.910 (21.85)
PreCooler	10.00 (50.00)	83 (1204)	

# Sunshot Turbine Design




# Rotor Design



4-Stage Axial Flow Design





- Temperature gradient at shaft ends required due to dry gas seals



Temperature profile in the shaft and stator piece in the thermal management region

(Blue = 50°C, Red = 715°C) (Kalra, et. al, 2014)

- Long flexible rotor and high gas density makes rotordynamics challenging



Rotordynamic Prediction for First Critical Speed

Rotordynamic Experience Chart from Moore (2006) with Sunshot Turbine Rotor Added



# 40 MMBtu/hr (11.7 MW) Heater

	Recuperator Outlet/ Heater Inlet	Heater Outlet/ Turbine Inlet
Temperature	470°C	715°C
Pressure	251.9 bar	250.9 bar
Mass flow rate of CO <sub>2</sub>	8.410 kg/s	8.410 kg/s



# Heater Heat Exchanger

- Staggered tube configuration
- Designed by SwRI and Thar
- Manufactured by Thar
- First Inconel 740H heat exchanger



- Sourced Printed Circuit Heat Exchanger (PCHE) from Vacuum Process Engineering (VPE) for Recuperator
- Plates are chemically etched and diffusion bonded in a large vacuum furnace.






Image courtesy of vpei.com



# VPE Recuperator on Stand



- 12 stage, 3600 rpm pump
- Provided by BHGE
- 80 to 250 bar at 15 kg/sec



# Turbine Assembly

- Assembly completed with no major issues
- All fits and seal clearances verified
- Rotor runout met specifications
- Axial end-play adjusted with shim packs
- Radial bearing clearances verified
- Thermal seal instrumentation added






# Turbine Assembly Completed


- Turbine assembled and installed on test stand
- Connections made to turbine in this order:
  - Large piping
  - Small piping
  - Lube oil supply and drain
  - Instrumentation




## Turbine Case Assembly



# Test Loop Components



# Assembled Turbine Casing on Operating Stand



# Final Assembled Turbine Test Rig



# Turbine Design Operating Points



	Speed (rpm)	Turbine Inlet Temp. °C (°F)	Turbine Inlet Pressure bar (psi)	Turbine Exit Pressure bar (psi)
<b>1<sup>st</sup> Design Point</b>	21,000	550°C (1022°F)	~200 bar (3000 psi)	80 bar (1160 psi)
<b>2<sup>nd</sup> Design Point</b>	27,000	715°C (1319°F)	~250 bar (3625 psi)	80 bar (1160 psi)

- SunShot

- 27,000 rpm; 1,320F; 3,500 psi
- 12 total turbine starts with 3 controlled shutdowns and 9 observed trips
- 37.5 hours of turbine operation
- Observed transients to determine how the loop performs to fast shutdowns to help with future designs
- Observed necessary trips and how the loop operated after and how to bring everything back online

- FOCUS

- Tested both thermals seals to similar operating conditions
  - 1020F; 21,000 rpm
  - Matched similar dry gas seal flows
  - Obtained thermal seal and case temperatures



# Test Results – 27,000 rpm

## 27000 rpm

27003 Expander speed a

27003 Expander speed b

3494.15 ORF-102 Expander inlet P

106.944 ORF-102 Expander inlet T

3.14039 ORF-102 Expander inlet DP

12.762 ORF-102 Expander inlet flow

801.976 Bolt T inlet side a

841.848 Bolt T inlet side b

190.4 Expander inlet side bearing T

2892.85 Expander balance piston HP P

181.642 Expander outlet side bearing T

0.511804 Expander NDE (IS) X prox

0.528434 Expander NDE (IS) Y prox

-0.58078 Expander NDE (IS) axial Z prox

0 Expander NDE (IS) X accel

0 Expander NDE (IS) Y accel

1066.5 Expander inlet T1

1104.78 Expander inlet T2

3376.51 Expander inlet P

Expander outlet T1

986.728 Expander outlet T2

1143.79 Expander outlet P

1151.8 ORF-105 Balance line P

861.815 ORF-105 Balance line T

15.8525 ORF-105 Balance line DP

1.69804 ORF-105 Balance line flow

0.576676 Expander DE (OS) X prox

0.555743 Expander DE (OS) Y prox


2.77528 Expander DE (OS) axial Z prox

0 Expander DE (OS) X accel

0 Expander DE (OS) Y accel


### LEGEND

- Temperature, deg F
- Pressure, psia
- Speed, rpm
- Vibration, mils pp or mils
- Acceleration, g
- DP, in H2O
- Flow, lbm/s






# Turbine Vibration Spectrum at 27,000 rpm




# Heater at 1750F (954C)




## 6 Hour 715C Endurance Test






Temperature vs Axial Location




# Turbine Transients

HIGH TEMPERATURE TRIP - SETTLE OUT TEMPERATURE



- Two trips evaluated
  - Highest temperature trip after 1,320F was reached
  - Highest pressure trip after 27,000 rpm was reached
- High temperature trip
  - Settle pressure is reached in less than 10 seconds
  - Dry gas seal flow still buffering turbine seals. Turned off after 30 minutes and turbine section vented

HIGH TEMPERATURE TRIP - SETTLE OUT PRESSURE




# Summary

- Turbine performance met mechanical and performance objectives.
  - Achieved design temperature of 715C, design speed of 27000 rpm, and near design pressure of 250 bar.
  - Highest temperature SCO<sub>2</sub> turbine to date.
  - Thermal seal maintained acceptable dry gas seal operating temperature with near linear profile.
  - Vibration well less than 0.5 mils with no signs of instability
  - Low critical speed response (good bearing damping and balance)
  - Good thrust balance and low thrust bearing temperature
  - Radial bearing temperatures low following modification
  - Many shutdown transients tolerated
    - Some leakage experienced out case joints due to loss of bolt preload
    - Being addressed with single piece case design with STEP
  - Modified dry gas seal panel maintained warm seal gas preventing dry ice formation

# Challenges with 700C Plant Design

- 700C yields greater efficiency than 550C but requires advanced nickel alloys for the hot section
- Material strength is creep limited above 600C
- Piping Materials
  - 316 stainless (\$8/lb) (up to 600C)
  - 347 stainless (\$9/lb) (up to 600C)
  - P91 (9 % chromium, 1 % molybdenum) (\$6/lb) (up to 450C due to spalling at higher temperatures)
  - IN625 (\$45-60/lb 8" and up) (up to 650C) (age hardening occurs above 650C)
  - IN740H (\$36/lb 8-10" from Special Metals) (up to 800C)
- Forging and bar stock costs:
  - IN 718 (\$36/lb)
  - Waspalloy (\$40/lb)
  - Nimonic 105 (\$47/lb)
  - Haynes 282 (\$19) (bar)
  - IN740H (\$22/lb) (bar)
- Inconel 740H primary heater and interconnecting piping required to avoid age hardening of IN625 above 650C.

# RCBC Cycle Efficiency vs. Turbine Inlet Temperature





# Acknowledgements

---

The authors would like to thank...

- Office of Energy Efficiency and Renewable Energy (EERE) within the U.S. Department of Energy
  - General Electric
  - Thar Energy
  - Aramco Services Co.
  - Fluor Marine (Navy Nuclear Laboratory)
  - Electric Power Research Institute (EPRI)
- for providing guidance and funding for this research.