
San Pasqual Band of Mission Indians Microgrid Project


Josh Simmons Lead Project Consultant Prosper Sustainably LLC November 16, 2020



San Pasqual General Information


- Reservation was established in 1910
- The Reservation encompasses approximately 3,143 acres
- 280 Tribal members and over 1,400 lineal descendants
- Reservation population is 1,600
- 450 homes on the reservation
- 83 homes have solar





San Pasqual and Wildfire







Power Supply Threats & Impacts

THREATS

- ➢ Severe weather
- ➤ High winds
- > Wildfires
- ➤ Earthquakes
- Localized physical damage to utility distribution systems
- SDG&E system upgrades (planned outages)

IMPACTS

- Inability to Use Facilities
- Lost Productivity & Revenues
- Equipment Damage

Microgrid Project Goals



<u>Resilience</u>: Maintain electric power during outages



Economic: Reduce electricity

costs




Environmental: 100% renewables, reduce emissions

Priority/Critical Electricity Loads

Facility	Emergency Purpose	Critical Electric Loads
Tribal Administration	Red Cross evacuation center; emergency public shelter; tribal command and control; first aid	HVAC, lighting, telecom/IT, food storage, food service
Housing & Security	First response (police); public safety and security monitoring	Telecom/IT, security camera monitoring, lighting
Fire Department	First response (residential fire station); 911 emergency dispatch	Telecom/IT, lighting, overhead door operation
Education Building	Emergency public shelter	HVAC, food storage, food service, lighting
Preschool	Emergency public shelter	HVAC, lighting
Wastewater Treatment Plant	Wastewater treatment for complex	Full load

Proposed Microgrid Components





San Pasqual Tribal Government Complex Microgrid Project CONCEPTUAL DESIGN

Master Meter

Existing/Sub Meter

New Solar PV Site

Existing Solar PV System

BESS Location

LP Genset Location

Point of Interconnection

Underground Cable Run

Building Cable Run

Existing Propane Tank

New Propane Tank



Project Benefits

Offset 108% of grid electricity
 Offset SDG&E electricity costs
 Provide redundant backup power

Project Team

<u>SPBMI</u>

John Flores, Environmental Director

David Martinez, Public Works Director

Desiree Morales, Utilities Manager

Owner's Representatives Josh Simmons Prosper Sustainably

Michael Burr Microgrid Institute

Dustin Jolley Sage Renewables

Design Build Contractor

Ralph Ciarlanti III Green Realities

Vipul Gore Gridscape Solutions

Cassidee Kido Energy Solutions

Code Compliance
EsGil Corporation

Project Status & Accomplishments



Contracted Design Build Contractor

 \checkmark

Completed SDGE applications for 3-phase service and interconnection



Completed design engineering



Construction activities have commenced



Completion of construction in Q1 of 2021 (est.)

Lessons Learned

- Procurement/contracting takes time
- Utility approvals take time
- Opportunities to leverage funding
- Budget changes
- Seek performance guarantees
- Regular, strategic communications
- Go fast by going slow

Thank you

Questions and Comments

Josh Simmons Prosper Sustainably 805.694.8089

jsimmons@prospersustainably.com

